

Draft guidance for the planning of new MRI installations

February 2026

5	Definitions	3
6	Abbreviations	6
7	List of tables	6
8	List of figures	7
9	1 Introduction	8
10	2 Project brief & feasibility (RIBA stages 0-1)	12
11	2.1 Introduction	12
12	2.2 Client team	12
13	2.3 General clinical requirements	13
14	2.4 General space requirements	14
15	2.5 General MR system requirements	16
16	2.6 Project delivery options	21
17	2.7 Summary & checklist	23
18	3 Design (RIBA stages 2-4)	25
19	3.1 Introduction	25
20	3.2 Design team	25
21	3.3 MR suite layout and general design	27
22	3.4 Specific rooms/areas within the MR suite	33
23	3.5 Examples of an MR suite layout	63
24	3.6 Supporting plant and items external to the MR suite	70
25	3.7 Summary & checklist	83
26	4 Build (RIBA stage 5)	88
27	4.1 Introduction	88
28	4.2 Removal of old MR system	90
29	4.3 RF cage	90
30	4.4 Quench pipe	92
31	4.5 Build requirements prior to MR scanner delivery	93
32	4.6 Build requirements prior to ramping up MRI magnet	94
33	4.7 Summary & checklist	96
34	5 Delivery & installation (RIBA stage 5)	97
35	5.1 Introduction	97
36	5.2 MR scanner delivery	98

37	5.3	MR scanner installation.....	99
38	5.4	Ancillary equipment installation	100
39	5.5	Summary & checklist.....	100
40	6	Acceptance (RIBA stage 6).....	102
41	6.1	Introduction	102
42	6.2	Non-imaging acceptance test checks	102
43	7	Use (RIBA stage 7).....	105
44	7.1	Introduction	105
45	7.2	Policies and procedures	105
46	7.3	Preventative maintenance.....	105
47	7.4	Changes within the MR suite.....	108
48	7.5	Changes outside of the MR suite.....	108
49	7.6	Adverse incident reporting.....	109
50	7.7	Replacement/decommissioning.....	109
51	7.8	Summary & checklist.....	110
52	8	Examples.....	111
53	8.1	Example 1.....	111
54	8.2	Example 2.....	119
55	9	References.....	123
56			
57			
58			
59			


DRAFT

Definitions

Term	Definition	Source of definition
B₀ Hazard Area	The space around the MR EQUIPMENT where the static magnetic field can cause HARM	IEC 60601-2-33
MR Conditional	An item with demonstrated safety in the MR Environment within defined conditions including conditions for the static magnetic field, the time-varying gradient magnetic fields, and the radiofrequency fields.	ASTM F2503-23
MR Controlled Access Area	A locally defined area of such a size to contain the MR Environment . Access shall be restricted and suitable warning signs should be displayed at all entrances.	MHRA 2021
MR Environment	The three-dimensional volume surrounding the MR magnet that contains both the Special Environment (Faraday shielded volume) and the B₀ Hazard Area (space around the MR equipment where the static magnetic field can cause harm). This volume is the region in which an item might pose a hazard from exposure to the electromagnetic fields produced by the MR equipment and accessories, and for which access control is part of the risk mitigation. Adapted from IEC 60601-2-33	ASTM F2503-23
MR Installer	The organisation that is responsible for the installation of the MR system. This may be the MR Manufacturer, but in some cases the installation may be subcontracted to separate teams or the MR system may be purchased from another supplier.	This guidance
MR Projectile Zone	A locally defined volume containing the full extent of the 3 mT magnetic field contour, or other appropriate measure, around the MR scanner.	MHRA 2021
MR Responsible Organisation	The organisation that is responsible for the use and maintenance of the MR system, e.g. hospital. Adapted here from the more general definition of a Responsible Organisation in IEC 60601-1, “The entity accountable	IEC 60601-1

	for the use and maintenance of a Medical Electrical Equipment or Medical Electrical System.”	
MR Responsible Person	<p>An individual within the MR Responsible Organisation to whom day to day responsibility for MR Safety is assigned.</p> <p>“It is recommended that the chief executive or the general manager delegate the day-to-day responsibility for MR Safety to a specified MR Responsible Person who might most effectively be the clinical director, head of the department, clinical scientist, medical physicist or MR superintendent radiographer of the institution where the equipment is located.”</p>	MHRA 2021
MR Safe	An item that poses no known hazards resulting from exposure to any MR Environment . MR Safe items are composed of materials that are electrically nonconductive, nonmetallic, and nonmagnetic.	ASTM F2503-23
MR Safety Expert	<p>A general description of the role of the MR Safety Expert is provided in the JMRI consensus publication.</p> <p>The MHRA highlight the MR Safety Expert should be a designated professional with adequate training, knowledge and experience of MRI equipment, its uses and associated requirements.</p>	JMRI consensus statement, doi: 10.1002/jmri.25282
MR Unlabelled	An item with no MR Safety labelling	MHRA 2021
MR Unsafe	An item which poses unacceptable risks to the patient, medical staff, or other persons within the MR Environment .	ASTM F2503-23
Special Environment	Electromagnetic environment with electromagnetic characteristics different from those specified in this collateral standard in Table 2 through Table 9 or that requires EMISSIONS limits, IMMUNITY TEST LEVELS or test methods that are different from those specified for the professional healthcare facility environment and the HOME HEALTHCARE ENVIRONMENT	IEC 60601-1-2

64 Figure 1 illustrates the different defined MRI safety zones around an MR scanner. The [MR Projectile](#)
 65 [Zone](#), is the zone closest to the MR scanner that is associated with the attraction of ferromagnetic
 66 objects, potentially forming projectiles. Further out, is the [B₀ Hazard Area](#), associated with
 67 unintentional reprogramming of active implantable medical devices. The [Special Environment](#)
 68 (Faraday shielded volume) is defined by the RF cage and is associated with risks from RF emissions
 69 from the MR scanner inadvertently impacting on other electrical equipment. The [MR Environment](#)
 70 encompasses any risks associated with the MR scanner and is a combination of the [B₀ Hazard Area](#)
 71 and the [Special Environment](#) (Faraday shielded volume). For examples, such as above, where the [B₀](#)
 72 [Hazard Area](#) spills out into an adjacent room, the [MR Environment](#) is generally the combination of
 73 the MR Examination room and the controlled areas of the adjacent room. If the [B₀ Hazard Area](#) is
 74 contained within the MR Examination room, then the extent of the [MR Environment](#) can just be the
 75 extent of the MR Examination room. Finally, the [MR Controlled Access Area](#), is the area the
 76 encompasses the [MR Environment](#) where access to the [MR Environment](#) is controlled.
 77
 78



79
 80
 81 *Figure 1. A example plan of an MR suite showing the different defined MRI safety zones around the MR scanner; the [MR](#)*
 82 *[Projectile Zone](#), (purple), the [B₀ Hazard Area](#) (green), the [Special Environment](#) (blue), the [MR Environment](#) (orange) and the*
 83 *[MR Controlled Access Area](#) (red).*

84
 85
 86

87 **Abbreviations**

88

89	HBN	Health Building Note
90	HSE	Health & Safety Executive
91	HTM	Health Technical Memorandum
92	NHSE	National Health Service England
93	RIBA	Royal Institute of British Architects

97 **List of tables**

98 Table 1. Key individuals and groups specific to new MRI installations that should be considered for
99 the client team. 13


100 Table 2. Key individuals/groups in the context of MRI that should be considered as part of the design
101 team for new MRI installations. 26

102 Table 3. Example activities associated with the build phase of a new MRI installation project. 89

103 Table 4. Examples activities associated with delivery and installation phase. 98

104 Table 5. List of non-imaging acceptance test checks relevant to a typical MRI installation. 104

105



106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156

List of figures

Figure 1. A example plan of an MR suite showing the different defined MRI safety zones around the MR scanner; the MR Projectile Zone, (purple), the B ₀ Hazard Area (green), the Special Environment (blue), the MR Environment (orange) and the MR Controlled Access Area (red).....	5
Figure 2. Mapping of typical governance stages and MRI installation project phases to the RIBA plan of work stages.	10
Figure 3. Magnetic field isocontours overlaid on plans of a 1.5 T MR suite. In this example, if the B ₀ Hazard Area is defined by the 0.5 mT threshold then magnetic shielding in both side walls/access control is required for the areas where the 0.5 mT fringe field (blue) protrudes slightly from the MR Examination room. This is not required if the B ₀ Hazard Area is defined by the 0.9 mT threshold (purple). Both fringe fields extend into the MR Technical room at the back of the MR scanner which therefore requires access control in either case.	16
Figure 4. Main differences between traditional, design & build and turnkey procurement solutions	22
Figure 5. Example MRI functional workflow diagram for the flow of patients within the MR suite. After the MRI examination, patients may spend some time within a recovery area before returning to the patient changing (out-patients) or patient transfer area.	28
Figure 6. Example layout of an MR suite (reproduced from the MHRA guidelines with permission), showing both the MR Controlled Access Area and the MR Environment, as well as the ACR MR Safety zones.	29
Figure 7. MR Controlled Access Area signage from the IPEM MRI warning signage templates.....	30
Figure 8. Two example layouts for fire compartmentalisation.	31
Figure 9. Example of wooden frame providing electrical isolation between honeycomb waveguides in the RF cage and external air ducting.	46
Figure 10. IPEM door and floor warning signs (IPEM 2017) and an example of both in practice, additionally demonstrating a second copy of signage on the inside of the door to maintain a visible warning sign when the door is open	47
Figure 11. Example of artificial skylight designed for use in the MR Examination room that may be considered to improve the patient experience of an MRI scan.	53
Figure 12. Example of change in floor colour to demarcate the MR Projectile Zone close to the MR scanner and a tethered anaesthetic machine	54
Figure 13. Example of anchor point in wall providing scope for non-ferromagnetic chain to tether an MR Conditional anaesthetic machine to avoid it being taking closer to the MR scanner than intended.	55
Figure 14. Oxygen monitor (top) and magnet emergency run-down unit (ERDU) (bottom)	59
Figure 15. Heating, ventilation, and air conditioning (HVAC) mimic panel, providing information on the chilled water entering the facility, magnet and control room temperature and relative humidity. The oxygen sensor alarm and emergency extract fan status are shown as is the chiller status.	59
Figure 16. Example of IPEM signage for the labelling of various MR Safety related items.	60
Figure 17. Examples of quench pipe outlet designs.	71
Figure 18. MRI quench pipe outlet warning signage from IPEM MRI safety notices.	73
Figure 19. Example of MRI supporting plant. The air handling unit is highlighted by the yellow dotted box. Also shown is the condenser unit for the MR Examination room air conditioning and the MR chiller system that provides chilled water to the MR system heat exchanger located in the equipment room. The red dotted line partially shows the magnet access. This wall is demolished for installation/removal of the magnet.	77
Figure 20. Example RF cabin results, showing the shielding effectiveness at 30 MHz, 63 MHz and 128 MHz, demonstrating all results were greater than 100 dB.	90
Figure 21. Loose cables trailing on the suspended ceiling within the RF cage are known to be a source of RF spikes and should be avoided by use of secure cable trays and mounting brackets.	92

157 1 Introduction

158 This guidance provides support for the planning, installation, acceptance and subsequent use of new
159 clinical MRI installations. It has been drafted with a UK focus, but it is anticipated that many aspects
160 of this guidance may be relevant more generally to new clinical MRI installations. This work links in
161 with the MHRA guidelines for MR Safety ([MHRA 2021](#)), the primary authority for MR Safety guidance
162 in the UK, as well as more general MHRA guidance on the management of medical devices ([MHRA
163 2021a](#)). These guidelines have been developed in parallel with the forthcoming update of the NHS
164 Health Building Note 06-01 ([HBN 06-01](#)) that provides more general guidance for diagnostic and
165 interventional imaging. Where relevant, reference is made to other HBNs¹ and Health Technical
166 Memoranda (HTMs)². Note, Wales and Scotland publish versions of the HBNs and HTMs applicable
167 to their national health systems. Finally, this guidance incorporates some site planning information
168 provided by individual MR manufacturers.

169
170 The target audience for this guidance are MR staff, hospital estates and facilities professionals,
171 architects, engineers and other professional groups involved with the planning of new MRI
172 installations. This document is written predominantly with the fixed installation of superconducting
173 horizontal bore whole-body MR systems in mind (generally 1.5T or 3T), since these are currently the
174 most common. However, this guidance is expected to be helpful to those planning to install other
175 designs of MR scanner, including mobile scanners, MR systems based on permanent or resistive
176 magnet system designs, and superconducting systems that do not require a helium quench pipe.
177 This guidance aims to make suggestions based on considered best practice, while recognising that
178 in many cases there may be a local need for variations. NHSE also publish a guidance on managing
179 and reporting derogations from HBNs, HTMs and other NHS estates related standards or guidance
180 documents ([NHSE 2023](#)).

181
182 This guidance has been drafted by a multi-professional working group with representation from the
183 following stakeholders.

- 184 • Architects for Health
 - 185 ○ Hal Jones, Floyd Slaski Architects
 - 186 ○ Franko Covington, Building Design Partnership Ltd
- 187 • Association of Anaesthetists
 - 188 ○ Chloe Fairbairns, South Tees Hospitals NHS Foundation Trust
- 189 • Association of Healthcare Technology Providers for Imaging, Radiotherapy and Care
190 (AXREM)
 - 191 ○ Craig Buckley, Siemens Healthineers
 - 192 ○ Terry Heathcote, Siemens Healthineers
 - 193 ○ David Martin, formerly Siemens Healthineers
 - 194 ○ Matthew Clemence, Philips Healthcare
 - 195 ○ Clare Harris, Philips Healthcare
 - 196 ○ Gavin Houston, GE HealthCare
 - 197 ○ Allen Munt, GE HealthCare
 - 198 ○ Chris Wilson, GE HealthCare
 - 199 ○ Huw Shurmer, Fujifilm
 - 200 ○ Megan Newberry, Fujifilm
 - 201 ○ James Davies, Easote
 - 202 ○ John Manchester, Easote
 - 203 ○ Gary Fletcher, McNaughts
- 204 • British Association of Magnetic Resonance Radiographers

¹ A complete list of HBNs is available at <https://www.england.nhs.uk/estates/health-building-notes/>

² A complete list of HTMs is available at <https://www.england.nhs.uk/estates/health-technical-memoranda/>

- 205 ○ Rachel Watt, NHS Grampian
- 206 ● British Institute of Radiology
- 207 ○ Martin Graves, University of Cambridge
- 208 ● Institute of Healthcare Engineering and Estate Management
- 209 ○ Andrew Ward, NHS Wales Shared Services Partnership
- 210 ● Institute of Physics and Engineering in Medicine
- 211 ○ David Price, Guy's & St Thomas' NHS Foundation Trust
- 212 ○ Maria Schmidt, Royal Marsden NHS Foundation Trust
- 213 ○ Cormac McGrath, Belfast Health & Social Care Trust
- 214 ○ Dan Wilson, Leeds Teaching Hospitals
- 215 ○ Siân Curtis, University Hospitals Bristol and Weston NHS Foundation Trust
- 216 ○ Geoff Charles-Edwards, Guy's & St Thomas' NHS Foundation Trust, Royal Marsden NHS Foundation Trust
- 217 ○ Rebecca Quest, Imperial College Healthcare NHS Trust
- 218 ○ Mike Hutton, The Christie NHS Foundation Trust
- 219 ○ Mike Hutton, The Christie NHS Foundation Trust
- 220 ● Medicines and Healthcare products Regulatory Agency (MHRA)
- 221 ○ David Grainger, MHRA
- 222 ● Royal College of Radiologists
- 223 ○ Mark Radon, Walton Centre NHS Foundation Trust
- 224 ● Society and College of Radiographers (SCoR)
- 225 ○ Alex Lipton, Society and College of Radiographers

226
227 Contributions from the following individuals during the preparation of this guidance are gratefully
228 acknowledged.

- 229 ● Niven Smith & Shane Greenwood, Envirotec Ltd
- 230 ● Ilhem Toumi & Jean-Pierre Fronte, ETS-Lindgren
- 231 ● Tobias Gilk, Gilk Radiology Consultants
- 232 ● Gordon McKenzie, Imedco
- 233 ● Michael Steckner, MKS Consulting
- 234 ● Alexandra Guthrie & Sandy Thompson, National Fire Chiefs Council
- 235 ● Abigail Pride & Michael Rope, NHS England
- 236 ● Michael Bernard, Andy White & David Haire, Siemens Healthineers
- 237 ● Yvonne Kinsella, UK Health Security Agency


238
239 In preparing this guidance, the working group invited the wider MRI community to share real-world
240 examples of issues encountered with new MRI installations, particularly those that might have been
241 avoided or reduced with greater awareness and consideration of relevant issues and more informed
242 decision-making. Selected submissions are presented throughout this guidance as short case
243 examples that aim to highlight the relevance of specific recommendations. In several cases, multiple
244 contributors reported the same or similar issues. All contributions are gratefully acknowledged.

245
246 This guidance is structured into various phases, mapping onto the Royal Institute of British Architects
247 (RIBA) work stages ([RIBA 2020](#)) that are widely used in many NHS capital development projects.

- 248 ● **Project brief & feasibility (RIBA stages 0-1).** This covers initial work to consider what is
249 required, the feasibility of different options, typically leading to the development of a
250 strategic outline case (SOC).
- 251 ● **Design (RIBA stages 2-4).** This covers the full design of the MRI installation.
- 252 ● **Build (RIBA stage 5).** This section covers the building works for a new MRI installation.
- 253 ● **Installation (RIBA stage 5).** This section is concerned with the installation of the MRI
254 equipment itself.

- 255 • **Acceptance (RIBA stage 6).** This phase covers the checks performed on behalf of the
256 purchaser that ultimately lead to formal acceptance and handover of the MRI installation.
- 257 • **Use (RIBA stage 7).** This phase highlights issues relating to the use of the MRI installation.

258
259 The governance of NHS capital development projects often starts with the production of a strategic
260 outline case (SOC), which if approved progresses to an outline business case (OBC) and ultimately a
261 full business case (FBC), capturing the project's design with regards to financial, management and
262 operational aspects. Figure 2 shows how these governance stages often map to the phases in this
263 guidance and in turn onto the RIBA work stages. Importantly, this alignment to the RIBA work
264 stages is indicative and this may vary for individual projects. For example, a SOC might include RIBA
265 Stage 2 Concept Design due to project-specific characteristics. Typically, construction will not start
266 until approval of the Full Business Case (FBC) which normally precedes the release of funding for
267 work to commence. Additionally, the order for the MR system is typically placed after the FBC is
268 approved. Project teams therefore need to plan for a period of design coordination at the start of
269 RIBA Stage 5, when the MRI suppliers are fully engaged and ready to prepare their final drawings.
270 However, earlier coordination can help to lower the risks. A period of final coordination with the MR
271 supplier may also be covered prior to Stage 5 via a Pre Contract Services Agreement (PCSA).
272 Completing the design and coordination with the MR supplier will enable the Principal Contractor to
273 finalise the proposed contract sum and construction programme.
274



275
276 *Figure 2. Mapping of typical governance stages and MRI installation project phases to the RIBA plan of work stages.*

277
278 For building projects that fall within the Building Safety Act definition of Higher Risk Building (HRB),
279 the RIBA Stage 4 design proposals must be fully coordinated with the MR supplier's proposals prior
280 to making the building regulations application (Gateway 2). RIBA Stage 5 Construction work must not
281 start until approval from the Building Safety Regulator is granted. An RIBA Stage 4 PCSA period or
282 equivalent would be appropriate for an HRB process. During the PCSA all specialist design

283 subconsultants, that are relevant to building regulations compliance, such as mechanical and
284 electrical subcontractors, RF cage designers, fire stopping specialists, etc need to be appointed to
285 ensure a fully coordinated and demonstrably compliant design.

286

287 This guidance does not aim to provide detailed recommendations on procurement, although a few
288 general points are included here as initial suggestions. Although there are national procurement
289 schemes, different organisations may have individual approaches to tendering and procurement of
290 new equipment. Consequently, it is important to engage with procurement colleagues within the
291 local organisation early on in a new MRI installation project to seek guidance on the local processes
292 and options available. The following national bodies that provide further advice.

- 293 • England: NHS Supply Chain: for contractual and purchasing procedures. MR scanners and
294 associated option and related services, [https://www.supplychain.nhs.uk/product-](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/)
295 [information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/)
296 [option-and-related-services/](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/)
- 297 • Scotland: contact Scottish Healthcare Supplies
- 298 • Wales: contact Welsh Health Supplies for procurement matters and Welsh Health Estates for
299 Technical and Estates related issues. [https://nwssp.nhs.wales/ourservices/specialist-estates-](https://nwssp.nhs.wales/ourservices/specialist-estates-services/our-services/diagnostics-and-therapies/)
300 [services/our-services/diagnostics-and-therapies/](https://nwssp.nhs.wales/ourservices/specialist-estates-services/our-services/diagnostics-and-therapies/)
- 301 • Northern Ireland: contact the Department of Health, Social Services and Public Safety
302 (DHSSPS)

303

304 Additionally, the MHRA's guidelines for the management of medical devices ([MHRA 2021a](#)) provide
305 some recommendations on appropriate acquisition and selection. Importantly, while resources such
306 as the NHS supply chain can provide a helpful overview of available MR systems ([NHS Supply Chain](#)
307 [2025](#)) this information may not be complete/up-to-date and confirmation from the MRI
308 manufacturers is recommended. Many new MRI products are announced at the Radiological Society
309 of North America (RSNA) annual meeting that historically has occurred at the end of November each
310 year, although some options may not be immediately available to purchase. Additionally, new MRI
311 products have been announced at other scientific meetings such as the European Congress of
312 Radiology (ECR) and the International Society of Magnetic Resonance in Medicine (ISMRM).

313

314 The range of options for an individual MR system can be very broad, particularly for software-based
315 options, and additional complexity may arise where MRI manufacturers group certain options
316 together. To help provide clarity on what is included in any tender offer it is recommended to
317 request a corresponding list of items that are **not** included in any offer.

318

Real-world example: misunderstanding over what was included in tender

It was misunderstood by MR staff that the list of options purchased with an MR system included one for extended table movement that was required to support a need for whole-body MRI scanning. This was not identified until after the MR system was installed.

Impact: The MR system was unable to provide whole-body MRI examinations until the MR system was replaced 15 years later.

319


320 Where possible, it is strongly recommended to visit sites who already have been working with the
321 MR system under consideration, to discuss their experiences. Typically, MRI manufacturers are able
322 to help with organising such visits.

323

324 Often, a small proportion of the total cost of the MR system is held back until the system is
325 accepted. Consequently, it is important to identify what the acceptance criteria should be and to
326 specify these as part of any invitation to tender.

327 **2 Project brief & feasibility (RIBA stages 0-1)**

328



329
330

331 **2.1 Introduction**

332 This section highlights aspects of MRI site planning that are recommended as part of developing the
333 project brief and assessing the feasibility of location options for a new installation. These steps are
334 performed prior to the formal design phase.

335

336 At the end of this phase of the project there should be enough information to allow a high-level
337 comparison of advantages and disadvantages of different options, including basic costings, that can
338 be used to produce a strategic outline case (SOC).

339

340 **2.2 Client team**

341 The client team are responsible for compiling the project brief that is required to inform the design
342 (RIBA 2020). They are also key to each subsequent stage in the project, providing clarifications and
343 oversight to help ensure the project meets their vision as much as possible. Some members of the
344 client team may additionally contribute to, or be part of, the design team. Table 1 highlights several
345 individuals and groups that are important to consider involving within the client team for new MRI
346 installations. [HBN 00-01](#), that provides general design guidance for healthcare buildings, highlights
347 the importance of patient and public involvement in strategic planning. This is echoed by patient
348 bodies such as the Patients Association, who encourage involvement of patients and carers in the
349 design of local diagnostic services ([Patients Association, 2024](#)).

350

351

Key individuals/groups	Key roles and responsibilities in this project phase
MR service manager	To help define the clinical need and workload and to ensure that the facility can support all required processes. Share existing MR department management policy documents with the project team.
MR Clinician	To support definition of the clinical needs for the project. It is expected the clinical specialty will match the MRI service, i.e. a radiologist for a radiology-led MRI service, a cardiologist for a cardiology service
Supporting clinical services where relevant (e.g. anaesthetics)	To help provide high level requirements with regards supporting clinical services
MR Responsible Person	To ensure appropriate MR Safety within the project brief
MR Safety Expert	To provide technical expertise to ensure appropriate MR Safety within the project brief.
MR physicist	To provide technical expertise to support more general physics aspects for defining the project brief.
IT personnel	To ensure any new facility meets the need of the users in communication, data management and security, access to PACS and other relevant systems. Their involvement may be more substantial in the design phase, but it may be helpful for them to be involved earlier to help identify potential issues.

MR manufacturers	Although the formal tender process may not start until the end of the design phase once the full business case (FBC) has been approved, MRI manufacturers will often be able to provide valuable support at this phase of a project and their engagement is recommended as early as possible. A pre contract services agreement (PCSA) may be considered if required.
Hospital Estates	High level overview on location options and risks, e.g. power supply, structural information, long-term site plan, etc. Additionally, provision of 'golden thread' building information to the project team to satisfy Building Safety Act, e.g. power supply, water supply, structural information, fire safety information etc.
Design Team – including statutory Principal Designer duty holder roles.	High level overview on design options and risks, e.g. overall area available for MR Controlled Access Area , structural slab to slab height and loadings, MRI access for install and replacement, quench pipe route, MEP infrastructure and plant space, adjacent areas that may affect or be affected by the magnet, broader building context issues – patient flows, fire safety, construction access etc. Identify all designer appointments, their scopes of work and establish the designer's responsibility matrix.
Healthcare planner	Sites may consider utilising the services of a Healthcare Planner to help lead the development of stakeholder consensus and overseeing its synthesis throughout the design and planning process. Support from a healthcare planner may be more relevant for larger developments where capacity planning and clinical flow assessment is required.

352
353 *Table 1. Key individuals and groups specific to new MRI installations that should be considered for the client team.*

354
355

356 2.3 General clinical requirements

357 Clearly defining the general aims and requirements of a new MRI installation is a crucial first step to
 358 enable identification and comparison of feasible options. A key component of this is to define the
 359 different patient cohorts and MRI services that are to be accommodated. The requirements for an
 360 MRI installation aiming to provide basic MR imaging services for ambulatory out-patients may be
 361 quite different from one designed for in-patients. A key decision here is whether to include provision
 362 for anaesthetic cases at some point during the expected lifetime of the MR system, since
 363 modifications to an operational MR suite to introduce the capability for anaesthetic cases may be
 364 more limited, costly and disruptive. Another key decision is the potential need to support paediatric
 365 patients as well as specialised procedures such as MRI for radiotherapy planning, intraoperative and
 366 interventional MRI services. An MR system aimed at performing only head MRI scans may not
 367 require the full scope of patient table movement through the scanner, which subsequently may
 368 allow for compromises in the size of the MR Examination room.

369
 370 Defining the expected patient cohorts also helps with the additional step of identifying any
 371 additional stakeholders to provide high-level advice regarding clinical requirements for this stage of
 372 the project. Nursing or anaesthetic teams may accompany in-patients; other patients may be
 373 accompanied by carers or hospital staff, translators and religious/cultural chaperones, all of which

374 may require additional space. Paediatric patients, general anaesthetic procedures, mental health
375 patients, prisoners, and advanced procedures which include extra ancillary equipment such as
376 radiation therapy treatment planning or MR guided focussed ultrasound will all have different
377 requirements. [HBN 06-01](#) provides general guidance regarding the pathway for different patient
378 groups, as well as functional relationships, workflows and logistics for the planning of new MR suite.
379

380 The general clinical requirements should consider the overall workload, since this can impact on
381 general space requirements in addition to more specific aspects in the design phase. Additionally,
382 consideration should be given to the potential for future expansion of services to be undertaken.
383 Finally, operational continuity and the level of resilience should be defined, since this will impact the
384 design, particularly regarding engineering specifications.
385
386

387 2.4 General space requirements

388 MRI installation projects generally fall into one of the following types

- 389 • Replacement of an existing MR scanner with no, or minimal, changes to the building,
- 390 • Installation of a new MR scanner into a re-purposed existing building. This may include
391 expansion of an existing MR suite.
- 392 • Installation of a new MR scanner in a new purpose-designed building.

393 The space requirements for each of these may vary significantly. Additionally, an independent
394 department is likely to require a larger footprint than an MR suite within a larger imaging
395 department where facilities such as reception and waiting areas can be shared.
396

397 Although MR manufacturers provide specifications regarding minimum space requirements for a
398 particular MR system, this may be focussed on the minimum to accommodate the equipment
399 without consideration of how the system is to be used. Designing solely to manufacturer minimum
400 specifications, without reference to clinical workflows and patient cohorts, is likely to result in
401 operational constraints, reduced throughput, compromised patient experience, and the need for
402 costly retrospective modifications once the MRI service becomes operational. It is important that the
403 overall space requirements for an MRI installation are defined by the overall clinical need. Ignoring
404 this and simply designing to an MR manufacturer's minimum specifications can have serious
405 negative implications for when the MR suite becomes operational, again highlighting the importance
406 of defining the expected patient cohorts and workflows as the first step in any new MRI installation.
407

408 [HBN 06-01](#) provides general guidance on space requirements for MR installations, including the
409 following.


- 410 • Patient access: Patients may not be ambulant, may require transfer to an [MR Conditional](#)
411 wheelchair or bed. In-patients may need to be transported in a bed, and thus require wider
412 corridors, turning points and a location for the transfer to an MR-Safe/Conditional trolley.
- 413 • Patient Facilities: Space for private conversations when screening patients is essential;
414 activities requiring private space also include giving consent to procedures (clinical and
415 research) and counselling. Furthermore, patients require changing facilities, lockers to store
416 their belongings, access to a toilet and drinking water. Separate areas for paediatric patients
417 are desirable, and all patients require privacy. Some patients will be accompanied by
418 chaperones, guardians, carers, and translators. Poorly designed or under-dimensioned
419 waiting areas may limit the patient throughput.
- 420 • Examinations under General Anaesthetic or sedation: space required for equipment,
421 personnel, and activities such as patient preparation and recovery. A separate space for
422 paediatric procedures is desirable. GA personnel take up space either in the control room or
423 MR Examination room during examinations.

- 424 • Clinical Procedures: Space is required for cannulation of patients prior to the examination
425 and recovery from invasive procedures (MR-guided biopsies and others). Staff require
426 handwashing facilities in the vicinity of those activities. First aid, addressing allergic reactions
427 and adverse events, resuscitation and other clinical interventions require a dedicated private
428 space and equipment that must be stored in the vicinity. Some clinical procedures require
429 bowel and bladder preparation, and are only viable if a toilet is available very close to the
430 MR scanner.
- 431 • Storage: Auxiliary equipment such as an [MR Conditional](#) bed and wheelchair, trolleys and
432 stepladders must be available to the MR Unit. Other specialist activities require equipment
433 to be stored: MR-guided focussed ultrasound, Radiotherapy planning accessories, MR-
434 guided biopsies, etc. GA equipment needs storing when not in use, and some equipment
435 needs charging (e.g. injectors). Although equipment does not need to be stored within the
436 [MR Controlled Access Area](#), there are many advantages in having dedicated equipment in
437 MRI, as the workload in checking whether they are [MR Safe](#) /[MR Conditional](#) is significant.
- 438 • Administration: Administrative tasks require a separate space and a degree of privacy.
439 Administrative personnel make direct contact to the general public and may need to
440 enter/leave the [MR Controlled Access Area](#) frequently.
- 441 • Staff Facilities: MR Staff require changing facilities and storage space for their belongings.
442 MR staff need access to rest areas for breaks.

443 These are discussed further in the design section of this guidance.
444

445 A more specific space-related decision for the local site to consider at the start of the project is what
446 static magnetic field threshold will be used in the project for controlling access to the high magnetic
447 fields around the MR scanner to protecting against inadvertently changing the function of
448 pacemakers and some other implantable medical devices, an area now defined as the [B₀ Hazard](#)
449 [Area](#). Historically, this threshold has been 0.5 mT, with the primary reference for this being the
450 international standard IEC 60601-2-33. However, a recent update to this standard (published in the
451 UK as BS EN IEC 60601-2-33 (2024)) increases this threshold to 0.9 mT. The main benefits of this
452 change are increased flexibility for the installation of MR systems into limited spaces with potentially
453 significant cost savings as demonstrated by Figure 3 (reproduced from [Steckner et al. 2024](#)).
454 However, although the new 0.9 mT limit has been recognised in the recently updated [ACR manual](#)
455 [on MR Safety](#), at the time of writing (Feb 2026) the MHRA guidelines have not yet been updated to
456 reflect changes in BS EN IEC 60601-2-33 (2024). Where a threshold above 0.5 mT is adopted, the [MR](#)
457 [Responsible Organisation](#) should explicitly document this decision, including the clinical and safety
458 rationale, stakeholder agreement, and any additional risk mitigations. Particular consideration
459 should be given to the presence of patients, staff, or visitors with implantable medical devices, and
460 to alignment with current national guidance. This decision should be reviewed if national guidance is
461 updated.
462
463

464
465



466
467

468 *Figure 3. Magnetic field isocontours overlaid on plans of a 1.5 T MR suite. In this example, if the [B₀ Hazard Area](#) is defined*
469 *by the 0.5 mT threshold then magnetic shielding in both side walls/access control is required for the areas where the 0.5 mT*
470 *fringe field (blue) protrudes slightly from the MR Examination room. This is not required if the [B₀ Hazard Area](#) is defined by*
471 *the 0.9 mT threshold (pink). Both fringe fields extend into the MR Technical room at the back of the MR scanner which*
472 *therefore requires access control in either case.*

473
474
475

476 2.5 General MR system requirements

477 Once the general clinical aims for a new MRI installation have been established, it is necessary to
478 consider some general requirements for MR systems to help rule out unsuitable location options
479 early in the project. MR manufacturers provide lists of requirements as part of their site planning
480 guide (sometimes known as a preinstallation manual) for specific MR scanner models. These site
481 planning guides are generally accessible and the client team are encouraged to seek copies from MR
482 manufacturers that are likely to be of interest. Additionally, involvement of representation from the
483 MR manufacturers at this stage in the project can be helpful to provide general guidance when
484 exploring location options for a new MR installation.

485

486 It is in the interest of the users for a site to be as compliant as possible with the site planning guide
487 for the selected MR system to enable the manufacturer to meet their own performance
488 specifications for the MR scanner. Since selection of the MR system will typically occur later in the
489 project, it may be helpful to consult site planning guides for a number of potential MR systems and
490 to apply additional margins to stated specifications to cover the uncertainty of the selected MR
491 system as well as provide flexibility for a future upgrade/replacement.

492

493 Proximity of MR scanner to neighbouring equipment and moving metal objects

494 The MR scanner can be adversely affected by nearby equipment and large moving objects, resulting
495 in impaired image quality. One example is the presence of a neighbouring MR scanner. Site planning
496 guides list minimum distances between the isocentres of two scanners to avoid each impacting on

497 the other in terms of the magnetic field homogeneity. Typically, these distances depend on the
498 orientation of the magnetic field in relation to each other. Installing scanners closer than the
499 recommended minimum separation distance may add cost and downtime during installation (and at
500 other stages such as during remedial work and replacement) as they may require simultaneous
501 magnetic field shimming.

502
503 The MR manufacturers site planning guides typically included recommendations regarding minimum
504 distances between the location of an MR scanner and large moving objects such as lifts, differently
505 sized motor vehicles, trains and linear accelerator gantries, based upon their estimated mass.
506 Additionally, electrical current in high voltage power lines, transformers, switches, motors, or
507 generators near the magnet may also affect the MRI magnetic field homogeneity. Site planning
508 guides provide further details, often specifying a threshold for permitted current or distance of the
509 equipment from isocentre. These thresholds may vary with the electrical current AC frequency.

510
511 The introduction of passive magnetic shielding (typically high permeability steel) can help to reduce
512 these requirements slightly, although these are considered less effective for low frequency
513 variations. However, active compensation systems are available which report an ability to reduce
514 low frequency environmental magnetic field variations by two orders of magnitude. It is important
515 to recognise the limits to which passive and active magnetic shielding can help support a non-ideal
516 location for an MR system.

517
518 Since the usage of plant rooms change over time, often with the installation of new equipment at
519 higher power rates, additional margins should be considered to avoid potential issues in the future.
520 In case of doubt on the suitability of a particular site for an MRI installation, it is possible to perform
521 a B_0 test and measure the temporal magnetic field fluctuations at a particular proposed isocentre
522 position, across a range of frequencies. This requires specialist equipment and is time consuming
523 and expensive. Therefore, it is only viable to proceed with B_0 tests for a few selected sites which
524 have been pre-screened and appear to be suitable. The B_0 test in itself relates to field fluctuations
525 during the period of time that the measurement takes place. Consequently, it is important to ensure
526 that the measurement made during a period of representative use of the building. If required, there
527 are options for magnetic shielding to limit the effects of these external magnetic field fluctuations on
528 the MR scanner.

529
530 Additionally, the fringe static magnetic field from the MR scanner may adversely impact other
531 equipment in the immediate vicinity to the [MR Controlled Access Area](#). In a hospital setting,
532 equipment that may be particularly sensitive to the fringe magnetic fields include gamma cameras,
533 PET scanners, CT scanners, X-ray analogue image intensifiers and linear accelerators. Maximum
534 permissible magnetic flux density (mT) levels for various pieces of equipment are often included in
535 the MRI manufacturers site planning guides, although it is recommended to consult the
536 manufacturers of the neighbouring equipment for requirements more specific to the item of
537 equipment.

538
539 It is possible to use passive magnetic shielding to limit the extent of the magnet fringe fields outside
540 of the MR Examination room. In addition to cost implications, passive magnetic shielding is also
541 heavy, and may take up some MR Examination room space; it must be planned at early stages, as
542 part of the building structure. The amount of shielding required is calculated by vector field
543 simulation of the magnetic field. This is performed by MRI manufacturers or specialist companies.
544 Additionally, MR manufacturers typically specify minimum distances between any shielding and the
545 MR scanner.

546

547 MRI manufacturers will have a minimum ceiling height for magnet installation to allow access to the
548 top of the magnet. There must also be sufficient space above the false ceiling for the necessary
549 services to be run, particularly ventilation ducting.

550
551

552 [Structural requirements & delivery/removal routes](#)

553 The weight of whole-body MR scanners varies considerably. This has immediate implications for the
554 structural requirements of potential locations, both in terms of the final position of the MR scanner
555 and for delivery/removal routes. Such structural requirements should feed into the planning of new
556 buildings and need to be checked for existing buildings. If magnetic shielding is to be used to limit
557 the extent of the [MR Environment](#) into areas adjacent to the MR Examination room, the weight of
558 this shielding must also be taken into consideration. Structural changes to existing buildings can be
559 considered to support additional loads if required.

560

561 Additionally, MR systems typically have requirements in terms of mechanical vibration. Special
562 vibration absorbing mounts may be required in some cases where levels of vibration may be of
563 concern. It may be advisable to carry out a vibration survey of any proposed sites for a new MRI
564 installation to establish typical levels, and vibration requirements should be considered as part of
565 the design of a new building.

566

567 In addition to supporting the magnet weight, there are restrictions on the ferromagnetic content of
568 slabs and walls close to isocentre described in all site planning guides. A high ferromagnetic content
569 may compromise the field homogeneity, making it impossible to shim the magnetic field to meet the
570 manufacturer's specifications. The ferromagnetic content is not necessarily known in existing
571 buildings, particularly if the buildings are very old. As a result, it may be necessary to drill the slab for
572 samples to be tested. Upgrading and modifying parts of the structure of older existing buildings can
573 be prohibitively expensive, and therefore structural matters must be considered early in the site
574 planning process.

575

576 It is important to consider the delivery route for each potential location of a new MR system at the
577 early stages of the project, as it can have a significant impact on installation costs and in some case
578 may rule out potential locations options. Delivery routes may involve lifting the magnet over existing
579 buildings. There may be a need to reinforcing the floor (temporarily or permanently) along the
580 delivery route to allow the translation of the magnet to its location; deliveries to upper floors and
581 listed buildings require particular attention. The MR manufacturers site planning guide will confirm
582 the minimum clear dimensions required for access. Consequently, it is often preferable for MR
583 Examination rooms to be located with or close to an external wall to aid delivery and future removal
584 of the MR scanner, which also reduces the risk of changes over time that prohibit the same delivery
585 route being used for the future extraction/replacement of the MR scanner. If the new MRI
586 installation project includes construction of the building, then the building fabric should be designed
587 so that the relevant section of external wall or roof can be removed and reinstated for future MRI
588 replacement.

589

590 Consideration of the local site development control plan is important to identify if any proposed
591 locations for new MRI installations are at future risk with regards other proposed projects that may
592 impact on the access route for a future replacement of the MR system. It is also important to
593 maintain an access route throughout the lifetime of the MR system for the replacement of large
594 components of the MR system, e.g. the gradient coil, in the event of failure, and for deliveries of
595 liquid helium that additionally requires consideration of associated legislation such as the Pressure
596 Systems Safety Regulation.

597

Real-world example: Delivery/removal route for MR scanner not maintained

During the lifetime of an MR system, a new building was constructed, blocking the original and only route for MR scanner delivery/removal.

Impact: At additional cost to the institution, the MR scanner was cut up into pieces to allow removal and reutilisation of the space. Associated loss of potential income from resale of magnet.

598

Real-world example: Delivery/removal route for MR scanner not maintained

During the lifetime of an MR system, the original and only route for MR scanner delivery/removal was removed.

Impact: The MR scanner was bricked up and left in situ, with subsequent loss of functional space within the hospital building.

599

Real-world example: Delivery/removal route for MR scanner not maintained

During the lifetime of an MR system, the original and only route for MR scanner delivery/removal was enclosed behind a new facade to the hospital.

Impact: Sections of the facade to the hospital had to be removed at an additional cost of around £70K to enable access/removal/replacement of the MR scanner.

600

601 **Chillers**

602 An MR scanner generally requires a continuous and uninterrupted supply of liquid coolant. This is
603 typically provided by a dedicated chiller. Different parts of the MR system require cooling,
604 depending on the specific design. In general, the most critical item is the compressor head
605 (coldhead) which minimises the helium boil off rate. Interruption of the supply of cold water has
606 serious implications, as it will cause cryogenics to evaporate more quickly, and their replacement is
607 costly. Therefore, the design of the chiller plant is also critical.

608

609 While basic specifications for the chiller are provided by MR manufacturers in their site planning
610 guides, consideration should be made early in the project to the provision of a backup chiller
611 solution based upon how critical the continued operation of the MR scanner is to the institution.
612 Importantly, problems with chillers resulting in downtime of clinical MRI services are one of the
613 most frequently quoted frustrations by MRI users. The design and provision of resilient critical
614 services is a key element to all building engineering services within healthcare as outlined in [HTM 00](#)
615 core standards (Appendix A). Duplicate or shared load designs increase reliability and reduce the
616 probability of clinical disruption. Additionally, they may help with preventative maintenance to the
617 plant equipment with minimal disruption to the clinical service. For some MR systems, a backup
618 chiller is listed as essential in the site planning guide. Notably, at least one of the main MRI
619 manufacturers reports that the majority of new MRI installations now incorporate a backup chiller to
620 minimise the likelihood of MR system downtime.

621

Real-world example: No backup chiller solution

A clinical MR scanner with no backup chilled water solution was down for around 2 weeks when one of the components in the chiller failed and there was a long lead time on sourcing a replacement part, despite the chiller being maintained and serviced by an established contractor. The hospital was also liable for costs of replacing the helium that was lost during this period.

Impact: MR scanner down for 2 weeks

622

623 Temperature and humidity

624 MRI requires control of environmental temperature and humidity for the MR Examination room and
625 equipment room (and sometimes the MR control room), with specifications provided by MR
626 manufacturers in their site planning guides. Therefore, decisions must be made early in the planning
627 process on whether MR will have a dedicated air handling unit (AHU) or whether this provision will
628 be integrated with other facilities within the institution. As part of this, particular consideration
629 should be given to humidification/dehumidification the reliability of solutions for humidity control.
630 Low levels of humidity increase the risk of image quality problems and MR manufacturers may
631 refuse to troubleshoot MR systems if the room humidity is consistently too low. Too high humidity
632 levels impact on patients' ability to thermoregulate during the MRI scan and are therefore a safety
633 issue. [HTM 03-01](#) provides general guidance on ventilation.

634

635

636 Power Supply

637 The power requirements for an MR scanner and supporting plant can be significant compared to
638 other radiological equipment. Consequently, it is important to establish early on the maximum
639 power requirements for potential MR systems and supporting plant, and to confirm whether these
640 can be met at each of the locations being considered for siting the MR system. Where the available
641 power is insufficient to meet the highest requirements, this will need to feed into identification of
642 MR systems that can be supported. Again, consideration should be made for potential future
643 upgrades with increased power requirements, such as higher imaging gradient performance.

644

645 General advice on the power supply requirements for MR systems is provided in [HTM06-01](#),
646 although more up to date information may be provided by the MR manufacturers.

647

648

649 Repurposing an existing RF cage

650 Keeping an existing RF cage may be considered for projects where an MR scanner is to be
651 replaced/upgraded without any structural changes to the MR Examination room layout. In these
652 cases, a measurement of attenuation levels of the RF cage early in the project is important to
653 establish its current performance and whether this is meeting MR manufacturer specifications,
654 although it is recognised that many MR scanners may be operating without problems within RF
655 cages that have a performance that is below the MR manufacturer's original specification ([Small et
656 al. 2026](#)). Where specs are not met, remedial work on the RF cage may help to increase attenuation
657 levels, particularly around the MR Examination room door, which is a common site for a drop in RF
658 performance over time.

659

660 Ultimately, where RF cage performance is below specification, the local site should make an
661 informed, documented cost-benefit decision regarding continued use, informed by MR physics
662 advice and with clear agreement on the acceptance of any residual risk. Specific points to consider
663 include the following.

664

- 665 • The occurrence of external RF interference on MR images from the current MR scanner. MR
666 systems may be able to operate without external RF interference impacting on image quality
667 when the RF cage is below spec. However, this may not be true for all sequences (e.g. EPI-
668 based imaging, spectroscopy, or quantitative techniques), and the risk tolerance may differ
669 between routine clinical imaging and advanced or research applications. In many cases the
670 performance of the RF cage is already below spec when new MRI installations become
operational ([Small et al. 2026](#)).

- 671
- 672
- 673
- 674
- 675
- 676
- 677
- 678
- 679
- 680
- New MR systems may be more sensitive to external RF interference. However, this working group are not aware of any examples where the existing RF cage has been used where the presence of external RF interference started after a new/upgraded system was installed.
 - The replacement of an MR scanner provides an ideal opportunity to replace/work on the RF cage. However, remedial work on the RF cage is possible at any point during the lifetime of an MR system.
 - The MR manufacturer may decline to provide support for any image quality problems associated with external RF interference. However, this may be the case with any MR system where the RF cage is found to be below spec.

681 [MRI quench pipe route](#)

682 At the time of writing, many MR systems require a quench pipe to vent helium gas from the MR
683 scanner to outside of the building, with an appropriate location for the quench pipe outlet (also
684 known as the quench pipe exhaust) to avoid individuals being exposed to the resulting plume of cold
685 helium gas in the event of a magnet quench. The design of the quench pipe is discussed in the design
686 stage of this guidance. However, consideration of potential routes of a quench pipe is advised early
687 in the project to feed into the comparison of sites under consideration. Of note, there are increasing
688 options for superconducting MR systems that operate with very little helium, sometimes described
689 as “dry” MR systems, that do not require an MRI quench pipe.

690

691


692 [2.6 Project delivery options](#)

693 Consideration of project delivery options is recommended at this stage of the project to help with
694 initial cost estimates. Figure 4 highlights the main differences between traditional, design & build
695 and turnkey procurement solutions. The client must be satisfied that the preferred procurement
696 route enables them to adequately plan, manage and monitor the project and to be satisfied of the
697 competencies of all parties engaged in the project, all in accordance with the building regulations,
698 building safety act, CDM regulations and any other applicable regulations. Regardless of
699 procurement route, the Client must appoint the statutory Principal Designer roles, otherwise the
700 Client will retain these responsibilities.


701

702


703



704



705



706

707 *Figure 4. Main differences between traditional, design & build and turnkey procurement solutions*

708

709

710

711

712 **Mobile/relocatable MR scanner to provide cover during replacement MRI projects.**
 713 For replacement MRI projects, planning for the temporary installation of a mobile/relocatable MR
 714 scanner on site can be helpful to maintain some level of MRI service during the building works. In
 715 these cases, consideration should be given to matching the temporary MR scanners (make & model,
 716 RF coils, software options) to either existing or new MR scanners to minimise additional training
 717 needs for staff.
 718

719 2.7 Summary & checklist

720 Considering all aspects of an MRI installation described above, the project team should be able to
 721 produce a shortlist of possible sites for a new MRI installation. These possible sites and the
 722 information gathered about them can now be put forward to MRI manufacturers for a technical
 723 opinion on their viability for a range of their equipment models. Ideally, different opinions would be
 724 gathered and compared. MRI manufacturers may suggest further specific tests to determine the
 725 viability of a given site (B_0 tests, vibration assessment, etc) and these tests should be undertaken
 726 prior to committing to a particular site.
 727

728 After the viability of the possible sites is confirmed, including confirmation of feasible delivery
 729 routes, an initial estimate of the costs of the installation can be produced, and the first version of the
 730 business plan can be completed. Ideally, this will enable the institution to make a final decision on
 731 the chosen installation site. However, it may be desirable to progress further design and
 732 investigation work on more than one option in order to reach a more informed final decision in the
 733 next phase of the project.
 734
 735

Client team	✓
Included key individuals/groups within client team to ensure accurate definition of project brief?	

736
737

General clinical requirements	✓
Defined the different patient cohorts and workflows that are to be accommodated?	
Identified additional stakeholders for aspects of the project design?	
Considered potential future expansion of services to be undertaken.	

738
739

General space requirements	✓
Obtained 'golden thread' building information: power supply, water supply, structural information, fire safety information, etc?	
Defined local magnetic field threshold for B₀ Hazard Area (e.g. 0.5 mT or 0.9 mT)?	

740
741

General MR system requirements	✓
Obtained site planning guides for MR systems of potential interest?	
Checked minimum distances between the isocentres of neighbouring scanners?	
Checked distances between proposed locations and large moving metal objects, e.g. lifts, vehicles?	
Considered B_0 test to be performed to measure the levels of magnetic field fluctuation at proposed MR scanner locations?	

Considered the distance from proposed MR scanner locations to high voltage power lines, transformers, switches, motors, or generators, and the potential need for magnetic field shielding to avoid possible interference on MR system.?	
Considered the potential impact of the fringe static magnetic field from the MR scanner on nearby equipment sensitive to magnetic fields?	
Considered the need for magnetic shielding to limit the extent of the magnet fringe fields outside of the MR Examination room?	
Considered vibration survey of any proposed sites for a new MRI installation to establish typical levels?	
Considered structural limitations of proposed locations?	
Identified a potential delivery route for scanner and servicing (e.g. large component replacement, He supplies) for each proposed location?	
Considered the local site development control plan to identify other proposed projects that may impact on the access route during the lifetime of the MR system or for a future replacement of the scanner?	
Considered high-level options for chiller, including provision of a backup solution?	
Considered high-level options for control of temperature and humidity?	
Confirmed the maximum power requirements for potential MR systems and supporting plant can be met for proposed locations?	
Considered provision of a secondary power supply?	
Considered provision of tertiary power supplies?	
If upgrading existing MR system, considered scope to repurpose the existing RF cage, including RF attenuation measurements to establish current performance?	
Considered high-level options for the route of a potential MRI quench pipe and location of quench pipe outlet?	
Completed high level definition of the MR Controlled Access Area for each proposed location?	
Considered feasibility of each proposed location against defined general clinical requirements and relevant HBNs & HTMs?	

742

743


Project delivery options	✓
Considered project delivery options?	

744

745

746

3 Design (RIBA stages 2-4)



3.1 Introduction

This section describes the design phase of a new MRI installation project, highlighting issues that are particularly relevant to MRI that should be considered to help avoid problems during the subsequent use phase. Particular focus is made towards the following aims.

- Ensuring appropriate safety of anyone in and around the MR suite who may be exposed to the hazards associated with MR scanners.
- Improving patient experience and efficient workflows.
- Minimising MR scanner downtime.

The design section focuses on recommendations for physical design requirements but also focuses on ideal configurations to reduce the probability that a ferromagnetic object could be taken into the MR Examination room. This includes the location of different rooms as well as line of sight to safety critical areas especially from the MR control room.

Where relevant, the reader is signposted to appropriate Health Building Notes (HBNs) and Health Technical Memoranda (HTMs) published by NHS England or their equivalent versions in Wales and Scotland. Consequently, general aspects of design that are not specific to MRI are not covered here except where the context is considered important.

Other sources of information to consider for the design of new MRI installations include the following.

- American College of Radiology (ACR) manual for MRI safety, Appendix 2: MR Facility Safety Design Guidelines ([ACR 2024](#))
- Optimization of MRI Turnaround Times Through the Use of Dockable Tables and Innovative Architectural Design Strategies ([Recht et al. 2019](#))

3.2 Design team

The design team are responsible for the design of the project based upon the requirements set out in the project brief ([RIBA 2020](#)), defined previously in the [Project brief & feasibility](#) phase of the project. Professional groups such as architects, structural engineers, electrical engineers and project managers are inherently part of the design team for building projects in general, although previous experience with MRI installations for individuals in these groups can be helpful to understand the particular requirements of MRI.

Input into the design team from people with specialist knowledge about different aspects of MRI is key to ensure an optimal design and to avoid various pitfalls that can negatively impact work within the space for many years to come. Table 2 highlights some of these key individuals/groups. In certain cases, an individual may cover more than one role, e.g. the superintendent MR radiographer is often the [MR Responsible Person](#). Importantly, clinical staff need to be allocated sufficient time to allow them to fully engage and contribute as part of the design team.

Key individuals/groups	Key roles and responsibilities in this project phase
Superintendent MR Radiographer	Radiographers are perhaps the professional group that will be most associated with working within the MR suite. Appropriate radiographer representation is key to ensure the design meets the clinical needs and supports safe and efficient workflows.
MR Responsible Person	To ensure appropriate MR Safety within the design. The MR Responsible Person is often covered by the Superintendent MR radiographer.
MR Safety Expert	To provide scientific support to the MR Responsible Person and project team on MR Safety aspects of the design. Typically, the MR Safety Expert role is covered by an MR physicist.
MR physicist	Advise on the design and equipment from an MR physics point of view. Provide MR acceptance testing.
Supporting clinical services where relevant (e.g. anaesthetics)	Provide details on requirements for supporting clinical services into the design.
PACS manager, IT personnel	To ensure any new facility meets the need of the users in communication, data management and security, access to PACS and other relevant systems.
MRI manufacturer	Although the formal tender process may not start until the end of the design phase once the full business case (FBC) has been approved, MRI manufacturers will often be able to provide valuable support at this phase of a project and their engagement is recommended as early as possible. A pre-contract services agreement (PCSA) should be considered if required. Some MR manufacturers may also offer formal design services.
RF cage manufacturer	Input into the design regarding options for the RF cage and MR Examination room door. They may also provide advice regarding magnetic shielding if required.
Magnetic shielding experts	Provision of advice regarding magnetic shielding.

791
792
793

Table 2. Key individuals/groups in the context of MRI that should be considered as part of the design team for new MRI installations.

794

795 It is important that the design team includes representation from all the different clinical groups that
796 are intended to use the space, and their approval on the final design should be confirmed prior to
797 the start of the build phase. For example, if the project brief includes scope for MRI under general
798 anaesthesia, it is important to ensure appropriate provision and location of medical gases, suction,
799 anaesthetic machines and that there is sufficient space to safely perform anaesthetic cases.

800

801 Ultimately, the design team should confirm the final design meets the project brief.

802

803

804

805

Real-world example: insufficient consultation and signoff by anaesthetists on the design of new MR suite

Anaesthetists were not fully consulted on the design of a new MRI installation to allow provision of anaesthetic cases resulting in insufficient space for induction/recovery to safely perform anaesthetic cases. There was no appropriate sign-off on the design from the local anaesthetic team.

Impact: No anaesthetic MRI cases were performed during lifetime of the MR system (10 years+).

806
807
808

Real-world example: Multiple examples of issues concerning MR Safety and image quality, all of which were associated with a lack of an [MR Safety Expert](#) in the design team.

- The [MR Controlled Access Area](#) and access controls were not implemented for a relocatable MR suite. When the issue was realised, access controls could not be installed due to the construction of the unit, so an additional door had to be installed at the end of a new link corridor.
- The [MR Controlled Access Area](#) and access controls were not implemented for a new MR suite, with general public access into the area immediately outside the MR Examination room. A stable door was subsequently installed, but access control recognised to still be non-ideal.
- Impact of moving vehicles parking adjacent to scanner was not considered during planning. Bollards to restrict adjacent vehicle access were retrospectively installed.
- Appropriate MR Safety notices not considered.
- Lack of local MR Safety policies and procedures.


Impact: additional cost to the hospital, impaired quality of service, compromised safety and delays to clinical use

809
810
811
812
813
814
815
816
817
818
819
820

3.3 MR suite layout and general design

The layout of the overall MR suite should provide an efficient and patient-friendly experience that enhances patient, staff, visitor and public safety. Figure 5 shows an example functional workflow for patients within the MR suite. Examples of the functional relationship between different rooms and areas provided in the forthcoming [HBN 06-01](#) guidelines, with an example provided for an MR suite supporting both out-patients and in-patient, including scope for anaesthetic cases, and a separate example for an MR suite in a hospital out-patient or community setting, without anaesthetics.

821



822
823

824 *patient transfer may occur inside the MRCAA for some designs.

825
826
827
828

Figure 5. Example MRI functional workflow diagram for the flow of patients within the MR suite. After the MRI examination, patients may spend some time within a recovery area before returning to the patient changing (out-patients) or patient transfer area.

829

830 General design options to make the space more patient-friendly should be considered. This is particularly key if looking to accommodate paediatric patients. Consideration should be given to the use of themes, murals, and natural imagery in the general decoration.

833

834 General MR Safety aspects that should be considered in the design include the following.

835
836
837
838
839
840
841
842

- Ensuring that persons with implanted/attached medical devices and other foreign bodies do not enter the [MR Environment](#) without prior safety checks and authorisation by MR staff.
- Ensuring that any other items whose function could be adversely affected by the strong static magnetic field are either kept out of the [MR Environment](#) or only permitted according to specified conditions.
- Ensuring that systems are in place to minimise the risk of ferromagnetic items being taken into the [MR Environment](#) where they could become projectiles.

843

844 Specific rooms/areas within the MR suite need to be considered are discussed further in subsequent sections.

873 Ideally, all patient and staff entry points to the [MR Controlled Access Area](#) should incorporate self-
874 closing, self-locking doors, although access must be immediately available in the event of a power
875 outage. Each entry to the [MR Controlled Access Area](#) should have warning signs on display. IPEM
876 offer freely available MRI warning signage templates ([IPEM 2017](#)) that include examples for entry
877 points to the [MR Controlled Access Area](#) such as that shown in Figure 7.

878
879



880
881
882 *Figure 7. [MR Controlled Access Area](#) signage from the IPEM MRI warning signage templates.*

883
884 To help with control of access, the number of entry points to the [MR Controlled Access Area](#) should
885 be minimised. Similarly, designs where the [MR Controlled Access Area](#) could be used as a “short-cut”
886 route to non-MRI related locations should be avoided.

887
888 For some MR suites it may be preferable to share areas outside of the [MR Controlled Access Area](#)
889 with other modalities, e.g. shared reception, changing rooms, sub-wait. Ideally all areas within the
890 [MR Controlled Access Area](#) should be dedicated to MRI to avoid MRI safety screening of persons for
891 non-MRI activities and to help with control of access to the [MR Environment](#).

892
Real-world example: design of MR suite did not provide any ability to define an [MR Controlled Access Area](#).

Problems with a lack of a defined [MR Controlled Access Area](#) were not identified until after the build had started. An [MR Safety Expert](#) was not involved in the initial planning of the MR suite.

Impact: delays while stud wall removed, additional steel shielding put in place and stud wall replaced.

893
894
895 **Fire**

896 It is critical to understand that typically the MR Examination room, MR Technical room and MR
897 control room form part of the functional MR system and should be considered as a single fire zone.
898 Consequently, the separating walls, including the RF cage, RF window and RF door, are not intended

899 to provide any fire protection. Furthermore, the use of any fire-stopping material between these
 900 rooms will not have been tested or certified for compatibility with the cables, pipes, fibreoptics, and
 901 other interconnecting parts of the MR system, especially with regards to the potential impact it may
 902 have on them or the RF shielding capability. Consequently, any introduction of such materials would
 903 constitute a modification of the medical device, which can void the product conformity, i.e. it would
 904 no longer be authorised for medical use.

905
906

Real-world example: local decision did not recognise MR Examination room, MR Technical room and MR control room as a single fire zone.

Local decision to incorporate fire-stopping material in the conduits between the MR technical room, MR Examination room, and MR control room.

Impact: this constituted a modification of the medical device that was unauthorised by the MRI manufacturer and impacted the product conformity.

907
908


Two example layouts for fire compartmentalisation are shown below in Figure 8.



 = Fire Rated Construction Enclosing MR Zone

 = Fire Rated Doors

909
910



 = Fire Rated Construction Enclosing MR Zone

 = Fire Rated Doors

911
912
913

Figure 8. Two example layouts for fire compartmentalisation.

914
915 Some MR manufacturers incorporate sensitive smoke detectors within the MR system to
 916 automatically switch off power to certain components of the MR scanner. The installation of a more
 917 general-purpose smoke detector within the MR Examination room requires an appropriate
 918 connection through an RF filter panel, but this is often avoided in practice by incorporating a smoke
 919 detector within the air extract duct, outside of the RF cage.

920
921 How a general fire alarm in the hospital will impact on access control for the [MR Controlled Access](#)
922 [Area](#) should be identified and if required, subsequent mitigations for maintaining access control
923 should be considered.

924
925 It is important that any fire extinguishers that are intended for use within the MR Examination room
926 are non-ferromagnetic. It is encouraged to plan for non-ferromagnetic fire extinguishers throughout
927 the [MR Controlled Access Area](#) or MR suite to mitigate for the possibility that any of them may be
928 used in the event of a fire in the MR Examination room.

929
930 Currently, it is uncommon to install fire sprinkler systems in MR units, although it is recognised that
931 non-ferromagnetic water sprinkler systems intended for use within MR Examination rooms are
932 available. Any installation of a sprinkler system in an MR unit should be a local decision, recognising
933 that if activated, medical device certification requirements would require the affected medical
934 device parts or the whole system to be replaced, at cost to the site. If a local decision is made to
935 install a water sprinkler system, at least one MR manufacturer recommends the design and
936 construction of a water sprinkler system should be made in consultation with the RF cage
937 manufacturer to ensure that any portion of the sprinkler system penetrating the RF cage is dry until
938 activated to avoid negatively impacting upon the RF cage performance.

939
940
941 [Delivery route](#)

942 Consideration of how any existing MR scanner will be removed and a new MR system delivered
943 should be part of the design. MR scanners can vary significantly in weight and physical size (for
944 details check site planning guides), and it is important that the entire proposed delivery route should
945 be validated. Additionally, consideration should be given to maintaining an on-going route for the
946 removal of the MR scanner when it reaches end-of-life, and the delivery of a replacement MR
947 system.

948

949 3.4 Specific rooms/areas within the MR suite

950 The following rooms/areas are described in a rough chronological order of an example out-patient's
951 journey through the MR suite. [HBN 06-01](#) offers more general guidance, including recommendation
952 on room sizes and example room data sheets.

953
954

955 Reception and waiting area

956

957 *Function*

958 Initial arrival point for out-patients. After their attendance is recorded, out-patients will typically
959 wait in this area before being called through to next stage. Patients may be asked to read and
960 complete an MR Safety screening form while in the waiting area, although this is dependent on local
961 practice and it is recognised that some patients may have had an opportunity to do this prior to
962 attendance.

963

964 *Location*

965 The reception and waiting room should be outside the [MR Controlled Access Area](#). It may be an area
966 that is dedicated to MR only or a shared waiting room for multiple modalities. Ideally, it should be
967 adjacent to reception bays/check in areas, toilets and an interview room for MR staff to verify with
968 the patient information given on the screening form. Close proximity to patient changing and
969 preparation areas is also desirable for efficient patient pathway flows.

970

971 *Operational/design considerations*

972 The reception may be multi-service / multi-modality or dedicated to MRI only. There should be
973 sufficient space to accommodate the expected number of patients. It may need to support in-
974 patients as well as out-patients. Additionally, it may need to support paediatric patients.

975

976 Further considerations associated with the sub-waiting area will be relevant here if a separate sub-
977 waiting area is not included in the design.

978

979

980 Pre-change preparation area

981 *Function*

982 To support certain patients, particularly paediatrics, by providing tools such as a toy/mock MR
983 scanner to simulate the MRI examination and increase the patient's familiarity with the MRI
984 experience. This can be particularly helpful for increasing patient cooperation during the MRI exam,
985 which can be important for optimum image quality. In some cases, this can avoid the need for
986 general anesthesia. A number of publications have highlighted the impact of play simulation in
987 increasing the proportion of paediatric patients who are able to undergo MRI without general
988 anaesthesia ([Carter et al. 2010](#), [Heales & Lloyd 2022](#), [Anwar et al. 2022](#)). One example of toy MR
989 scanner, was reported to save a hospital £150,000 in sedation and care costs ([BBC 2025](#)).

990 Additionally, virtual reality experiences that simulate the patient journey in MRI have also proven
991 very useful in a paediatric setting ([Stunden et al. 2021](#)). This area may also function as the waiting
992 area for paediatric patients.

993

994 *Location*

995 Generally, outside of the [MR Controlled Access Area](#).

996

997 *Operational/design considerations*

998 Accommodate space for a play specialist, as well as space for the patient's parents/carers.

999

1000 Patient screening areas / interview room

1001 *Function*

1002 A private area/room for MR staff to discuss/confirm with patients, the information declared on the
1003 patient screening form or to follow up on information. This personal information may be of a
1004 sensitive nature, and so an area that provides appropriate auditory and visual privacy is important to
1005 help encourage full disclosure any implants and other potential issues that may impact on the safety
1006 and quality of the MRI scan.

1007

1008 *Location*

1009 This should ideally be outside the [MR Controlled Access Area](#), between the reception/initial waiting
1010 area and the patient changing area.

1011

1012 *Operational/design considerations*

1013 Consideration should be given to supporting electronic patient screening, e.g. availability of power
1014 and IT connections.

1015

1016

1017

1018

1019

1020 Patient transfer area

1021 *Function*

1022 To transfer patients who arrive in/on standard wheelchairs or patient trolleys onto [MR Conditional](#)
1023 wheelchairs/patient trolleys.

1024 *Location*

1025 Patients arriving on beds, trolleys, or wheelchairs may require transfer onto an [MR Conditional](#)
1026 trolley, an [MR Conditional](#) wheelchair, or if available, directly onto a dockable scanner table. This
1027 transfer can occur either inside or outside the [MR Controlled Access Area](#). Selecting the most
1028 appropriate location is a key element of MR suite design, particularly for services managing patients
1029 with limited mobility or higher clinical acuity.

1030

1031 Patient transfer areas can require significant amounts of space. As all MR suites may have different
1032 design constraints it may be easier to site this either inside or outside the [MR Controlled Access Area](#)
1033 depending on the availability of sufficient space.

1034

1035 **Advantages of Locating the Transfer Area Outside the [MR Controlled Access Area](#)**

1036 *Reduced risk of unsafe equipment entering the controlled area*

1037 Conducting transfers outside the [MR Controlled Access Area](#) limits the presence of unsafe
1038 equipment near the controlled zone, reducing the risk of inadvertent introduction of unsafe items
1039 and lowering projectile hazard potential.

1040

1041 *Fewer accompanying staff entering the [MR Controlled Access Area](#)*

1042 Porters, ward staff, and carers can assist with transfer without passing into the controlled area,
1043 reducing the need for MR Safety screening and supervision of additional personnel.

1044

1045 **Disadvantages of Locating the Transfer Area Outside the [MR Controlled Access Area](#)**

1046 *Additional monitoring and staffing needs*

1047 Patients transferred outside the [MR Controlled Access Area](#) may require continuous supervision,
1048 especially those at risk of deterioration. This may require increased staffing or redesign of adjacent
1049 spaces to ensure good visibility and access.

1050

1051 *Increased movement of [MR Conditional](#) equipment*
1052 Transferring outside the [MR Controlled Access Area](#) may increase travel distances for [MR](#)
1053 [Conditional](#) trolleys or dockable tables. These devices are often heavy, less manoeuvrable, and
1054 expensive, and MRI departments may be hesitant to move them out of the controlled environment
1055 into less monitored areas.

1056
1057 *Potential workflow inefficiencies*
1058 If MR staff must leave the [MR Controlled Access Area](#) to assist with transfer, this can reduce
1059 scanning efficiency and slow patient throughput.

1060
1061 **Considerations for Locating the Transfer Area Inside the [MR Controlled Access Area](#)**

1062 *Proximity to the MR Examination room*
1063 Locating the transfer area inside the [MR Controlled Access Area](#) minimises travel distance to the
1064 scanner, reducing the movement of [MR Conditional](#) equipment and improving workflow efficiency.
1065 However, some distance is advisable to reduce the risk of unsafe equipment being inadvertently
1066 taken into the MR Examination room.

1067
1068 *Improved monitoring of higher-risk patients*
1069 Patients who are clinically unstable, sedated, or require close observation can be monitored more
1070 effectively if transfer occurs within the controlled environment and adjacent to MR staff.

1071 *Requirement for adequate controlled-area space*
1072 If the transfer area is placed inside the [MR Controlled Access Area](#), the space must be large enough
1073 to accommodate beds, trolleys, equipment, accompanying staff, and safe circulation routes—all
1074 while complying with MR Safety zoning and controlled access requirements. Space within the [MR](#)
1075 [Controlled Access Area](#) is often limited, and allocating sufficient footprint for transfers may restrict
1076 other functional areas.

1077
1078 **Summary**

1079 The decision to locate the patient transfer area inside or outside the [MR Controlled Access Area](#)
1080 depends on a balance of MR Safety, available space, patient monitoring requirements, equipment
1081 logistics, and operational efficiency. Departments with limited controlled-area space or a desire to
1082 minimise [MR Controlled Access Area](#) traffic may prefer an external transfer area, whereas services
1083 handling clinically complex patients or aiming to streamline equipment movement may favour an
1084 internal approach.

1085
1086 Note, patient transfer may take place on a ward if [MR Conditional](#) equipment is sent up to the ward.

1087
1088 *Operational/design considerations*
1089 The design should consider safe storage of trolleys and wheelchairs that are unsafe for MRI,
1090 preferably outside the [MR Controlled Access Area](#). Wheelchairs and trolleys that are unsafe for MRI
1091 present a significant hazard if left near entrances to MR Examination rooms.

1092 Patients who require transfer from wheelchairs onto a trolley or dockable table may require the use
1093 of a hoist. Careful consideration should be given to the provision of a fixed hoist which has the
1094 advantage of unable to take into the MR Examination room and they typically can work to transfer
1095 patients directly onto [MR Conditional](#) trolleys or dockable tables. Mobile hoists have large feet for
1096 stability which may not fit under these specialist items and end up requiring multiple transfers.

1097
1098
1099

Real-world example: Long feet of mobile hoist in use in an MR suite did not fit under the dockable MR table or [MR Conditional](#) trolley

Patients had to be transferred from their wheelchair to a standard [MR Unlabelled](#) trolley and subsequently from the [MR Unlabelled](#) trolley to the dockable table.

Impact: Additional time to perform patient transfer with more manual handling for MR staff.

1100

1101

1102 *Patient changing rooms*

1103 *Function*

1104 The function of this area is for patients to be able to change from their own clothes into [MR Safe](#)
1105 clothing (e.g. scrubs or gowns) that ideally are pocketless. This ensures that there are no conductive
1106 fibres or other components within clothing (that have implications for safety and MR image artefact)
1107 and that no personal items (e.g. watches, jewellery, wallets, phones, hair grips) are brought into the
1108 MR Examination room.

1109

1110 *Location*

1111 Ideally, the patient changing area should be located outside of the [MR Controlled Access Area](#) for
1112 the following reasons.

- 1113 • Personal items and other objects that may be unsafe to take into the [MR Environment](#) are
1114 kept outside of the [MR Controlled Access Area](#), reducing the likelihood of them being
1115 inadvertently taken into the MR Examination room.
- 1116 • Reduced activity within the [MR Controlled Access Area](#) which reduces the risk of inadvertent
1117 access.

1118

1119 *Operational/design aspects*

1120 Patients will usually be coming from safety screening to the changing area and then moving onto
1121 either a sub-wait, preparation room or directly to the MR Examination room. The changing area
1122 should be in close proximity to all these areas for efficient workflows.

1123

1124 Once the patient has changed, the next workflow step may be one of the following.

- 1125 • The patient is taken straight through to the patient preparation area for scan preparation
- 1126 • The patient is taken straight through to the MR Examination room for their scan if no
1127 preparation is required.
- 1128 • The patient waits in the changing room. Careful consideration of this option should be made
1129 with regards impact on overall patient throughput, as other patients cannot get ready for
1130 their scan.
- 1131 • The patient waits in a changed sub-waiting area.

1132

1133 The number of changing rooms should be able to accommodate the planned patient throughput.
1134 This should include consideration of potential future increases in patient throughput. Standard
1135 options for patient changing rooms should be considered, such as provision for patients in
1136 wheelchairs, a nurse call, ability to unlock and open the door outwards in the event of an
1137 emergency.

1138

1139 Secure storage space, e.g. lockers, should be available close to the changing area to allow patients to
1140 store their clothes and personal items while they are within the [MR Controlled Access Area](#). Local
1141 sites should consider how they wish to manage placement of patient locker keys while the patient is
1142 undergoing their MRI scan. It may be reassuring for the patient for their locker key to stay within the
1143 MR Examination room during their scan, in which case it is helpful to consider options for non-

1144 ferromagnetic keys, such as aluminium or brass (additionally recognising that softer metals such as
1145 brass may be less robust to physical wear and tear), or non-metal options such as RFID. Provision for
1146 master key to be held in a secure location if needed is recommended.

1147
1148 There should be sufficient storage space close to the changing rooms for both clean and used [MR](#)
1149 [Safe](#) clothing.

1150
1151 Supervision of patients should be considered. For outpatients it may be acceptable for the patients
1152 to be unattended until they are ready for their scan. Inpatients may have different needs and may
1153 need closer supervision.

1154 1155 *Sub-waiting Area*

1156 *Function*

1157 The function of the sub-waiting area is a secondary waiting area for patients who have been MR
1158 Safety screened and have changed into [MR Safe](#) clothing. This may be helpful to separate these
1159 patients from those in the general waiting area who have not yet undergone MR screening and
1160 changed into [MR Safe](#) clothing.

1161
1162 For some patients, the sub-waiting area may also function as a location where they drink an oral
1163 preparation prior to their MRI scan.

1164 1165 *Location*

1166 Ideally, the sub-waiting area should be located outside of the [MR Controlled Access Area](#) to help
1167 reduce the patient's time within the [MR Controlled Access Area](#) and the associated level of
1168 supervision by MR staff that is required. In some cases, the initial waiting area may also serve as the
1169 sub-waiting area.

1170
1171 The sub-waiting may be adjacent to the entrance to the [MR Controlled Access Area](#) and the
1172 preparation area within, as this follows the patient pathway and it is more efficient for staff.

1173 1174 *Operational/design considerations*

1175 If a separate sub-waiting area is not included in the design then these consideration should form
1176 part of the section for the patient waiting area.

1177
1178 Access to toilets within/close to the sub-wait area should be considered, particularly if intended MRI
1179 service includes examinations that may necessitate patients emptying their bladder/bowels
1180 before/immediately after their scan.

1181
1182 The area should incorporate scope for patients in wheelchairs.

1183
1184 Ferromagnetic detection systems are intended as ancillary screening devices and are not
1185 intended to be used as a replacement for traditional safety programmes, training or primary
1186 screening methods but as a complimentary tool. If a local decision is made to install a ferromagnetic
1187 detection system, then the sub-waiting area is one location where this can be located. Here, it can
1188 serve as an additional check for any ferromagnetic items before taking a person into the [MR](#)
1189 [Controlled Access Area](#). An alternative location for a ferromagnetic detection system is at the MR
1190 Examination room door, where it can help support a check for ferromagnetic items as a person
1191 enters the MR Examination room. Local MR staff will likely be best placed to define the optimum
1192 location based on established work procedures and planned patient workflows. A key point to
1193 consider is the scope for alarm fatigue, where MR staff become desensitised to the alarm as a result
1194 of frequent alarm alerts.

1195 Patient preparation area

1196

1197 *Function*

1198 The primary purpose of this area is the final preparation of the patient before they enter the MR
1199 Examination room. This will include functions such as cannula insertion, but may also include
1200 sedation / anaesthetic induction.

1201

1202 If there is no separate recovery area then the patient preparation area will also function as a location
1203 for the patient to recover after their MRI exam. This may include any patients having drug reactions,
1204 e.g. to MRI contrast media. Additionally, the area may need to provide a location for the crash team
1205 to come to perform emergency resuscitation procedures, outside of the [MR Environment](#).

1206

1207 If there is no dedicated patient transfer space outside of the [MR Controlled Access Area](#) then the
1208 preparation area may also need to provide a space for transfers to take place from standard
1209 equipment that is typically unsafe for MRI to [MR Safe/MR Conditional](#) alternatives. Such equipment
1210 may include wheelchairs, hospital bed, patient monitoring, infusion pumps, anaesthetic machine and
1211 oxygen cylinders. Additionally, the space may then provide a location for the MR Safety screening of
1212 in-patients. Finally, the space may need to act as a 'holding area' whilst an in-patient is waiting to
1213 return to the ward.

1214

1215 *Location*

1216 The preparation area is typically located within the [MR Controlled Access Area](#), near to the MR
1217 Examination room, as it usually forms the step in the patient pathway immediately pre/post MRI
1218 scan.

1219

1220 *Operational/design considerations*

1221 The area should include space to support a sufficient number of cannulation chairs. The size of the
1222 area and its position in relation to the MR Examination room door should allow for easy
1223 manoeuvring of an [MR Conditional](#) trolley or dockable MR table in/out of the MR Examination room.
1224 Even if the site is planning only to scan ambulatory out-patients, this may be relevant to support safe
1225 evacuation of patients from the MR Examination room when required.

1226

1227 How patients within the preparation area will be medically supervised should be considered. In
1228 many cases, having the preparation area observable from the MR Control room is preferable to
1229 support this.

1230

1231 When considering access and size especially with respect to anaesthetic cases, any room used for
1232 anaesthetic induction may need to be able to accommodate:

1233

- 1234 • a bed or standard trolley as [MR Conditional](#) trollies may not meet the requirements for
anaesthesia (e.g. they do not tip head down).
- 1235 • carers and parents of children or patients with learning disabilities may need to be able to
1236 come into the preparation room for anaesthetic induction.
- 1237 • provision of additional procedures (e.g. dental care for severe learning disabled patients,
1238 lumbar punctures/biopsies) which may require additional room for staff and equipment to
1239 carry out these procedures.
- 1240 • Space for access to resuscitation and difficult airway equipment.
- 1241 • Lockable drug cupboards.

1242

1243

1244 Provision of medical gases may be required. If anaesthetic cases are planned, input into the design
1245 of the preparation area from the local anaesthetic team and eventual sign off is strongly
1246 recommended.

1247

1248 To help with control of access, accommodating an additional WC within the [MR Controlled Access](#)
1249 [Area](#) may be helpful to avoid MR Safety screened patients having to temporarily exit the [MR](#)
1250 [Controlled Access Area](#).

1251

1252

DRAFT

1253 MR Examination room

1254 It is particularly important to ensure the design of the MR Examination room is as complete as
1255 possible since subsequent changes may require the magnet to be temporarily ramped down, which
1256 is both costly and extends MR scanner downtime.

1257

1258 For replacement MR systems, the design requirements will depend on the level of alterations that
1259 are planned. However, even with minimal changes, it is important that MR staff are fully engaged in
1260 the design process to help ensure that important details are not missed.

1261

1262

Real-world example: reinstallation of anaesthetic gases was missed when new RF cage was installed as part of a replacement MRI installation

It was wrongly assumed that the existing provision of anaesthetic gases would be reinstated when a new RF cage was installed as part of a replacement MRI project.

Impact: Initial MRI anaesthetic cases delayed by several weeks. MR scanner was down for one day to retrofit anaesthetic gases with additional cost to the hospital.

1263

1264

1265 *Function*

1266 The MR Examination room is where MR scanning occurs, but this may also include different aspects
1267 depending on the MRI services that are to be provided. This may include the following.

- 1268 • Administration of MRI contrast agent and other drugs
- 1269 • Interventional activities (e.g. biopsy)
- 1270 • Transfer of the patient onto and off the scanner couch.

1271 In addition to the MR scanner, the room needs to various other equipment according to the
1272 particular MRI services that are to be provided.

1273

1274 *Location*

1275 The MR Examination room is located next to the MR Control room and typically immediately
1276 adjacent to the MR Technical room and patient preparation/recovery area. The MR Examination
1277 room is part of the [MR Environment](#), and is therefore located within the [MR Controlled Access Area](#).

1278

1279 The entrance and approaches to the MR Examination room will ideally be visible from the MR
1280 control room. This is to allow MR staff within the MR Control room to observe whether anyone is
1281 unexpectedly attempting to access the MR Examination room. Similarly, incorporating some
1282 distance in the design between the entrance to the MR Examination room and entrance to the [MR
1283 Controlled Access Area](#) is desirable to help to mitigate the risk of an unauthorised person entering
1284 the MR Examination room if they manage to gain access to the [MR Controlled Access Area](#), e.g. via
1285 tailgating another individual.

1286

1287 Importantly, the MR Examination room needs to be located such that the position of the MR scanner
1288 within the room meets the MR manufacturers specification regarding minimum distances from the
1289 isocentre of the MR scanner to various items that may negatively impact MR quality, which may
1290 include the following.

- 1291 • Steel within the building
- 1292 • High-voltage power cables
- 1293 • Other MR systems. In general, designs where multiple MR scanners are orientated in parallel
1294 provides scope for minimum separation distances.
- 1295 • Large moving ferromagnetic objects, e.g. motor vehicles, lifts

1296

1297 Additionally, the potential for neighbouring equipment sensitive to magnetic fields, e.g. gamma
1298 cameras, to be adversely impacted from the MRI fringe magnetic field should be considered.
1299
1300

1301 *Operational/design considerations*

1302 The MR Examination room must be large enough, and arranged appropriately, to enable safe and
1303 efficient transfer of all patients—including those walking or arriving on [MR Conditional](#) beds,
1304 trolleys, or wheelchairs—both into the room and onto/off the MR scanner table. The room layout,
1305 entrance location, and scanner orientation should all facilitate smooth patient flow and allow for
1306 rapid patient evacuation in the event of an emergency. Space must also be sufficient for transferring
1307 any [MR Conditional](#) equipment intended to enter the room, such as an anaesthetic machine or
1308 power injector. While manufacturers may provide minimum room-size specifications, these often
1309 focus solely on accommodating their scanner and associated hardware. It is therefore essential to
1310 consider broader clinical requirements, emergency planning, and the specific MRI services to be
1311 delivered when determining the appropriate room size. Storage and operational space for
1312 emergency evacuation equipment (e.g., evacuation trolleys) should also be planned within the room
1313 layout.
1314

1315 Additionally, consideration should be given to any additional equipment that will be required
1316 temporarily/permanently within the MR Examination room to support the intended MR services.

1317 This equipment may include the following.

- 1318 • [MR Conditional](#) power injector
 - 1319 • [MR Conditional](#) anaesthetic machine
 - 1320 • [MR Conditional](#) patient monitoring
 - 1321 • [MR Conditional](#) patient video system
 - 1322 • Additional equipment not included as standard e.g. display units for fMRI visual stimulation
 - 1323 • MR-guided biopsy equipment
 - 1324 • Specialised MR procedures e.g. MR-guided focussed ultrasound.
 - 1325 • Radiotherapy planning lasers
- 1326
1327

1328 [HBN 06-01](#) has general recommendations about scanner positioning to allow clear views along the
1329 magnet bore, MR Examination room door location, provision of area next to the table for patient
1330 transfer, provision of a relaxing and distracting patient environment, fixtures and fittings,
1331 soundproofing, minimum room sizes. It also recommends that it is adjacent to the control room and
1332 technical room.
1333
1334

Real-world example: insufficient space at the rear of the MR scanner to allow the MR table to move out to full extent

Design did not account for extended MR tabletop motion that was provided for whole body MR applications.

Impact: MR scanner had limited scope to perform whole-body MRI studies for the duration of the MR system (10 years+).

1335


1336

1337 *Anti-vibration pads*

1338 Even if building vibration levels are within limits at the time of installation, incorporating use of anti-
1339 vibration pads helps to mitigate for future vibration problems that might arise from the nearby
1340 installation of other equipment during the lifetime of the MR system. Additionally, anti-vibration

1341 pads may help to reduce the acoustic impact from the MR scanner to neighbouring areas via
1342 structure-borne noise transmission. MR manufacturers typically provide specifications for anti-
1343 vibration pads to be used for their systems.
1344

Real-world example: new plant equipment installed close to MR suite creating vibrations that exceeded MR manufacturer's specifications



The vibration created by the equipment exceeded the specification limit defined by the MR manufacturer.

Impact: No known impact on MR scanner in this case, but it was recognised that the MR scanner was installed on anti-vibration pads.

1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358

RF cage

Typically, the MR Examination room needs to be enclosed within an RF cage (also known as a Faraday cage or RF cabin) to shield the MR scanner from external radiofrequency signals originating from outside the MR Examination room that can otherwise impact on image quality. The RF cage also serves to attenuate the RF signals emitted by the MR scanner being transmitted beyond the MR Examination room. The MR manufacturer will specify the required shielding effectiveness. Typically, this is between 90-100 dB at several specified radiofrequencies. If scope for multi-nuclear MR systems is to be included, then consideration of testing at additional relevant frequencies may be appropriate, particularly after all installation work has completed.

Real-world example: Equipment producing RF interference at 31P frequencies

A third-party piece of equipment that was intended to be used in conjunction with 3T MR systems was found to produce RF interference at 31P frequencies at 3T.

Impact: The screen was not used during 31P-MR exams, preventing the acquisition of some planned studies.

1359
1360
1361
1362

It is important that all requirements from RF cage manufacturer are incorporated into the design. Typical requirements for the concrete slab supporting the RF cage include the following

- 1363
- 1364
- 1365
- 1366
- 1367
- 1368
- 1369
- 1370
- 1371
- 1372
- 1373
- 1374
- 1375
- 1376
- 1377
- 1378
- 1379
- Depth. It is often important to ensure a consistent floor level between the MR Examination room and immediately outside the room, recognising that even relatively small physical bumps can be unacceptable for wheeling certain patients in/out of the MR Examination room. To achieve this, the concrete slab underneath the RF cage should be cast/scabbled to accommodate the cross-section of the RF cage the MR Examination room door, as specified by the RF cage manufacturer. Alternatively, feathering of the floor immediately outside of the MR Examination room to raise the height as it approaches the MR Examination room may be possible, although subsequent implications of a non-level floor for patient trolleys and other wheeled equipment should be considered.
 - Flatness. Typically, RF cage manufacturers have requirements on the flatness of the concrete slab that are often stricter than many other building projects. Additional self-levelling compound may be required to meet the required specification.
 - Dryness. Prior to installing the RF cage, the concrete slab should be sufficiently cured to support the weight of the MR scanner, since the first step of the RF cage build often involved laying down a moisture barrier that may restrict further drying of the slab.

Real-world example: change in floor level when entering the MR Examination room door

The change in floor level caused a “bump” when wheeling patients in/out of the MR Examination room that was significantly problematic for patients with spinal problems.

Impact: A slope to avoid bump was retrofitted at additional expense and time

1380

1381

Real-world example: setting of lower floor level for MR Examination room did not take into account the MR Examination room door frame

While the floor of the MR Examination room was equal to the floor level outside, the reduction in the slab level did not extend to the MR Examination room door, resulting in a sizeable change in level at the door threshold.

Impact: A slope to avoid bump was retrofitted at additional expense and time

1382

1383

1384 Some aspects of the RF cage design are specific the make and model of MR scanner which is to be
1385 installed. Examples of this include the penetration panel and floor anchoring points. Consequently,
1386 delaying the build of the RF cage until selection of the MR system helps to avoid separate follow up
1387 work on the RF cage. Additionally, it is important to plan for the RF cage build to start once as much
1388 of the main building works have completed. Delivery of the RF cage materials before the project is
1389 ready may result in additional challenges for the secure storage of materials and an increased risk of
1390 damage.

1391

1392 Different materials can be used for the RF cage, with copper, aluminium and steel being the main
1393 examples. Copper has an advantage over aluminium and steel of being able to adapt on site to any
1394 unexpected deviations from plans. Additionally, it may be helpful to support future adaptations to the
1395 RF cage. At the time of writing at least one of the major MR manufacturers recommends the use of
1396 copper as the preferred material for the RF cage suggesting effectiveness, long term stability, design
1397 possibilities, manufacturing, customising and costs. RF cages made from aluminium require
1398 additional care during construction, particularly around doors and windows, to ensure sufficient
1399 electrical contact between panels due to the layer of aluminium oxide that may otherwise negatively
1400 impact on the level of RF attenuation. Steel is also an option for RF cages, although MR
1401 manufacturers may specify additional requirements, such as the use of non-ferromagnetic material

1402 immediately underneath the MR scanner. Further details can be found in the MR manufacturers site
1403 planning guides.

1404
1405

Real-world example: external wall was not sufficiently weatherproof before RF cage was built

During a period of stormy weather water penetrated the building, came down internal walls and under the RF cage.

Impact: The RF cage, along with the internal walls and floor, had to be replaced, resulting in a two-month project delay with associated significant costs for the hospital that included outsourcing of MRI scanning.

1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420

Any electrically conducting connection through the RF cage (e.g. electrical supply for lighting, power sockets, network cable) must pass through an RF filter, while any non-electrically conducting connection through the RF cage can pass through a waveguide. There is scope to use media convertors to modify conducting signalling cables, e.g. ethernet cabling, into non-electrically conducting fibre-optic cable, thereby allowing it to pass through an RF waveguide. However, electrical filters for ethernet connections are also available. If general anaesthesia of patients is to be performed it is essential to install RF waveguides through the RF cabin for suction, oxygen, medical air, anaesthetic gases, and an anaesthetic gas scavenging system.

The location and dimensions of waveguides should be confirmed with the intended users. This should attention to the height of planned waveguides, particularly into the MR Control room where it may be helpful to locate both above and below worktop level to support a range of connections.

Real-world example: no waveguide between MR Examination room and control room.

A new MR unit was installed without any waveguides between the MR Examination room and the MR control room.

Impact: impaired ability for optical fibre connections between MR Examination room and the MR control room, e.g., for patient monitoring, power injector.

1421
1422
1423
1424
1425
1426
1427

Larger diameter waveguides may be required, e.g. to allow projection of images/video from outside of the MR Examination room, or to allow items to be passed into the MR Examination room for particular MRI cases. Consideration should be given to waveguide solutions as part of the MR Examination room door that allow placement of non-conducting lines without needing to disconnect these from the patient.

Real-world example: size of installed waveguide was insufficient for intended use

Size of installed waveguide was found to be insufficient to allow pass through of items required for general anaesthetic cases.

Impact: Wider waveguide was retrofitted at additional cost. 2 days downtime

1428
1429
1430
1431
1432
1433

Although uncommon, should a local decision be made to install a fire sprinkler system within the MR Examination room, sprinkler systems that avoid hold the water outside of the RF cage should be used. Non-ferromagnetic water sprinkler systems intended for use within MR Examination rooms are available. RF cage manufacturers may be able to advise further on suitable designs.

1434

1435 A removable conducting plate within the RF cage, known as a penetration panel or filter panel, can
1436 be used to accommodate multiple RF filters/waveguides. Use of softer metals, such as brass, for the
1437 penetration panel can be helpful practically if there is a need to add additional connections in the
1438 penetration panel after it has been installed. Installation of a blank plate may be helpful as part of
1439 futureproofing.

1440

1441 A penetration panel will be installed for the MR manufacturer to make connections between the MR
1442 scanner and their equipment in the MR Technical room. Ideally, this MR system penetration panel
1443 should be dedicated to connections made by the MR manufacturer only. One or more additional
1444 penetration panel should be installed to support other connections into the RF cage that are not
1445 directly associated with the MR system. The distance between the MR system penetration panel and
1446 other penetration panels should meet any minimum distance requirements specified by the MR
1447 manufacturer. Additionally, a minimum clearance on both sides of the filter panel should be
1448 specified for servicing/future modifications.

1449

1450 Air ducts connect into the RF cage via separate honeycomb waveguides. The ceiling of the RF cage
1451 should incorporate a typically 600x600 mm honeycomb wave guide, providing an air connection
1452 from the MR Examination room to the void immediately above the RF cage that provides some
1453 ability for air pressure equalisation when the MR Examination room door is opened/closed.

1454

1455 To further avoid the potential for RF interference to be transmitted into the MR Examination room,
1456 it is important for the RF cage and all electrical items within it to be connected to a common
1457 electrical earth. The RF cage must be connected to a single RF common electrical ground stud which
1458 is also the earthing connection for the MR system power distribution unit supporting the gradient
1459 and RF system cabinets in the MR Technical room. This ensures a common earth between all parts of
1460 the system. Typically, a separate earth reference point is required for each MR system. Further
1461 details should be available in the MR manufacturer's site planning guide.

1462

1463 To ensure electrical isolation between honeycomb waveguides in the RF cage and external air
1464 ducting, a non-conducting packing material, e.g. wood, should be used, as shown below in Figure 9.
1465 Mechanical vibration is known to be another potential source of RF interference. Consequently, a
1466 degree of mechanical isolation between the RF cage and any attached structures (e.g. ducting, pipes)
1467 is desirable to reduce the possibility of vibrations being transmitted onto and into the RF cage.

1468



1469
1470
1471
1472

Figure 9. Example of wooden frame providing electrical isolation between honeycomb waveguides in the RF cage and external air ducting.

1473
1474
1475
1476
1477
1478
1479
1480
1481

If an existing MR scanner is being replaced and it has been established in the pre-design phase that the performance of the existing RF cage is sufficient (perhaps with localised remedial work if required) then repurposing the existing RF cage can reduce costs. This option also provides scope to plan for the old MR scanner to be removed immediately prior to the delivery of the new MR system, utilising the same exit/delivery route including scaffolding, creation of MRI entry/exit panels, propping and ramps. It is important to note that there may be substantial delays and costs associated with a late decision to procure and install a new RF cabin.

Real-world example: An existing RF cage was initially considered to be sufficient for a replacement MRI installation, but the performance was subsequently found to be insufficient during the build phase of the project.

A new RF cage was purchased and installed.

Impact: Additional 3 weeks to project + additional £200K costs

1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493

MR Examination room door

Unless there are other requirements, there is usually only a single door into and out of the MR Examination room. This should be lockable to prevent inadvertent access when the MR suite is unattended. However, this door should always be openable from within the MR Examination room.

The MR Examination room door should have clear signage indicating the hazards in the MR Examination room. Immediately outside of the MR Examination room door it is helpful to incorporate floor signage to highlight that the magnetic field is always on, as well as a retractable belt barrier that can be used to further provide access control as required. A mains-powered illuminated “The magnet is always on” sign with integrated battery backup may be placed above the

1494 MR Examination room door, although consideration should be made for an appropriate schedule for
 1495 preventative maintenance. Examples of all of these are shown below in Figure 10.
 1496
 1497



1498
 1499



1500
 1501
 1502
 1503
 1504
 1505

Figure 10. IPEM door and floor warning signs (IPEM 2017) and an example of both in practice, additionally demonstrating a second copy of signage on the inside of the door to maintain a visible warning sign when the door is open

1506 For MR scanners with a quench pipe, in the unlikely event of both a magnet quench and a quench
1507 pipe failure, large amounts of helium gas may be emitted into the MR Examination room over a
1508 short period of time (typically, 10s of seconds). This will greatly increase the room air pressure and
1509 subsequently prevent opening of the door if it opens inwards into the MR Examination room. An
1510 emergency air extract system, discussed later in the [Air Handling](#) section, is typically insufficient on
1511 its own to remove the large amounts of helium gas from a full quench for an MR system containing
1512 many 100s of litres of liquid helium in a timely manner to avoid room over-pressure and allow
1513 immediate access to the MR Examination room. Various mitigation options to consider for this
1514 scenario include the following.

- 1515 • An outwardly opening MR Examination room door.
- 1516 • An outwardly opening hatch within the MR Examination room door or elsewhere within the
1517 wall of the RF cage.
- 1518 • An alternative over-pressure relief mechanism.

1519
1520 The door into the MR Examination room forms part of the RF cage. The RF seal may result in greater
1521 resistance to opening/closing and therefore consideration should be made to ways to aid manual
1522 handling, both in the initial design and subsequently with regards ongoing maintenance during the
1523 use phase.

1524
1525 There have been several examples of MR Examination room door failures where the lock on the MR
1526 Examination room door has failed, preventing MR staff from accessing the patient ([Steckner et al.
1527 2026](#)), many of which have been reported as adverse incidents. The size and specialist nature of the
1528 magnet room door make door failure more difficult to rectify. Importantly, some RF cage
1529 manufacturers provide backup options to open the door in these scenarios and requests for
1530 clarification on this are recommended to feed into the design. Where these are not available, sites
1531 should consider further mitigation options, such as the following.

- 1532 • As a result of the RF contact fingers around the edge of the door, the force required to pull
1533 the door open can be considerable. A magnet room door design where the handle to pull
1534 the door open is physically separate from the door locking mechanism may help to reduce
1535 wear and tear, and ultimately failure of the door locking mechanism.
- 1536 • A second door into the MR Examination room provides additional mitigation for failure of
1537 the main magnet room door. The advantages of a second magnet room door are that it
1538 provides an alternative entrance / exit. The disadvantages are that additional control
1539 measures will be required to ensure no inadvertent access into the MR Examination room,
1540 the increased expense and the requirement for sufficient space to accommodate this design
1541 feature. A possible solution to inadvertent access would be to require the second MR
1542 Examination room door to be locked at all times and only unlocked in an emergency
1543 situation. It should be noted that having a second magnet room door may increase
1544 maintenance costs.

1545
1546
1547

Real-world example: MR Examination room door latch failure

A radiographer found the MR Examination room door would not open, preventing them from gaining access to the patient in the scanner. After various unsuccessful attempts were made to open the door, including the patient attempting to open the door from the inside, the fire rescue services were called in and a decision was made for them to



break and remove a window into the MR Examination room, through which the patient was rescued (see photo). Fortunately, the patient was able to remove themselves from the MR scanner and stayed calm throughout the 3 hours before they were rescued.



Subsequently, the door manufacturer replaced the door with another that included a removable panel that allowed access to the door latch mechanism should a similar event occur (see photo). Additionally, they replaced the door latch with a roller-ball latch.

Impact: 7 days of MR scanner downtime, about £20K cost to hospital

1548

1549

1550 *Magnetic shielding*

1551 In addition to RF shielding, there is scope to install high magnetic permeability metal shielding within
1552 the walls/floor/ceiling of the MR Examination room. Typically, the main objective for this magnetic
1553 shielding (sometimes described as passive shielding) is to limit the extent of the [B₀ Hazard Area](#)
1554 to the MR Examination room, particularly if the adjacent area is publicly accessible. Such shielding is
1555 often required for higher field MR systems, e.g. 3T, particularly if the building has a floor
1556 immediately below the MR scanner. Additionally, magnetic shielding can be used to reduce to
1557 likelihood of nearby large moving metal objects, such as motor vehicles and lifts, negatively
1558 impacting MR image quality (via temporary disturbances to static field homogeneity) if the minimum
1559 distances from these objects to the proposed position of the MR scanner, as specified by the MR
1560 manufacturer, cannot be met.

1561

1562 To establish whether magnetic shielding may be required, MR manufacturers provide information in
1563 their site planning guides about the spatial extent of the static magnetic field around their MR
1564 systems. This can be overlaid on room plans to give an initial indication of the extent magnetic field
1565 contours, although importantly the actual distributions may vary due to metal in the structure of the
1566 building around the MR Examination room, in particular the location of steel beams. Simulations to
1567 take these into account and calculate more accurate distributions can be performed by the MR
1568 manufacturers. Consequently, it is important to identify any existing steel in the vicinity of the MR
1569 Examination room to support these more accurate calculations. Subsequently, such simulations can
1570 be used to calculating the amount of magnetic shielding that is required to restrict the extent of the
1571 [B₀ Hazard Area](#) accordingly. Importantly, these predictions will be based on the ferrous metal used
1572 for the shielding. Examples include M36 silicon steel, Armco and Stabolec steel. In instances where a
1573 different material to that used in the simulations is desirable, e.g. to better accommodate structural
1574 needs, this should be checked with the MR manufacturer. In some cases, updated simulations may
1575 be required.

1576

1577 In the scenario where a decision on the magnetic shielding is required before a decision on the MR
1578 scanner to be installed, simulations may be performed by other bodies, e.g. RF cage manufacturers,
1579 based on a known worst-case example.

1580
1581

Real-world example: [B₀ Hazard Area](#) extension into main hospital corridor following inaccurate magnetic shielding calculations.

This was attributed to steel within the building that was not taken into account in the magnetic shielding calculations. The extension of the [B₀ Hazard Area](#) into the main hospital corridor exposed patients and staff to hazards associated with the static magnetic field.

Impact: Additional shielding installed at cost to hospital, 1 month delay to project

1582
1583
1584

Real-world example: the [B₀ Hazard Area](#) extended further out of the building than predicted.

The original calculations of the fringe field did not consider metal cladding on the building which pushed the fringe field out in areas without cladding.

Impact: delays while stud wall removed, additional steel shielding put in place and stud wall replaced.

1585
1586

Real-world example: the [B₀ Hazard Area](#) extended further out of the building than predicted.

The original calculations of the fringe field did not consider existing metal plate in the floor which pushed the fringe field out in neighbouring areas.

Impact: additional work required to corridor to avoid public access to [B₀ Hazard Area](#).

1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597

The amount of magnetic shielding can vary in size, from a small plate on a single wall to multiple layers on all walls, the ceiling and floor, with weight varying according from a few hundred to thousands of kilograms. Consequently, magnetic shielding may be significant in terms of structural support and therefore reconfirmation of structural support for any magnetic shielding is recommended. Additionally, the MR manufacturer will specify limits on the size of magnetic shielding that can be used in relation to the distance of the shielding from the MR scanner. If magnetic shielding is required underneath the MR scanner then there may be scope to suspend this from the slab into the ceiling void of the floor below to increase the distance to the MR scanner isocentre.

1598 *Acoustic noise*

1599 MR scanners can generate significant amounts of acoustic noise. Additionally, equipment in the MR
1600 Technical Room may also be acoustically loud. Acoustic noise issues should be considered,
1601 particularly if there are noise-sensitive locations near to the MR suite. These locations include wards,
1602 office space and operating theatres but may include other areas. Sensitivity to acoustic noise is likely
1603 to be more of an issue for a new MR suite, where people in neighbouring areas are unfamiliar to the
1604 background sounds of MRI scanning. Additionally, acoustic noise within the MR suite should be
1605 considered. One of the potential disadvantages of MR suite designs where the MR Examination
1606 room opens directly into the MR control room is increased noise levels in the MR control room.
1607

1608 Noise transfer can be airborne or via the building structure. Positioning the MR scanner on anti-
1609 vibration pads within the MR Examination room may help to reduce structure-borne noise
1610 transmission, in addition to vibration issues. The use of acoustic foam/panels either side of the RF
1611 cage as well as sound-insulating plasterboard may help reduce noise transmission to adjacent areas.
1612 Similarly, the introduction of non-conducting packing material into RF waveguides may be helpful to
1613 support reduced transmission of acoustic noise. The use of passive acoustic screening within the MR
1614 Examination room has also been reported ([Moelker et al 2003](#)).
1615

1616 To address acoustic risks and advise the design team the client should consider appointing an
1617 acoustic engineer to advise and potentially perform/specify requirements for an acoustic noise
1618 survey. More general guidance on acoustic noise considerations is provided in Health Technical
1619 Memorandum 08-01: Acoustics ([NHSE 2013](#)). Site planning guides may describe options for acoustic
1620 noise suppression and some RF cage manufacturers offer options for this as part of their product.
1621

1622

1623

1624

1624 *Patient privacy*

1625 Depending on the types of MRI examinations planned, the use of blinds or switchable smart glass
1626 should be considered with any windows into the MR Examination room to ensure patient privacy.

1627 *Lighting*

1628 In addition to lower power requirements, LED-based lighting offers the benefit of longevity
1629 compared to incandescent lamps. Additionally, conventional filament lamps on an AC supply in the
1630 immediate vicinity of the magnet will experience oscillating forces that further reduce their
1631 longevity. However, general LED lighting, where the conversion from AC mains to DC occurs within
1632 the lamp unit, can cause RF interference that negatively impacts on MRI image quality. Lighting in
1633 the MR Examination room should be provided by direct current (DC) LED fittings, certified as suitable
1634 for use in the MR Examination room.
1635

Real-world example: original LED lighting installed in MR Examination room caused artefact on MR images

Standard LED lighting that was not specifically designed to be compatible with MRI was installed. The AC/DC conversion that occurred at each lamp produced RF interference that was picked up by the MR scanner, impacting image quality.

Impact: Costs and delay required to retrofit appropriate LED lighting.

1636
1637 Consideration should be given to the required lux levels in all areas within the MR suite including the
1638 MR Examination room, particularly if planned MRI services include items where increased
1639 illumination is important such as injection and biopsy. [HBN 06-01](#) does not provide specific guidance
1640 on lux levels, instead signposting to Lighting for healthcare premises guidelines from the Chartered
1641 Institution of Building Services Engineers ([CIBSE 2019](#)). This CIBSE guidance has recommendations
1642 for both 300 lux and 500 lux for MRI imaging suites. The higher figure of 500 lux is recommended
1643 here as a minimum, particularly if there is an intention to perform injections, biopsies or other
1644 interventions within the MR Examination room, with an option to dim the lighting if required, e.g. to
1645 support feed and wrap neonatal MRI. Colour controllable LEDs for mood-enhancing lighting to
1646 enable an improved patient experience may be considered. Emergency lighting in the event of a
1647 power failure is a requirement under [BS 5266-1 \(2025\)](#), with the level of emergency lighting
1648 determined by local requirements.

1649
1650 Ideally, the light switch for the MR Examination room should be located outside of the room, e.g. in
1651 the MR Control room, to provide the ability to illuminate the MR Examination room without
1652 entering. This allows a visual inspection via the MR Control room window while maintaining a locked
1653 MR Examination room door which may be preferable in the event of an alarm going off out of hours.
1654

Real-world example: Fire alarm in MR suite out of hours

The fire alarm was triggered in the MR suite in the middle of the night. The attending fire brigade wanted to illuminate the MR Examination room to visually check for signs of smoke, but the light switch was located in the MR Examination room.

Impact: MR staff were called to site to gain access to the MR Examination room to turn on light. Subsequent new MRI installations designed with MR Examination room light switch located in the MR control room.

1655
1656
1657 Finally, artificial skylights or illuminated wall panels should be considered to improve the patient
1658 experience, although again these should be designed to work in an MR Examination room without
1659 causing RF interference. An example of such a skylight is shown below in Figure 11.
1660



1661
1662
1663
1664

Figure 11. Example of artificial skylight designed for use in the MR Examination room that may be considered to improve the patient experience of an MRI scan.

1665
1666
1667

Patient experience

1668 Various options are available for consideration within the MR Examination room to help improve
1669 patient experience. Importantly, such measures can help improve patient co-operation during the
1670 MRI scan, particularly with regards staying still, which subsequently has an impact on the quality of
1671 the MR image acquired. This may be more relevant for certain patients, e.g. individuals who are
1672 particularly anxious and paediatrics.

1673

1674 In addition to artificial skylights and illuminated wall panels mentioned above, a video system that
1675 allows patients to watch videos during their MRI scan can be helpful in multiple situations. If such a
1676 system is incorporated into the design of the MR Examination room, then it will need to be located
1677 behind the MR scanner, level with the scanner bore for the patient to view. Ideally, it will be
1678 mounted to the wall, but there is scope to have systems mounted on a floor stand. Such video
1679 systems require additional space within the MR Control room for the video control.


1680

1681 *Floor demarcation and tether anchor points*

1682 Consideration should be given to marking a zone within the MR Examination room using a change in
1683 floor colour or a visible line. This can be helpful to demarcate a specific static magnetic field strength
1684 around the MR scanner. The chosen field strength typically serves one of two purposes:

- 1685 • To indicate where certain MR Conditional equipment—which has limits on the maximum
1686 static magnetic field it can safely be exposed to—should be excluded from. An IPEM report
1687 on MRI safety signage ([IPEM 2017](#)) indicates a 10 mT floor marking is appropriate for most
1688 [MR Conditional](#) equipment that may be brought into the room.
- 1689 • To define the extent of a local [MR Projectile Zone](#), if such a zone is designated based on local
1690 risk assessment.

1691
1692 An example of floor demarcation is shown below in Figure 12.
1693



1694
1695
1696 *Figure 12. Example of change in floor colour to demarcate the [MR Projectile Zone](#) close to the MR scanner and a tethered*
1697 *anaesthetic machine*

1698
1699 Additionally, the fitting of anchor points in the walls inside the MR Examination room with fixed-
1700 length tethers should be considered to help ensure such [MR Conditional](#) equipment is not
1701 inadvertently moved closer to the MR scanner and into a higher magnetic field than is specified on
1702 the [MR Conditional](#) labelling. The fitting of these and any other wall fixations must be carefully
1703 planned to avoid inadvertently penetrating the RF cage. An example of wall anchor points is shown
1704 below in Figure 13.
1705



1706

1707

1708

1709

Figure 13. Example of anchor point in wall providing scope for non-ferromagnetic chain to tether an [MR Conditional](#) anaesthetic machine to avoid it being taken closer to the MR scanner than intended.

1710

1711 *Storage*

1712 Provision of adequate storage within the MR Examination room is essential to accommodate various
1713 MRI equipment and consumables. It is important to consider standard manual handling, which can
1714 be particularly relevant for heavier items such as some MRI coils and test objects. The MR
1715 manufacturer may provide a coil storage cart as part of the MR system, but additional storage will be
1716 likely.
1717

Real-world example: high shelving for MRI test objects

Manual handling was not considered as part of the design and high shelving was installed for the storage of heavy MRI test objects.

Impact: Ongoing manual handling issues for MR staff and potentially increased risk of droppage.

1718

1719

1720 *Power sockets/network ports*

1721 The need for power sockets and network ports within the MR Examination room should be
1722 considered. Any power and network cabling connections into the MR Examination room will be
1723 required to pass through filters to avoid introducing unwanted external RF interference into the
1724 room.
1725

1726

1727

1728 *Wall-mounted emergency stop buttons*

The MR examination typically has two wall-mounted emergency stop buttons.

- 1729 • Magnet quench button.
- 1730 • Mains electrical power off button.

1731

1732 The location of emergency stop buttons should ensure they are easily accessible to staff while
1733 minimizing the risk of accidental activation. A common and effective location is above the height of
1734 frequently used equipment, such as patient trolleys, but still within comfortable reach for most staff.
1735 To further reduce the risk of unintended activation, it is recommended to install a protective guard
1736 flap over any emergency button. The emergency buttons should be clearly labelled as to their
1737 purpose.
1738

1739

Real-world example: Shelving in MR Examination room was positioned immediately below the Magnet quench button which did not have a protective cover

An item of equipment was placed on the shelving, partly obscuring the magnet quench button. Subsequently, the item was pushed back on the shelf, inadvertently coming into contact with the emergency button and activating a magnet quench.

Impact: Downtime & cost of replacement helium associated with unintended manual activation of magnet quench

1739

1740 Recovery area

1741

1742 *Function*

1743 An area for patient recovery that is separate to the preparation area may be considered. This may be
1744 helpful to facilitate an efficient workflow if the available size of the preparation area is limited and
1745 cannot accommodate multiple patients.

1746

1747 *Location*

1748 The recovery area may be located outside of the [MR Controlled Access Area](#), although close
1749 proximity may be desirable to minimise distance during the transport of any intubated patients if
1750 planning to provide MRI scanning under general anaesthetic.

1751

1752 *Operational/design considerations*

1753 If outside of MRCAA, there may be scope to share the recovery area with other modalities.

1754

1755 For anaesthetic recovery piped oxygen and suction must be available.

1756

1757 Lockable drug cupboards may be required.

DRAFT

1758 MR Control room

1759

1760 *Function*

1761 The Control room is the hub of the MR suite and is where MR staff will spend significant amounts of
1762 time. Activities associated with this room include controlling the scanner, observing the patient
1763 whilst in the scanner, performing administrative computer-based tasks associated with the MRI
1764 service, taking phone calls and having oversight of activities occurring within other areas of the MR
1765 suite.

1766

1767 *Location*

1768 The MR Control room is located next to the MR Examination room. Ideally, it should either be
1769 located close to the entrance to the [MR Controlled Access Area](#) (or have other means for MR staff
1770 within the MR Control room to observe this entrance, e.g. CCTV) in order to help supervise access to
1771 the [MR Controlled Access Area](#), e.g. observing tailgaters.

1772

1773 *Operational/design considerations*

1774 The Control Room requires sufficient space for the operator console and additional devices such as:
1775 a CCTV monitor for patient observation; the patient call/alert system; patient intercom and possible
1776 music system; a control system for the power injector; a remote monitor for any patient
1777 physiological monitoring equipment; and usually a separate computer for accessing the Hospital
1778 Radiology Information System (RIS) and/or the Hospital electronic patient record (EPR) system. More
1779 generally, the control room should be of sufficient size (see [HBN 06-01](#)) to allow the full range of
1780 occupancies expected to be accommodated. Higher occupancies may occur for GA sessions or other
1781 specialist scanning activity and should be considered when planning the control room. Guidelines
1782 from the Association of Anaesthetists of Great Britain and Ireland ([Wilson et al. 2019](#)) highlight the
1783 need for additional space in the MR Control Room to allow remote anaesthetic monitoring
1784 equipment and line-of-sight patient monitoring for all staff, anaesthetists and radiographers.

1785

1786 The MR Control room should provide line of sight overview of the inside of the MR Examination
1787 room via a viewing window. A preferred configuration is for the control room to have an
1788 uninterrupted view down the magnet bore to allow the MR operator to be able to observe the
1789 patient for signs of distress / deterioration. For this reason, viewing from the rear of the magnet is
1790 generally undesirable. Where direct line of sight is not feasible, a view down the magnet bore may
1791 be provided by additional means such as CCTV.

1792

1793 Additionally, the control room should ideally provide direct line of sight to the area immediately
1794 outside of the MR Examination room door, allowing the MR staff within the Control room to observe
1795 anyone approaching the MR Examination room.

1796

1797 Shared control rooms for multiple MR systems can be beneficial, e.g. to allow greater flexibility for
1798 radiographer support between MR systems, although patient privacy and background noise when
1799 communicating with patients should be considered.

1800

1801 Dimmable lighting in the MR Control room is generally helpful to allow MR staff to modify lighting
1802 level to be appropriate for viewing MR images.

1803

1804 The use of window blinds/switchable opaque glass for the MR Examination room should be
1805 considered to ensure patient privacy for certain MRI examinations. Additionally, their inclusion with
1806 other windows in the MR Control room may be appropriate to protect patient confidentiality.

1807

1808 Consideration should be given to what control/alarm panels are to be installed within the MR
 1809 Control room to immediately alert MR staff to any issues associated with the supporting plant so
 1810 that they can take appropriate action and potentially minimise any downtime of the MRI service.
 1811 These should include the following.

- 1812 • Chiller mimic panel to alert MR staff to any issues with the chiller.
- 1813 • MR Examination room heating ventilation and air conditioning (HVAC) status. [HBN 06-01](#)
 1814 recommends that there should be a green indicator light in the control room to confirm to
 1815 the staff that the ventilation is operational and a red light to indicate that it is not
 1816 operational or has a fault.
- 1817 • MR Examination room temp. [HBN 06-01](#) recommends there should be an audible alarm if
 1818 the ambient room temperature falls outside of the range specified.
- 1819 • MR Examination room humidity
- 1820 • Leak detection in MR Technical room
- 1821 • Oxygen alarm
- 1822 • Medical gases
- 1823 • Nurse call for changing rooms/toilet

1824



1827

1828

1829

1830 *Figure 15. Heating, ventilation, and air conditioning (HVAC) mimic panel, providing information on the chilled water*
 1831 *entering the facility, magnet and control room temperature and relative humidity. The oxygen sensor alarm and emergency*
 1832 *extract fan status are shown as is the chiller status.*


1833

1834 The MR Control room should also contain a button to initiate the emergency field shut down unit (
 1835 more generally known as a quench button) and emergency electrical power off button as well as
 1836 more standard fittings such as light switches. As with the MR Examination room, these buttons
 1837 should be positioned to ensure they are easily accessible to staff while minimizing the risk of

1838 accidental activation. A commonly recommended location is above the height of frequently used
1839 equipment yet still within comfortable reach for most staff. To further reduce the risk of unintended
1840 activation, it is recommended to install a protective guard flap over any emergency buttons.
1841 Additionally, both the quench and emergency electrical power-off buttons should be clearly labelled
1842 in accordance with MHRA recommendations. Clear labelling of each control/alarm panel should be
1843 considered, incorporating a description of what it is, an indication of the normal levels and who
1844 should be contacted in the event of an alarm. Figure 16 highlights the following labels from the IPEM
1845 MRI safety notices ([IPEM 2017](#)).

- 1846 • MR scanner magnetic field off (magnet quench button)
- 1847 • MR scanner electrical power off
- 1848 • MR Examination room emergency air extract
- 1849 • MR Examination room oxygen monitor
- 1850 • MR Examination room temperature and humidity.

1851



1852

1853

1854

1855 *Figure 16. Example of IPEM signage for the labelling of various MR Safety related items.*

1856

1857

Real-world example: Chiller mimic panel not installed in MR control room.

On a non-turnkey installation, MR staff missed that a chiller mimic panel was not planned for the MR control room. Consequently, once operational, MR staff were not made aware of chiller problems until they resulted in problems with MR system.

Impact: Chiller alarm panel was retrofitted at additional expense

1858

1859

1860 Given the potentially large number of items of electrical equipment within the control room, it is
1861 important to ensure the MR Control room has sufficient number and distribution of power sockets
1862 and network ports. It is often helpful to have sockets available both above and below desk height to
1863 support a range of connections.

1864

1865

1866 MR Technical room

1867

1868 *Function*

1869 The MR Technical room accommodates parts of the MR system that are sited outside of the MR
1870 Examination room. This equipment is generally housed within multiple equipment cabinets. The
1871 technical room may also incorporate additional equipment to support certain MR examinations, e.g.
1872 a video projector to support functional MRI studies.

1873

1874 *Location*

1875 The MR Technical room is generally located adjacent to the MR Examination room as the MR
1876 manufacturer will generally specify a maximum length for cables between the MR scanner and the
1877 equipment within the MR Technical room. However, this may still allow for a small amount of
1878 separation between these two rooms if required. There may be additional reasons for immediate
1879 adjacency to the MR Examination room, e.g. for an fMRI projector within the MR Technical room to
1880 project into the MR Examination room.

1881

1882 *Operational/design considerations*

1883 The size of the MR Technical room and the distance between the electronic cabinets and MR system
1884 should comply with the MR manufacturer's requirements. Additionally, the MR manufacturer may
1885 have requirements for a minimum separation distance between the electronics cabinets of different
1886 MR systems at the same nominal field strength (e.g. one MR manufacturer has a recommendation of
1887 a 5 m separation), that close proximity of MR Technical rooms or having a shared MR Technical
1888 room. When planning adjacent MR Technical rooms, it is recommended to seek advice from
1889 potential MRI manufacturers. If adjacent MR systems are planned to be different nominal field
1890 strengths (e.g. 1.5T and 3T), then consideration should be given to changes with future scanner
1891 replacements.

1892

1893 Entrance to the MR technical room may be from within the [MR Controlled Access Area](#) or from
1894 outside of the [MR Controlled Access Area](#). Either way, a general door lock is recommended, with the
1895 physical key often kept in the MR Control Room. Entrance to the MR Technical Room via the MR
1896 Examination room itself should be avoided where possible. Practically, it is desirable for the entrance
1897 to the MR Technical room to be relatively close to the MR Control room, particularly for MR
1898 engineers who often need to work between these locations when on site.

1899

1900 Generally, the MR Technical room is the location within the MR suite with the greatest requirements
1901 in terms of power and chilled water. Additionally, there may be significant requirements for air
1902 conditioning. These are all discussed in the section on the [supporting plant](#). Water pipes
1903 immediately above the electrical equipment cabinets should be avoided where possible.
1904 Consideration should be given to the installation of drip trays above electrical equipment cabinets,
1905 ideally with a direct connection to drain. Since the MR technical room is often unoccupied,
1906 installation of a leak detection system in any drip trays and in the floor of the MR technical room is
1907 advisable with an alarm point within the MR Control room to help ensure swift remedial action in
1908 the event of a leak.

1909

Real-world example: Water damage to MRI electrical equipment in the MR Technical Room

Water leak from floor above into MR Technical room leading to damage to electrical equipment.

Impact: £100,000 cost, 3 weeks system down time for replacement of MRI cabinets. A drip tray was subsequently installed above the cabinets with a leak detection system incorporating an alarm in the MR Control room.

1910

1911 Network connections and power sockets within the MR Technical room may be required to support
1912 remote monitoring solutions.

1913
1914

1915 Cleaning/storage/staff changing

1916 Consideration should be given to sufficient storage space for cleaning equipment and other items
1917 within the MR suite. These may include the following.

- 1918 • Filters and other consumables for chillers and other supporting plant
- 1919 • [MR Conditional](#) patient transfer equipment
- 1920 • [MR Conditional](#) monitoring equipment
- 1921 • Radiotherapy planning equipment.

1922

1923 Ideally, [MR Safe](#)/[MR Conditional](#) items that are to be used within the [MR Environment](#) should be
1924 stored within the [MR Controlled Access Area](#) to help ensure they are not inadvertently swapped
1925 with similar equipment that is unsafe to bring into the [MR Environment](#).

1926

1927

Real-world example: [MR Safe](#) cleaning equipment stored outside the [MR Controlled Access Area](#) inadvertently swapped with ferromagnetic cleaning equipment

A fully plastic mop, labelled as [MR Safe](#), that was used to clean in the [MR Environment](#) was inadvertently swapped with another mop that contained ferromagnetic components. This was subsequently taken into the MR Examination room.

Impact: Ferromagnetic incident where ferromagnetic mop was pulled into the MR scanner bore.

1928

1929

1930 Additionally, space for staff changing including secure storage should be considered.

1931


1932

1933

1934

1935 **3.5 Examples of an MR suite layout**


1936 This section provides examples of different MR suite layouts, highlighting various ideal and non-ideal
 1937 aspects of each. All of these examples utilise 0.5 mT as the static magnetic field threshold for the [Bo](#)
 1938 [Hazard Area](#). This threshold was formally increased to 0.9 mT in version 4 of IEC 60601-2-33 ([IEC](#)
 1939 [2022](#)). As discussed in the pre-design phase, a local decision is recommended on where to set the
 1940 threshold. The ACR zones are highlighted on these example plans in addition to the [MR Controlled](#)
 1941 [Access Area](#) and the [MR Environment](#).



1942
1943

Ideal (good practice)	Non-ideal (potential issues)
Clear Zones	Tech room opens outside of MR Controlled Access Area although lockable door.
Good line of sight of RF door	
Interview room outside MR Controlled Access Area	
WC within MR Controlled Access Area	
View straight down bore from control room	
Prep area of reasonable size	
Changing rooms outside MR Controlled Access Area	
Single entrance into MR Controlled Access Area	
Spacious MR Examination room	

1944
1945




1946
1947

Ideal (good practice)	Non-ideal (potential issues)
Clear Zones	Partial line of sight of RF door
Good line of sight of RF door	Changing rooms inside MR Controlled Access Area
Interview room outside MR Controlled Access Area	
WC within MR Controlled Access Area	
View straight down bore from control room	
Prep area of reasonable size	
Changing rooms outside MR Controlled Access Area	

Single entrance into MR Controlled Access Area	
Spacious MR Examination room	


1948
1949



1950

Ideal (good practice)	Non-ideal (potential issues)
Clear Zones	Partial line of sight of RF door
Good line of sight of RF door	Changing rooms inside MR Controlled Access Area
Interview room outside MR Controlled Access Area	No WC within MR Controlled Access Area
View straight down bore from control room	No clearly identified preparation area. B₀ Hazard Area extends out of back wall of magnet requiring either shielding or control of access.
Changing rooms outside MR Controlled Access Area	
Single entrance into MR Controlled Access Area	


1951
1952



1953
1954

Ideal (good practice)	Non-ideal (potential issues)
Single entrance into MR Controlled Access Area	No line of sight of RF door
	Changing rooms inside MR Controlled Access Area
	No WC within MR Controlled Access Area
	Prep area is limited in size and ill defined.
	No interview room
	Side on view of MR scanner from control room.
	Patients have to walk past magnet room to get to reception and waiting areas.
	B₀ Hazard Area extends significantly out of the back wall of magnet requiring either shielding or control of access.

1955
1956




1957

Ideal (good practice)	Non-ideal (potential issues)
View straight down bore from control room (for Left hand scanner)	No line of sight of RF door from control room.
	Changing rooms inside MR Controlled Access Area
	No WC within MR Controlled Access Area
	No prep area
	No interview room
	Five entrances to the MR Controlled Access Area can be difficult to control access as well as providing potential opportunity for MR Controlled Access Area to be used as a walk through route.
	B₀ Hazard Area extends significantly out of the back wall of magnet requiring either shielding or control of access.

1958

1959

1960




1961

Ideal (good practice)	Non-ideal (potential issues)
Clearly defined zones	No line of sight of RF door from control room.
MR Technical room in MR Controlled Access Area	Changing rooms inside MR Controlled Access Area
	No WC within MR Controlled Access Area
	No prep area
	No interview room
	Side view of magnet from control room.
	Magnet room is small
	B₀ Hazard Area extends significantly out of the back wall of magnet requiring either shielding or control of access.

1962

1963



1964

Ideal (good practice)	Non-ideal (potential issues)
Clearly defined zones	Limited line of sight of MR Examination room door from control room.
Tech room in MR Controlled Access Area	Changing rooms inside MR Controlled Access Area
Exam room restricted in size and layout.	No WC within MR Controlled Access Area
	No prep area
	No interview room
	Magnet room is small
	B₀ Hazard Area extends significantly out of the back wall of magnet requiring either shielding or control of access.
	Magnet room has complicated shape which may be expensive.
	Exam room opens into busy corridor.

1965

1966

1967 **3.6 Supporting plant and items external to the MR suite**

1968

1969 Quench pipe

1970 Some of the latest generation of superconducting MR systems require very little helium, such that
1971 they can accommodate the helium gas that is produced in the event of a magnet quench within the
1972 physical confines of the scanner. However, the majority of clinical MR systems at the time of writing
1973 use much larger amounts of helium that require the installation of a quench pipe to vent the helium
1974 gas in the event of a magnet quench from the MR scanner to outside of the building. Appropriate
1975 design of the quench pipe is important to ensure safety.

1976

1977 Designing the general arrangement of a quench pipe at an early stage of a project, before specialists
1978 are engaged, requires careful consideration of several factors. Ultimately, the structural engineer
1979 will be responsible for specifying the quench pipe design.

1980


1981 The following steps are recommended for consideration to help guide the design process.

- 1982 • Understand the Purpose of Quench Pipes. Quench pipes are essential safety features
1983 designed to safely carry away helium gas in the event of a magnet quench. They help
1984 prevent pressure buildup and potential hazards by providing a controlled path for the
1985 escaping gas.
- 1986 • Locating the MR Examination room. The quench pipe is a consideration when deciding on an
1987 appropriate location for the MR Examination room. Due to the size of MRI's, however, the
1988 access required for installation or replacement usually dictates that the MR Examination
1989 room is located adjacent to an external wall, or in some instances on the top storey below a
1990 roof which can be opened for install and replacement. This, in turn, usually means the
1991 quench pipe also has near-by access to external air. If the area immediately around the
1992 quench pipe outlet is accessible, this should be a restricted area, e.g. governed by a permit
1993 to work.
- 1994 • Coordinate with MRI Equipment Layout. Gain an understanding of the planned layout of the
1995 MR suite, including the location and size of the MRI magnet and associated equipment. If
1996 the client has not chosen their preferred supplier, the architect may request permission
1997 from the client to contact the suppliers that are being considered, in order to request their
1998 standard design guidance. This information will influence the placement and routing of
1999 quench pipes.
- 2000 • Check MRI manufacturer requirements. MR manufacturers will typically specify quench pipe
2001 requirements for the diameter of the quench pipe related to the total distance and number
2002 of turns.
- 2003 • Identify Potential Quench Pipe Routes. Assess potential routes and locations for quench
2004 pipes based on the MR suite's layout and supplier guidance. Consideration should be given
2005 to minimizing the length of the quench pipe, and the number of turns required, to reduce
2006 resistance. Avoid routing pipes through occupied or sensitive or 'difficult to access' areas of
2007 the building. Avoid routing the pipe through fire rated construction to avoid breaching the
2008 integrity of the fire line. Plan for appropriate outlet gas discharge locations away from
2009 building openings (windows, intake louvres etc) and populated areas. Choose a discharge
2010 point at a higher elevation, if feasible and safe, to facilitate better dispersion of gas into the
2011 atmosphere. Seek feedback from the client's safety experts, building officials, and other
2012 relevant parties to validate the suitability of the proposed discharge location. Particularly for
2013 aesthetically-significant buildings, there may be restrictions on the quench pipe exiting
2014 through a side wall.
- 2015 • Some sites may have additional local restrictions. Be prepared to revise the design if
2016 additional safety measures or adjustments are recommended. Document the proposed
2017 quench pipe general arrangement in preliminary design drawings and specifications. Clearly

2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029

communicate the design intent and key risks to future specialists who will further develop and implement the detailed design.

- Identify Potential Quench Pipe Outlet Type. Once the preferred and safest outlet location is identified, choose the type of outlet that best directs the gases away from sensitive areas to allow for safe dispersal of helium gas without causing hazards to nearby individuals or buildings. Avoid locations where gas could be trapped or recirculated back into occupied spaces, for example through mechanical intake louvres. All outlets must be designed to prevent wind-driven precipitation from entering or collecting in the outlet. To mitigate for the potential of birds' nests, the outlet should be covered by a mesh to prohibit birds from entering. Typical outlet types are indicated in Figure 17.



2030
2031

Figure 17. Examples of quench pipe outlet designs.

2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048

- Exclusion Zones and Shielding. The recommended exclusion zones around quench pipe outlets can vary greatly between MR manufacturers. Previously, the HBN 06-03 guidance (2003) recommended a minimum of a 3 metre exclusion zone. HBN 06-03 was withdrawn around 2010 for reasons unknown, but the 3 metre minimal exclusion zone is still quoted in MHRA guidelines. The exclusion zone extent is also determined by the detailed design of the outlet. The level of design detail available can vary depending on the MRI supplier. MRI suppliers may provide detailed information for one or more types of outlets, but not necessarily the type that appears most suited to the project circumstances. Additional deflection shielding may also be required to guide the gases to safety and away from sensitive areas. Such additional shielding should normally be designed or specified by the quench pipe designer to ensure a single point of design responsibility.
- Quench Pipe Specialist Design Scope. The design needs to specify that the final outlet type, location and exclusion zone is all to be designed and confirmed by a specialist, commonly a subcontractor to the main contractor. In the even that fully coordinated detail designs are required for building regulations applications, then the client will need to have decided on

- 2049 the specific MRI equipment to be used and commissioned the full specialised design of the
2050 quench pipe and outlet based on the chosen equipment. In any event, it is recommended
2051 that the specialist is appointed as early as possible in the design process. The responsibilities
2052 of the specialist quench pipe designer should include the following.
- 2053 ○ confirmation or comment on the suitability of the proposed pipe route
 - 2054 ○ confirmation or comment on the suitability of the proposed outlet location and type.
 - 2055 ○ engagement with the client to agree the outlet type and position with regards to the
2056 anticipated maintenance regime.
 - 2057 ○ coordination with the MRI equipment supplier to ensure the supplier's technical
2058 performance requirements for the quench pipe are clear and understood.
 - 2059 ○ advise the architect on the required extent of exclusion zone.
 - 2060 ○ engagement with the design team to ensure design responsibilities, especially at points
2061 of interface, are clear and confirmed.
 - 2062 ○ advising the design team if any additional protection measures are required to the
2063 building fabric surrounding the quench pipe. For example, if the quench pipe is directed
2064 directly onto a roof.
 - 2065 ○ coordination with the design team including structural engineer to finalise all details
2066 necessary for construction, including quench pipe fixing points, secondary support
2067 structures etc.
 - 2068 ○ contribute to the health and safety file and operations and maintenance manual
 - 2069 ○ provision of compliance declarations for the quench pipe designs, in accordance with all
2070 relevant regulations associated with the specialist's scope of work, for building
2071 regulation submission.
 - 2072 ○ Consideration of introducing inspection points at regular intervals along the length of
2073 the quench pipe within the building to allow the integrity of the quench pipe and any
2074 fixings to be visually checked.
 - 2075 ● Exclusion Zone Access Control. There should be agreement on a suitable barrier system to
2076 prevent accidental access or to deter unauthorised access into the quench danger zone. The
2077 barrier system would need to allow access for routine quench pipe inspection and
2078 maintenance.
 - 2079 ● Consider Engineering Integration. With the project structural engineer, evaluate how
2080 quench pipes can be integrated into and fixed to the building's structural design. Whilst
2081 project building services engineers are not usually directly involved in the design and
2082 specification of the quench pipe, coordination between the pipework and other building
2083 services, including at high level within the MR Examination room is important, for example
2084 to avoid crossovers and ensuring adequate access.
 - 2085 ● Plan for Future Expansion and Maintenance. Anticipate future needs for maintenance and
2086 potential upgrades of the MR system. Design quench pipe routes and access points with
2087 consideration for ease of maintenance and potential future modifications.
 - 2088 ● Consider Future Building Use and Development. Where possible and with advice from the
2089 Client, anticipate future changes in building use or nearby developments that could affect
2090 the safety of the selected discharge location. Design the quench pipe outlet with flexibility
2091 to adapt to evolving circumstances.

2092
2093
2094
2095

Warning signs should be installed near the quench pipe outlet to clearly indicate the risks. Figure 18 shows the example signage for this location from the IPEM MRI safety notices ([IPEM 2017](#)).




Figure 18. MRI quench pipe outlet warning signage from IPEM MRI safety notices.

Real-world example: Inappropriate location of Quench Pipe Exhaust

The quench pipe outlet was originally located in area where building work was subsequently required. To enable the building work to be performed safely, the MR scanner was ramped down and the quench pipe outlet was relocated to a more appropriate position.

Impact: around £50K costs to hospital, downtime of MR scanner

Real-world example: Inappropriate location of quench pipe outlet

A quench pipe was installed with the outlet located 3 m from ground height rather than 3 m from head height of person standing underneath.

Impact: Physical barrier retrofitted to create 3 metre exclusion zone around the quench pipe outlet

Real-world example: Inappropriate location of quench pipe outlet

A quench pipe was installed with the outlet located in an area where access was required to service other equipment. This was identified during installation checks, and the quench pipe was relocated to a more suitable location before ramp up of the MR system.

Impact: Minor delay to MR system ramp up

2106 External physical barriers for access restriction.

2107 The installation of physical barriers may be required outside of the MR suite to restrict access to
2108 certain areas for the following reasons.

- 2109 • Hazardous areas such as regions of high magnetic field
- 2110 • Hazardous areas around the quench pipe outlet.
- 2111 • Prevent movement of large metal objects, e.g. motor vehicles, immediately adjacent close to
2112 the MR suite, that may otherwise negatively impact MRI image quality.

2113

2114 If restriction is only required for the purposes of minimising movement of large metal objects, then
2115 more aesthetic options, such as large planter, may provide sufficient obstacles.

2116

2117

Real-world example: Missing bollards to avoid motor vehicles driving/parking adjacent to MR suite.

The design did not take into account the need to restrict moving large metal objects (e.g. vehicles) within a manufacturer-specific distance from the magnet iso-centre to avoid negatively impacting the quality of MR images.

Impact: Physical bollards retrofitted at additional cost

2118

2119

2120

2121 [Chilled water supply](#)

2122 Superconducting MR scanners generally require a continuous supply of chilled water to keep the
2123 cold head running at all times to minimise helium boil off. Additionally, various electrical equipment
2124 in the MR technical room may require substantial cooling during MRI scanning. Typically, the closed-
2125 circuit chilled water supply will connect to the MR system in the MR Technical room.

2126
2127 The chilled water supply needs to meet the requirements of the MR manufacturer. However, strong
2128 consideration should be given to the provision of duplicate or shared load designs to allow individual
2129 chiller faults to be non-critical, particularly if the project brief highlights the importance of
2130 minimising downtime of the MRI service. Additionally, consideration should also be given to
2131 adequate maintainability of the chilled water system (e.g. appropriate bypass and filtration) to
2132 minimise disruption due to maintenance or fault. For some MR systems a backup chiller is listed as
2133 essential in the site planning guide. At least one of the main MR manufacturers reports that the
2134 majority of new MRI installations now incorporate a backup chiller to minimise the likelihood of MR
2135 system downtime. The inclusion of sufficient flow meters and pressure gauges in pipework should
2136 be considered to allow troubleshooting of chilled water problems.

2137
2138 It may be helpful to consider further in the design, scope to accommodate the temporary installation
2139 of mobile chillers as a further backup option.

2140
2141

Real-world example: Insufficient maintainability of chilled water system

A scanner dedicated chilled water system was installed with a recirculating, filtered water loop. The single filter was equipped with a maintenance bypass valve, allowing periodic filter maintenance without interruption of water flow. Following a water contamination incident, frequent filter cleaning was required. While the filter was bypassed for cleaning, contaminated water entered the scanner, contaminating the scanner's heat exchanger and necessitating downtime for repair.

Impact: In total, 10 episodes of filter blocking causing downtime, and 4 episodes of scanner heat exchanger contamination over an 18 month period.

2142
2143
2144
2145
2146
2147

For coastal locations, chillers utilising corrosion-resistant materials and protective coatings are recommended to ensure durability against corrosion from salt-laden air and higher humidity levels.

Real-world example: Inappropriate chiller installed for coastal location.

Original chiller was identified as inappropriate for an MR suite located close to the coast.

Impact: Chiller replaced at an additional cost of £180,000

2148
2149
2150
2151
2152
2153
2154
2155
2156
2157

Particularly if a decision is made not to go for a backup chiller, the design should consider a solution to keep the cold head running in the event of chiller failure. An option to install a mains water supply/drain into the technical room as a backup cooling solution for when the chiller fails may be possible for some MR systems. Typically, such backup solutions are only sufficient to support the cold head, aiming to avoid excessive helium boil off, and not support of MRI scanning which generally requires much greater levels of cooling. It should be recognised that backup systems have scope to be utilised for extended periods of time and such options should be viewed in conjunction with local sustainability policies.

2158 Air handling

2159 [HTM 03-01](#) recommends any room where anaesthetic gases are planned to be administered for the
2160 purposes of general anaesthesia (e.g. induction, MR Examination room, recovery) should have
2161 ventilation at 15 air changes/hour. Any other MR Examination rooms (interventional or non-
2162 interventional), including those where anaesthetic gases are planned to be administered for the
2163 purpose of pain relief or sedation but not full anaesthesia, should be at least 10 air changes/hour.
2164 Further details on ventilation are available from [HTM 03-01](#).

2165

2166 The air handling design should comply with any MR manufacturer's requirements. This may include a
2167 requirement for the incoming air to the MR Examination room to contain a proportion of non-
2168 recirculated air to mitigate for the potential of helium leakage.

2169

2170 The MR Technical room may have a substantial need for air conditioning to avoid overheating of
2171 various electrical equipment located within. Additionally, some MR systems, particularly low-helium
2172 superconducting systems, may have an air-cooled backup for the cold head in the event of a failure
2173 of chilled water supply. These can output a significant amount of heat into the MR Technical room
2174 which can be beyond the specification of typical air conditioning units.

2175

2176 MR systems often have particular needs regarding humidity levels within the MR Examination room
2177 and Technical Room, with many MR systems requiring a relative humidity around 50% for the MR
2178 Examination room. If the humidity is too high then there is a negative impact on patient safety as
2179 well as potential damage from condensation. If the humidity is too low, which may be more
2180 common during the winter months, then there may be a negative impact on MRI image quality.
2181 Importantly, MR manufacturer may refuse to spend time troubleshooting image quality issues if they
2182 note the MR Examination room humidity is too low. Hence the common need for both
2183 humidification and de-humidification.

2184

2185 The location of humidity control equipment, particularly if it requires servicing, should be agreed
2186 with MR staff.

2187

2188

Real-world example: Inappropriate location for humidity control unit.

Rather than the MR Technical room or other appropriate location, the humidity control unit was installed in the MR Control Room where it took up valuable space and was an inconvenience for MR staff each time the unit was serviced. It was subsequently identified there was a lack of communication between the design/installation teams and local MR staff.

Impact: Ongoing inconvenience for MR staff


2189

2190

2191 While many institutions may prefer to manage air temperatures centrally, e.g. via a building
2192 management system, some degree of local control may be important to support MRI scanning of
2193 certain patients, e.g. neonates. [HBN 06-01](#) recommends that any local adjustment of temperature
2194 control should be in line with those referenced in [HTM 03-01](#). An example of the various supporting
2195 plant for an MR system is shown below in Figure 19.

2196

2197



2198
2199
2200
2201
2202
2203

Figure 19. Example of MRI supporting plant. The air handling unit is highlighted by the yellow dotted box. Also shown is the condenser unit for the MR Examination room air conditioning and the MR chiller system that provides chilled water to the MR system heat exchanger located in the equipment room. The red dotted line partially shows the magnet access. This wall is demolished for installation/removal of the magnet.

2204
2205
2206
2207
2208
2209
2210
2211
2212
2213
2214
2215
2216
2217
2218
2219
2220
2221
2222
2223
2224
2225
2226
2227
2228
2229

For MR systems that include a quench pipe, it is recommended that an emergency air extract should be provided from the MR Examination room to mitigate for the possibility of helium leak. At least one MR manufacturer specifies a minimum of 12 room air exchanges per hour for the emergency air extract. The emergency extract duct should be located in the ceiling opposite the entrance to the MR Examination room to draw any potential helium escape away from the room exit. Importantly, emergency air extract systems are typically not sufficient by themselves to fully mitigate for the potential of large amounts of helium gas to be released into the MR Examination room over a short period of time (typically 10s of seconds) in the event of a magnet quench and a failure of the quench pipe. Consequently, as discussed in the section above on the MR Examination room, other forms of room overpressure relief need to be identified and incorporated into the design. The emergency extract ducting should aim for a direct route to an external wall, ideally avoiding crossing into another fire compartment.

The MHRA ([MHRA 2021](#)) advise “It is essential that an adequate number of oxygen monitors are installed and that they are regularly maintained.” MR manufacturers may provide an oxygen monitor as part of the MR system. For low helium MR systems that do not require a quench pipe, oxygen monitoring may not be required in accordance with the MR manufacturers guidance. Many oxygen detection systems are based on a chemical sensor that will need replacing multiple times through the lifetime of the MR system. To ensure that oxygen monitors can be maintained, it is important to design the location of the chemical sensor so that it is easily accessible. A common location is attached to the return air duct for the MR Examination room at a location outside of the MR Examination room, e.g. above the MR Control room.

Real-world example: Oxygen sensor installed at a location that was too difficult/hazardous to access

The oxygen sensor for a new MR system was installed at a location that could only be accessed via the outside of the building. This route was deemed too hazardous by maintenance engineers attending to service the oxygen sensor.

Impact: Oxygen sensor was not replaced and eventually failed leaving the MR suite with no oxygen monitoring.

2230
2231
2232
2233
2234
2235
2236

A low oxygen alarm should automatically trigger an emergency air extract fan from the MR Examination room to avoid any delays associated with a manual response. Additional functionality to allow manually initiation of the emergency air extract is advisable to allow pre-emptive operation.

DRAFT


2237 Electrical power supply

2238 MR systems and supporting plant often have substantial electrical power requirements. For the MR
2239 system itself, the MR manufacturer's site planning guide will specify the design capacity of the
2240 electrical supply and any other requirements such as permissible voltage variation, phase voltage
2241 imbalance, voltage waveform distortion (harmonics) and line impedance. Other electrical equipment
2242 attached to the same electrical supply may be a source of power quality problems (HVAC, motors,
2243 pumps, generators and lift machinery) such as harmonic distortion. A power quality survey should be
2244 considered prior to the design of the electrical supply, to identify any potential problems and design
2245 mitigations. An inadequate power supply may result in nuisance tripping of circuit breakers and high
2246 levels of harmonic distortion can impact image quality.


2247
2248

Real-world example: Insufficient quality of power supply resulting in intermittent poor image quality

An MR scanner was attached to an electrical switch board that also supplied a large chiller unit. Harmonics on the electricity supply that were generated by the chiller unit caused a noticeable ghosting on the MRI images. This effect was intermittent as it only occurred when the chiller was operating.



The figures below show the quality of the 3-phase electrical supply to the MR system exhibiting the ghosting artefact (left) and for a neighbouring identical MR system that was installed at the same time on a different power supply and did not exhibit the artefact (right). The measured total harmonic distortion for the affected MR scanner (left) was of 4.5%. Although this within the MR manufacturers specification of 5%, it was noticeably greater than the supply for the neighbouring MR scanner (right) that had a measured total harmonic distortion of 3.6%.



Identical Images of a test object with a basic spin echo sequence, acquired with a pump associated with the chiller unit on (left image). The noticeable ghosting was not present with the pump turned off (right image) and remained absent once a harmonic filter was fitted to the pump.

Impact: Cost to fit a harmonic filter to the separate chiller unit.

2249
2250

2251 For replacement MR system projects it is important to check the power requirements, since these
2252 may have increased compared to the existing MR system, particularly with higher MRI gradient
2253 performance on the many of the current generation of MR systems.
2254

Real-world example: increased power requirements for replacement MR scanner not planned for.

This was not noticed until MR acceptance testing when the power consistently tripped when performing MRI sequences with high intensity gradient switching.

Impact: Delays to clinical use while increased power supply was retrofitted.

2255
2256 Power requirements for all other electrical equipment that is intended to be used within the MR
2257 suite should also be considered. The power supply to any equipment that is intended to be used
2258 within the MR Examination room, e.g. power injector, anaesthetic machine, patient monitoring, will
2259 be required to go through a filter into the RF cage.

2260
2261 Consideration should be made to secondary power supply (SPS) support, e.g. generator, for MR
2262 systems and other critical electrical equipment within the MR suite in the event of a failure of the
2263 primary electrical supply. [HTM 06-01](#) includes MR scanners in a list of examples that may be
2264 regarded as risk grade B with regards loss of power supply, the highest risk level below life support
2265 or complex surgery. If a decision is made against SPS support for MR scanning, further consideration
2266 should be made to SPS support to chillers and cryocompressor to avoid problems with helium boil
2267 of. This will involve the provision of emergency power supply for the compressor and the supporting
2268 chiller. Prolonged periods (days) without a cryocompressor will result in a need for replacement
2269 helium, typically at additional cost to the institution. For low helium MR systems, shorter power
2270 interruptions may result in a magnet quench which may require a few days to recover from and
2271 potentially require magnet reshimming. In cases where availability of MRI is necessary even during a
2272 mains supply failure, then the design and quality of the essential supply should be validated to
2273 ensure that the MRI equipment will operate as intended.

2274
2275 Tertiary power supplies such as an uninterruptable power supply (UPS) may be considered to
2276 provide short-term power to the MR system (or components of the system) and supporting plant in
2277 the event of a failure of the primary electrical supply to cover the delay before the SPS becomes
2278 available and/or allow systems to be shut down normally. [HTM 06-01](#) provides general guidance for
2279 this and power issues more generally. Provision of a UPS to maintain operation of the entire MR
2280 system may be more relevant in special cases, such as interventional or intraoperative use, and
2281 specifications for an appropriate UPS may be found in MR manufacturers' site planning guides. More
2282 generally, UPS backup for the whole MR system is likely to be cost prohibitive in many situations, but
2283 consideration should be given to designing in UPS support for the following components of the MR
2284 system.

- 2285
- 2286 • Remote monitoring systems – to ensure the MR system is continuously monitored, allowing
2287 faults to be identified and addressed promptly.
 - 2288 • MR console computer – to avoid data corruption.
 - 2289 • Power sockets within the MR Examination room, e.g. for patient monitoring.
- 2290

Real-world example: Corruption of non-UPS supported MRI host computer following mains power failure.

As a result of an unexpected mains power failure, the MRI host computer became corrupted and required a complete rebuild to resolve.

Impact: At least 2 days downtime associated with rebuilding of MR host computer. Loss of all changes to protocols and other settings made since the last backup was performed.

2291
2292
2293

2294 **Building management systems**

2295 Integration of supporting plant into a Building Management System (BMS) can be valuable for
2296 identifying faults early, particularly when the scanner is not in use. Where environmental conditions
2297 are monitored or adjusted remotely, consideration should be given to providing additional local
2298 controls—for example, allowing limited-range temperature adjustments within the MR Examination
2299 room.

2300
2301 Clear escalation procedures should be in place to ensure that the local MRI service understands the
2302 extent of BMS integration and the associated response processes (e.g., communication routes,
2303 monitoring periods such as 24-hour observation, and required response times). Additional local
2304 protocols should also be established to guide staff when faults are detected before any BMS
2305 alarm-driven actions are initiated. Departments responsible for managing the BMS should
2306 understand the required actions and response times for each fault type linked into the system.

2307
2308 Potential use of the MR suite outside core hours, e.g. extended hours and on-call cases, should be
2309 considered as part of a BMS-managed air handling unit to avoid incidents where operation is
2310 reduced/disabled when required.

2311
2312

2313 **IT options & configuration**

2314 To allow setup of IT workflows, sites will be required to pass on details of basic IT options (RIS
2315 worklist, PACS) to the MR manufacturer so that they can be configured during installation. As part of
2316 this, sites are encouraged to consider potential options for IT options on the MR system more
2317 broadly which may help to support better workflows. Options may include the following.

- 2318 • Worklists. Some MR systems provide functionality for multiple worklists.
- 2319 • DICOM nodes. Connections to other DICOM nodes in addition to PACS. For each DICOM
2320 node, various options may be available, including the following.
 - 2321 ○ Query/retrieve
 - 2322 ○ Automatic send/archive of DICOMs. Some MR systems offer functionality to auto-
2323 send selected data based on specific DICOM tags.
 - 2324 ○ DICOM Storage Commitment – provides confirmation message back to the MR
2325 system that DICOMs have been received successfully.
- 2326 • MPPS (Modality Performed Procedure Step).
- 2327 • DICOM Study Description. Some MR systems offer an option to set this to match the
2328 Requested procedure from the worklist instead of the user-selected exam protocol.
- 2329 • Enhanced DICOM. This offers many advantages over what is often referred to as standard or
2330 classic DICOM, including faster data transfer and capture of additional information in the
2331 DICOM metadata. However, although Enhanced DICOM was introduced in the mid-2000
2332 there are some IT systems that may not support this. Sites should consider not only their
2333 PACS, but other 3rd party systems in use within the local organisation. Workaround options

2334 to produce standard DICOM versions of datasets when required should be considered. This
2335 may be relevant when considering the need for transfer of DICOMs between institutions.
2336 • NTP (network time protocol) server. Linking the MR system to an available NTP server helps
2337 to ensure an accurate time on the MRI host computer and subsequently an accurate time
2338 stamp on DICOM images which may be important for certain applications. Even if accurate
2339 at installation, without a link to an NTP server, the MR system clock may drift significantly
2340 over the lifetime of the MR scanner.
2341 • Remote monitoring options. The MR manufacturer should be able to provide requirements
2342 for network connections and institutional firewalls to allow them to remotely connect and
2343 monitor the MR system. Some remote monitoring options may place additional
2344 requirements on the design, e.g. power socket and a network connection in the MR
2345 Technical room.
2346 • Additional options for connected DVDs, USB drives, network shares and printers.
2347 MR manufacturers provide DICOM conformance statements which may help to understand some of
2348 the options available.

2349

2350 A network connection between the MR system and any associated workstations to the MR
2351 manufacturer is used for remote monitoring, technical and applications support. The MR
2352 manufacturer should provide details regarding local firewall configurations that are required to
2353 enable remote connection. Project managers should plan for change requests to be submitted to
2354 local IT teams in a timely manner to help ensure approvals can be obtained to ensure changes are
2355 implemented when required. For conventional superconducting MR systems, it is particularly
2356 important for this to be in place by the time of delivery, as remote monitoring is a key mitigation for
2357 certain issues that can result in significant additional cost and delays if not addressed in a timely
2358 manner.

2359

Real-world example: delays in firewall configuration to enable remote monitoring

Network firewall changes required to enable the MRI manufacturer to remotely connect to the MR scanner to monitor its status were not in place when the magnet quenched shortly after installation. The magnet quench happened on Friday evening was not discovered until staff returned on the following week. During this time ice had formed in the magnet cryostat. This required extensive work to remove and cool the magnet down.

Impact: Approx £150K additional cost to project. Approx 2 weeks delay to project

2360

2361

2362

2363 3.7 Summary & checklist

2364

Design team	✓
Design team includes representation from all professional groups to covers the technical aspects of the design?	
Design team includes representation from all the different clinical groups that are intended to use the space?	
Clinical staff within design team allocated sufficient time to allow them to fully engage and contribute to the design team?	
Design team confirmed the final design meets the project brief?	

2365

MR suite layout and general design	✓
General design options to make the space more patient-friendly considered?	
The MR Controlled Access Area is appropriately defined?	
Doors to MR Controlled Access Area are self-closing and self-locking?	
The MR Environment is appropriately defined?	
Appropriate signage for MR Controlled Access Area and MR Environment ?	
Appropriate definition of fire zones?	
How a general fire alarm in the hospital will impact on access control for the MR Controlled Access Area considered?	
Considered use of non-ferromagnetic fire extinguishers throughout the MR Controlled Access Area or whole MR suite?	
Delivery and extraction route of MR scanner(s) identified?	

2366

2367

Reception and waiting area	✓
Sufficient seating?	

2368

Pre-change preparation area	✓
Additional space for MRI simulator preparation?	

2369

2370

Patient screening areas / interview room	✓
Appropriate auditory and visual privacy?	
Support for current/future electronic patient screening requirements?	

2371

2372

Patient transfer area	✓
Defined location inside/outside of MR Controlled Access Area after operational and MR Safety considerations?	
Location for safe storage of trolleys and wheelchairs that are unsafe for MRI, preferably outside the MR Controlled Access Area ?	
Consideration of patient hoist?	

2373

2374

Patient changing rooms	✓
Sufficient number of rooms to accommodate planned patient throughput, including consideration of potential future patient throughput?	

Lockers for patients to securely store clothing and personal items?	
Consideration of non-ferromagnetic locker keys?	
Storage space for both clean and used MR Safe clothing?	
Space for patients in wheelchairs?	
Nurse call?	
Ability to gain access to room in an emergency?	

2375
2376

Sub-waiting area	✓
Appropriate access to patient toilets?	
Space for patients in wheelchairs?	
Consideration of ferromagnetic detection system to support screening prior to entry to the MR Controlled Access Area ?	

2377
2378

Patient preparation area	✓
Sufficient number of cannulation chairs?	
Sufficient space to allow easy manoeuvring of an MR Conditional trolley or dockable MR table in/out of the MR Examination room?	
Patient preparation area directly visible from MR Control room?	
Sufficient space for sedation/anaesthetic induction and recovery?	
Provision of medical gases considered?	
Sufficient space for general patient recovery if no separate recovery area?	
Sufficient space for patient transfer if there is no dedicated space for this outside of the MR Controlled Access Area ?	
Sufficient space for in-patient MR Safety screening if there is no dedicated interview area for this patient cohort?	
Sufficient space for 'holding area' whilst an in-patient is waiting to return to the ward?	
Additional WC within the MR Controlled Access Area considered?	

2379
2380

MR Examination room	✓
MR manufacturers requirements for space are met?	
Proposed position of MR scanner meets MR manufacturer's specifications for proximity to items that may impact performance of MR imaging?	
Proposed position of MR scanner to nearby equipment that may be adversely impacted by the fringe magnetic field considered?	
Sufficient space for easy and safe transfer of all patients in/out of the MR Examination room and on/off the MR scanner table including in an emergency patient evacuation?	
Sufficient space for required scanner table movement?	
Sufficient space to accommodate all equipment to support all planned MR procedures, e.g. power injectors anaesthetic machines, monitoring, po, biopsy, radiotherapy planning lasers	
Position of MR scanner and location of window into MR Control room provide a clear view down the scanner bore from the MR Control room?	
Provision of medical gases?	
Consideration of anti-vibration pads?	
Consideration of all relevant frequencies for RF cage testing if multi-nuclear MR system?	
Concrete slab is appropriate depth to accommodate RF cage to avoid step into the MR Examination room?	
Concrete slab is sufficiently flat for the RF cage?	

Concrete slab is sufficiently cured to accommodate the RF cage?	
Building is sufficiently weather-tight to support building of RF cage?	
Location and size of all waveguides confirmed with the intended users?	
Consideration of waveguide solutions within MR examination room door allowing placement of non-conducting lines without disconnecting from patient?	
Consideration of additional penetration panel for future use?	
Consideration of additional penetration panels in RF cage for connections into the MR Examination room that are not the responsibility of the MRI manufacturer?	
MR manufacturer's specifications met for minimum distance between the MR system penetration panel and other penetration panels?	
Sufficient clearance around penetration panels to allow access for future modifications?	
Appropriate signage on and around MR Examination room door?	
Consideration of retractable belt barrier outside MR Examination room?	
For MR system with quench pipes, consideration of mitigations for room over-pressure?	
Consideration of mitigation options for MR Examination room door failure?	
Consideration of the potential need for magnetic shielding from default plans of MRI fringe field (not taking local structure into account)?	
If required, calculations performed taking local structural environment into account for the MRI fringe fields and any required magnetic shielding to reduce extent of B₀ Hazard Area into areas adjacent to the MR Examination room?	
Confirmation structure can support the required magnetic shielding?	
Confirmation location of magnetic shielding is compliant with MR manufacturer's specifications?	
Consideration of acoustic noise transmission to areas outside of the MR suite?	
Consideration of acoustic noise protection within the MR suite?	
Sufficient patient privacy during MRI examination?	
LED lighting suitable for MR Examination rooms?	
LED lighting of sufficient with sufficient lux levels?	
Consideration of dimmable/coloured lighting?	
Light switch located outside the MR Examination room?	
Consideration of emergency lighting?	
Consideration of artificial skylights and illuminated wall panels?	
Consideration of patient video system?	
Suitable floor demarcation?	
Consideration of fitted hooks/anchor points in the walls	
Adequate storage for MRI equipment and consumables including consideration of manual handling issues?	
Consideration of mains power sockets in the room?	
Consideration of network ports in the room?	
Appropriate location of emergency stop buttons?	
Protective guard for emergency stop buttons?	
Appropriate signage for emergency stop buttons?	

2381
2382

Recovery area	✓
If anaesthetic recovery planned, piped oxygen and suction planned?	

2383
2384

MR Control room	✓
Sufficient size to allow accommodation of the full range of expected occupancies (including anaesthetics where planned)?	
Direct line of sight down the magnet bore?	
Direct line of sight to the area immediately outside of the MR Examination room door?	
Consideration of patient privacy and background noise if shared MR Control rooms are planned?	
Dimmable room lighting?	
Consideration of window blinds/switchable opaque glass for patient confidentiality?	
Consideration of control/alarm panels?	
All control/alarm panels appropriately labelled?	
Appropriate location of emergency stop buttons?	
Emergency stop buttons appropriately labelled?	
Sufficient number and position of power sockets and network ports?	

2385
2386

MR Technical room	✓
Complies with MR manufacturer's minimum space requirements?	
Position of electronic cabinets comply with MR manufacturer's requirements for distance to MR scanner?	
Distance between electronic cabinets supporting MR scanners at the same nominal field strength comply with any MR manufacturer's requirements for separation distance?	
Consideration of drip tray installation above electronic cabinets & associated leak detection alarm?	
Sufficient mains plugs and network ports?	

2387
2388

Cleaning/storage/staff changing	✓
Sufficient storage space for cleaning equipment and other items?	
Sufficient space for staff changing?	

2389
2390

Supporting plant	✓
Quench pipe design complies with requirements of the MR manufacturer?	
Appropriate exclusion zone including consideration of physical barriers around quench pipe outlet?	
Appropriate warning signage around quench pipe outlet?	
Consideration of physical barriers to increase distance of moving motor vehicles near MR suite?	
Chilled water supply meets the MR manufacturer's requirements?	
Consideration of duplicate/shared load chiller designs?	
Sufficient flow meters and pressure gauges to support troubleshooting?	


Consideration to design in scope for integrating mobile chillers as backup solution?	
Appropriate chiller options if coastal location?	
Consideration of mains water backup to maintain cold head operation?	
Air handling design complies with HTM 03-01 ?	
Air handing meets MR manufacturer's requirements?	
Humidity control design to meet MR manufacturer's requirements?	
Location of humidity control equipment appropriate for MR staff?	
Consideration of local control for MR Examination room temperature?	
For MR systems with quench pipe, appropriate emergency extract system, including position of extract duct in MR Examination room?	
For MR systems with quench pipe, oxygen monitor planned with an automatic trigger of emergency air extract?	
Appropriate location of oxygen sensor to support ease of access for servicing?	
Electrical power supply meets MR manufacturer's requirements?	
Consideration of secondary power supply support?	
Consideration of battery (UPS) backup for key items of equipment?	
Clarity with MR staff regarding BMS operation and fault reporting?	
Potential use of MR suite outside core hour considered for BMS-managed air handling unit?	
Consideration of MR system IT options?	
Timely submission of MR manufacturer's IT requirements to local IT teams planned?	

2391

DRAFT

2392 **4 Build (RIBA stage 5)**

2393



2394

2395

2396 **4.1 Introduction**

2397 This section covers the building works associated with a new MRI installation, prior to the delivery
 2398 and installation of the MR system. The involvement of multiple contractors at this stage of the
 2399 project requires careful coordination and effective communication to ensure details of the design
 2400 are fully realised as intended and that unexpected issues are managed appropriately. This may be
 2401 particularly important for non-turnkey installations if one or more contractors have no or limited
 2402 previous experience of working on new MRI installations with the additional issues that they need to
 2403 consider.

2404

2405 Project plans should include sufficient time during the build stage to allow for equipment installation
 2406 and commissioning before key timepoints, in particular the delivery of the magnet and subsequently
 2407 the magnet ramp-up. These two timepoints form two of the subsections below, together with a
 2408 further subsections on issues associated with the removal of a previous MR system, a new RF cage
 2409 and the magnet quench pipe.

2410

2411 If some aspects of the build are required to overlap with the installation of the MR system, then this
 2412 should be planned with the MR manufacturer in advance, especially if there is a need to ramp the
 2413 magnet down for certain items to be completed. If looking to do any such work with magnet at field,
 2414 then there will be a need to implement appropriate screening of individuals and equipment.
 2415 Additionally, it is important to incorporate reasonable contingency within the plan to help ensure
 2416 unexpected problems can be accommodated in a timely manner, ideally avoiding the need to delay
 2417 subsequent steps in the project that in turn can result in much more substantial delays to overall
 2418 project completion.

2419

2420 It is important for the project team to meet regularly during the build phase, although frequency
 2421 may vary, e.g. monthly for pre-commencement, then weekly for the final stages. These meetings are
 2422 opportunities to discuss general progress, any issues arising such as unexpected delays and
 2423 necessary re-scheduling, and to make any final decisions on design. It is helpful to provide the
 2424 project team with an up-to-date schedule of installation and commissioning (e.g. as a Gantt chart or
 2425 spreadsheet) so that any delays and scheduled activities are shared and planned for in terms of
 2426 availability of other staff groups/contractors, applications training and ultimately planning for the
 2427 the first clinical lists following handover. Examples of items that might appear in such a schedule are
 2428 listed below in Table 3.

2429

2430

Activity	typical duration [days]	Comments
Consider: Helium fill and QA if redundant system being sold	2	
Decommissioning and ramp down of current MR system (if appropriate)	1-2	For replacement of a current MR system
Erection of structural scaffolding access and landing platform	1-3	For systems <i>not</i> being installed on ground floor

Form MRI entry/exit panel	1-2	
Remove MRI & existing chiller	1-3	
Strip existing RF cage structure & associated mechanical & electrical works throughout	10-20	
Check and form floor levels & service openings to walls		
Take down existing walls and install new		
1 st mechanical and electrical installation	3-8	
Install RF Cabin and carry out RF cage test	5-8	
Form filter cupboard in cage	1-2	
Plasterboard & plastering throughout	3-5	
Doors & joinery fitted furniture	2-5	
Electrical Mains GO LIVE Date by Trust	Milestone date	
Suspended ceiling grids	1-2	
2 nd mechanical and electrical installation	2-5	
Install LED Lighting	1-2	
Mechanical, electrical commissioning	1-5	
Decoration throughout	2-5	
Floor coverings throughout	2-4	Install permanent floor markings of magnetic field isocontours in MR Examination room if required
Medical gases, scanner ventilation works	1-5	Preferably prior scanner delivery
Delivery checks	1 day	Prior MRI release for shipment
Snagging & post snagging mechanical & electrical /building works	1-3	

2431

2432 *Table 3. Example activities associated with the build phase of a new MRI installation project.*

2433

2434

2435 **4.2 Removal of old MR system**

2436 For replacement MR scanner projects that include a new RF cage, there will be a need to remove the
2437 old MR scanner near the start of the building works before arrival of the new MR scanner. Projects
2438 where the existing RF cage is being retained may provide scope for the removal of the old scanner
2439 and delivery of the new MR scanner to occur around the same time, e.g. over a single weekend,
2440 utilising the same exit/delivery route including scaffolding, creation of MRI entry/exit panels,
2441 propping and ramps as well as a single crane event. However, this may limit the scope to deal with
2442 unexpected issues.


2443
2444 Typically, decommissioning, ramp down and removal of an existing MR scanner will be organised by
2445 the MRI manufacturer of the new MR system, although this may be subcontracted to specialists
2446 dealing in used MRI equipment.

2447
2448

2449 **4.3 RF cage**

2450 When the main building structure is ready, construction of the RF cage is one of the first items in the
2451 build phase. Typically, the MR manufacturers specifications for the RF cage are confirmed by the RF
2452 cage manufacturer immediately after the cage has been built and then again immediately after the
2453 RF cage is resealed following delivery of the MR scanner. These measurements are performed with
2454 the RF cage disconnected from the earth reference point, allowing an electrical resistance
2455 measurement to be taken to demonstrate the absence of any additional earthing. It may be helpful
2456 for a member of the physics team that will be performing the acceptance testing to witness these
2457 measurements on behalf of the [MR Responsible Organisation](#). An RF cage certificate documenting
2458 the results should be provided demonstrating that the system complies with the manufacturers
2459 required shielding effectiveness. An example of this is shown in Figure 20.

2460



2461
2462
2463 *Figure 20. Example RF cabin results, showing the shielding effectiveness at 30 MHz, 63 MHz and 128 MHz, demonstrating*
2464 *all results were greater than 100 dB.*

2465
2466 At this point, it is recommended to confirm that all planned waveguides and filter panels to support
2467 connections to third party equipment (e.g. injector/projectors, TV screen, medical gases) have been
2468 installed according to the design, before installation of walls and decoration work within the MR
2469 Examination room.

2470
2471

Real-world example: Missing RF waveguide was not picked up until building works had completed.

RF waveguides indicated on the original plan were not installed. This omission was not picked up until after the building and decoration of the MR Examination room had completed.

Impact: Avoidable added time & cost associated with installation of RF waveguide: Ramp down MRI magnet, additional work to stud walls to gain access to RF cage, then repairs after waveguide fitted.

2472
2473

Real-world example: Medical gases not replaced

For a replacement MRI installation that involved a new RF cage room, the anaesthetics gases were not reinstalled. It was assumed by MR staff the room that the room was to be refurbished with like for like, but it was unclear if this was included within the design.

Impact: additional costs to retrofit, delays in clinical use

2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496

Since confirmation of RF cage performance is made prior to the remaining building & decoration of the MR Examination room and the installation of supporting services, various practical measures are recommended to help avoid unintentionally compromising the performance of the RF cage. These include the following.

- Temporary removal of the RF leaves at the bottom of the MR Examination room door to avoid potential damage arising from opening/closing the door over any trailing cables on the floor immediately outside of the MR Examination room door. Importantly, any such changes to the RF cage need to be reinstated prior to a follow up RF cage check and final handover to the customer.
- Connecting the RF cage to an insulation resistance tester that will generate an audible alarm if a path to earth is inadvertently made during the remainder of the building works. This is strongly advised to immediately flag any such problem, avoiding the potentially very difficult task of identifying them after all the building works have completed.
- Avoidance of any loose metal connections, since these can produce discharges of RF interference, appearing as RF spike artefacts on the MR images and degrading diagnostic quality. The suspended ceiling should be fixed. Suspension via movable clamps or springs should be avoided. Similarly, any cabling in the ceiling void should be fixed to appropriately secure cable trays and mounting brackets. Loose cables trailing on the suspended ceiling within the RF cage as demonstrated in Figure 21 are known to be a source of RF spikes and should be avoided.



2497
2498
2499
2500

Figure 21. Loose cables trailing on the suspended ceiling within the RF cage are known to be a source of RF spikes and should be avoided by use of secure cable trays and mounting brackets.

2501
2502
2503
2504
2505

Importantly, the use of any ferromagnetic materials/components during the subsequent building works within the RF cage should be avoided, since may subsequently present a subsequent projectile risk when the MRI magnet is ramped up.

Real-world example: ferromagnetic screws used within MR Examination room.

Ferromagnetic screws were used for fixings within the MR Examination room. During a routine inspection of the quench pipe, a ceiling tile bracket was dislodged and was pulled into the MR scanner, narrowly missing the MR engineer and causing some superficial damage to the outer covers of the scanner.

Impact: cost & time associated with ramping magnet down, replacing all ferromagnetic fixings and ramping magnet back up.

2506
2507
2508
2509
2510
2511
2512
2513
2514

Finally, RF cage performance may already have dropped by the time the MRI installation has completed and is ready to hand over to the customer ([Small et al. 2026](#)). Consequently, consideration should be given to planning for a repeat RF cage test once all building work and installation of the MR scanner has completed to confirm the performance of the RF cage is still appropriate.

2515 4.4 Quench pipe

2516 For MR systems that incorporate a quench pipe, the following steps are recommended to be taken
2517 at installation to confirm that the quench pipe has been installed correctly and to support ongoing
2518 annual inspections.

- 2519 • Obtain confirmation from the MR manufacturer that the MRI quench pipe has been installed
2520 to their specification.
- 2521 • Perform a risk assessment if required for accessing locations to visually inspect the quench
2522 pipe outlet. Potential mitigations may include introducing a permit to work system for the
2523 area immediately around the quench pipe outlet.

- 2524
- 2525
- 2526
- 2527
- 2528
- 2529
- 2530
- 2531
- 2532
- 2533
- 2534
- 2535
- 2536
- Perform a visual inspection of the quench pipe outlet, taking photographic evidence of the following to support subsequent annual check.
 - Access to quench pipe outlet is appropriately controlled
 - No obstructions to the quench pipe outlet
 - Any rain covers/protective mesh are in place
 - Appropriate signage is in place, e.g. [IPEM 2017](#).
 - Area below the outlet appropriate to mitigate risk of exposure to cryogenic gases in the event of an MRI quench, e.g. open windows, sufficient distance to public spaces.
 - Perform a visual inspection of as much of the quench pipe as is practical to do so, taking photographic evidence of the following to support subsequent annual check
 - Insulation
 - Hazard warning tape

Real-world example: Incorrect location for quench pipe outlet

The quench pipe outlet was planned to be located 3 metres above head height, but was fitted 3 metres above ground level.

Impact: additional works to increase height of quench pipe outlet. Minor delay in magnet ramp up and clinical use.

2537

2538

2539

2540 **4.5 Build requirements prior to MR scanner delivery**

2541 Timely commissioning of items within the build phase of the project is key to help identify issues as
2542 early as possible. This is important as missing opportunities to perform any remedial work prior to
2543 key timepoints in the project can greatly increase overall delays with an associated greater cost. One
2544 of the key timepoints in the project timeline is the delivery of the MR scanner.

2545

2546 Conventional superconducting MR scanners require a connection to power and a chilled water
2547 supply when they arrive on site to minimise helium boil off. Consequently, water chillers should be
2548 installed and commissioned and all chilled water pipework fully pressure tested and flushed with
2549 clean filters prior to MRI delivery. Ideally, any planned backup chilled water supply with the
2550 associated changeover mechanism should also be fully installed, commissioned and ready to use if
2551 needed by the time of MRI delivery. The mains electrical cable for the MR system should have been
2552 pulled and be ready to connect to the MR system.

2553

2554 Installation and commissioning of the RF cage should have completed, including confirmation of
2555 expected non-MR manufacturer waveguides and filter panels. An opening in the RF cage will then
2556 need to be made, sufficient in size to bring the MR scanner into the room.

2557

2558 The HVAC, including all ductwork, should also be fully installed and commissioned prior to magnet
2559 delivery. Additionally, the oxygen monitor should be installed and commissioned, including
2560 confirmation that a low oxygen alarm automatically triggers the emergency air extract mechanism
2561 from the MR Examination room.

2562

2563

2564

2565

2566

Real-world example: Emergency extract continuously drawing cold air into MR Examination room

During winter, the MR Examination room was impacting on clinical MRI. Eventually, it was identified that the emergency extract system was incorrectly configured and this had not been picked up at commissioning. The emergency extract system was reconfigured to correct operation.

Impact: Reduced capacity and delays to patient scans

2567

2568

2569

MR Examination room lighting should be fully installed and commissioned. Ideally, all fire compartmentation works should also have been completed.

2570

2571

Real-world example: Poor communication between installation parties

An issue with external RF interference and image artefacts was identified to arise from some additional lighting within the MR Examination room lighting aimed at improving the patient experience, but access to the control box was blocked by the subsequent installation of pipework. Consequently, these lights were permanently turned off.

Impact: Unusable lighting system, impaired patient experience

2572

2573

2574

Local network connections and IT firewall changes should be in place to allow the MR engineers to configure remote monitoring of the MR system by the MR manufacturer soon after magnet delivery. Additionally, local connections to the BMS should be operational to help identify any issues with the chiller and supporting plant in a timely manner.

2575

2576

2577

2578

2579

2580

4.6 Build requirements prior to ramping up MRI magnet

2581

Another key timepoint in the project is when the MRI magnet is ramped up, since it is then that all of the risks associated with the large static magnetic field become real and permanent. If the MR system is based upon a permanent magnet, then these risks may be present when the MR scanner is delivered.

2582

2583

2584

2585

2586

Where possible, all building work and installation & commissioning of equipment within the MR Examination room should be completed prior to the MR scanner being ramped up to avoid the need to manage the additional risks of performing work in the presence of the high magnet field. Key items of work to consider include the following.

2587

2588

2589

- In-room storage
- Medical Gases
- Electrical safety testing, including commissioning of any IPS/UPS sockets

2590

2591

2592

2593

2594

2595

It is important that an [MR Controlled Access Area](#) should be in place by the time the MRI magnet is ramped up to field. It should be clear who is responsible for the [MR Controlled Access Area](#) since this will be prior to handover of the MR system and building work to the [MR Responsible Organisation](#). It is important to confirm the installation of any planned magnetic shielding to avoid the agreed magnetic field threshold extending into areas adjacent to the MR Examination room.

2596

2597

2598

2599

2600

2601

Real-world example: Magnetic shielding in the design was not installed.

Magnetic shielding in the ceiling above the MR Examination room that was included in the design to avoid the [B₀ Hazard Area](#) extending into consultation rooms above the MR suite was not installed during the main build phase of the project.

Impact: >£50K additional cost to hospital, 2 month delay to project

2602
2603

Real-world example: steel shielding, specified during design phase, was not installed.

The need for steel shielding to contain fringe field from extending into offices above the MR Examination room was identified during the design phase of the project but was not sufficiently communicated to the installation team.

Impact: Additional costs, plus a 2–3-month delay to ramp down MRI magnet, order and install shielding, then ramp MRI magnet back up.

2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618

It may be beneficial to aim for installation and commissioning of any [MR Conditional](#) equipment that is intended to be used within the MR Examination room, e.g. anaesthetic machines, power injectors and patient monitoring, to occur before the magnet is ramped up to reduce the impact on needing to screen and supervise installation engineers within the [MR Environment](#) once the MRI magnet is at field. Similarly, it may be helpful for installation/commissioning of other items intended to be used within the [MR Controlled Access Area](#) more generally, e.g. intercom system and nurse call system. The reader is referred to [HBN 06-01](#) for further information on more general items to consider.

Importantly, the data connection for remote monitoring of the MR system by the MR manufacturer should be confirmed prior to ramping up the magnet, as this can help to ensure timely intervention in the event of a problems relating to/including a magnet quench when MR engineers or MR staff are not on site.

Real-world example: delays in firewall configuration to enable remote monitoring

Network firewall changes required to enable the MRI manufacturer to remotely connect to the MR scanner to monitor its status were not in place when the chiller supporting the MR system developed a fault. The failure of the chilled water supply resulted in the MR scanner losing helium for 4 days before a radiographer visited and discovered the problem. This resulted in over 200 litres of helium being lost.

Impact: hospital had to cover costs for replacement helium

2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630

Finally, any floor sealing and a deep clean of the MR Examination room is recommended immediately prior to magnet ramp up to avoid the need to use non-ferromagnetic equipment. The clean may be helpful to remove any ferromagnetic swarf or other particulates that may have been introduced to the room, e.g. via contractor's clothing or footwear.

If ongoing building works are still ongoing when the magnet is ramped up it is recommended to install a tack mat in the MR Examination room doorway, if not already in place, to capture dust and dirt and help minimise the introduction of further ferromagnetic particles into the MR Examination room.

2631 4.7 Summary & checklist

RF cage	✓
All specifications from the RF cage manufacturer have been met, e.g. slab depth, flatness, dryness?	
RF cage attenuation measurements completed and within MR manufacturer's specifications?	
All planned waveguides and filter panels to support connections to third party equipment have been installed before the installation of walls and further building work within the MR Examination room?	
Consideration of temporary measures to avoid/identify inadvertent damage to RF cage during remainder of building/installation works?	
Insulation resistance tester in place to immediately indicate if electrical connections to earth are inadvertently made?	
Loose metal connections are appropriately secured, e.g. cable trays?	
Consideration of repeat measurement of RF cage performance after all building and installation works completed?	
All fixings within the MR Examination room are non-ferromagnetic?	

2632

Quench pipe	✓
Received confirmation from the MR manufacturer that the MRI quench pipe has been installed to their specification?	
Risk assessment completed if required for accessing locations to visually inspect the quench pipe outlet?	
Documented visual inspection of the quench pipe and quench pipe outlet to support subsequent annual inspections?	

2633


Requirements prior to MR scanner delivery	✓
Required power supply for MR system in place?	
Chillers installed, commissioned and ready for connection to MR system?	
If specified, backup chilled water system installed, commissioned and ready for use?	
If required, quench pipe installed and confirmed to meet MR manufacturer's requirements?	
HVAC installed and commissioned	
Oxygen monitor installed and commissioned, including confirmation of automatic triggering of emergency air extract by oxygen alarm?	
MR Examination room lighting should be fully installed and commissioned?	
Data connection for remote monitoring in place?	
BMS connections to supporting plant operational?	

2634

Requirements prior to ramping up MRI magnet	✓
All storage within MR Examination room built/installed?	
Medical gases installed and commissioned?	
Electrical safety testing completed?	
MR Controlled Access Area in place, with clear allocation of responsibilities?	
Any planned magnetic shielding installed?	
Installation and commissioning of any MR Conditional equipment that is intended to be used within the MR Examination room?	
Confirmation by MR manufacturer of working remote monitoring?	
MR Examination room floor sealed?	
Deep clean of the MR Examination room?	
Installation of tack mats at entrance to MR Examination room?	

2635 **5 Delivery & installation (RIBA stage 5)**

2636



2637
2638

2639 **5.1 Introduction**

2640 This section covers the delivery and installation of the MR system. Although both this and the
2641 previous build section are part of RIBA stage 5, they are separated here since in the context of new
2642 MRI installations they form two distinct pieces of work.

2643

2644 Use of the term [MR Installer](#) in this section recognises that for some new MRI projects the MR
2645 manufacturer may subcontract installation of the system to a separate team. Additionally, the MR
2646 system may be purchased from another supplier.

2647

2648 Ideally the majority of the building work will have completed by this stage of the project. However,
2649 there will typically be a need for some overlap to reseal the RF cage and complete the build and
2650 decoration of the MR Examination room. Consequently, it is important to consider and agree how
2651 site responsibilities will be managed between the [MR Installer](#) and other contractors.

2652

2653 It is important to establish schedules with all parties concerned in the early stages of the MR
2654 installation. Examples of items that might appear in the schedule of work for the delivery and
2655 installation phase are listed below in Table 4.

2656

2657

Activity	typical duration [days]	Comments
MR scanner and associated equipment delivery including liquid helium	1	Note: local Council should be notified in advance and permission obtained for any road closures required for delivery of MR scanner if applicable
Internal cabin finishing works	1-2	Make good post delivery. Refit RF cabin scanner entry panels
Helium fill	0.5	To suit manufacturer's programme
MRI Scanner installation, ramp up & commissioning period	4-8	Once the MR scanner is ramped up permits to work should be issued (MR) and MR Safety screening of contractors/Trust staff accessing MR controlled areas
Network connections (PACS + remote monitoring)	1-2	Integral with MRI commissioning

Installation of ancillary equipment e.g. contrast injector	1-2	Consider this prior to MRI ramp up. Also check any dedicated enabling requirements (power, data, structural mounts, etc)
Cleaning of MR suite	1-2	To meet local requirements

2658

2659 *Table 4. Examples activities associated with delivery and installation phase.*

2660

2661

2662 5.2 MR scanner delivery

2663 Conventional superconducting MR scanners are not ramped up during transit and therefore the
 2664 hazard of the large magnetic field is not present. Consequently, the requirements for delivering MR
 2665 systems are generally similar to those associated with the delivery of other large items of
 2666 equipment. Sites should follow standard practice and recommendations for such deliveries.

2667 Typically, the [MR Installer](#) will organise and manage many of the aspects associated with the MR
 2668 scanner delivery. Specific points to consider include the following.

- 2669 • Structural capacity for delivery/exit route within the building
- 2670 • Structural capacity of the proposed location for the crane & all approvals to erect
- 2671 • Hospital approvals. Potential impact on any hospital services/other departments should
 2672 have been discussed well in advance, mitigations considered and plans agreed well in
 2673 advance of the proposed delivery date.
- 2674 • Council/other external approvals, e.g. any public road closures required for cranes to
 2675 remove/deliver the magnet should have been approved in advance by the local council.
 2676 Consider also requirements for any crane jib or load over-sail of property not under the
 2677 control or ownership of the main contract or its agents.
- 2678 • Forming delivery/exit apertures for MRI
- 2679 • Forming scaffold/platform for MRI exit/delivery

2680

2681 MR systems based on permanent magnets may pose additional logistical challenges for delivery in
 2682 terms of increased weight compared to superconducting magnets, as well as the permanent
 2683 magnetic field. Non-ferromagnetic alternatives may be required for many of the tools typically used
 2684 to rig the MR scanner. The benefit is that there are no cryogenics and therefore no need for quench
 2685 pipes or a continuous water cooling system. Typically, there is also only one cabinet that comes with
 2686 the system that requires power.

2687

2688

Real-world example: Late change in delivery route for MR scanner

Permissions for the original proposed delivery route were not obtained, and an alternative delivery route had to be arranged at short notice.

Impact: Additional cost

2689

2690 If included in the design, MR scanners should be placed on MR manufacturer approved anti-
 2691 vibration pads at their final location in the MR Examination room. Super-conducting MR systems will
 2692 require connection to the dedicated chilled water supply at delivery to ensure minimal helium boil
 2693 off.

2694

2695

2696 **5.3 MR scanner installation**

2697 The installation of the MR scanner will typically be performed dedicated MR installation engineers.
2698 They will generally be very experienced with the installation of MR systems and be able to manage
2699 appropriately any potential issues that might arise. Consequently, this section focuses more on a few
2700 issues that may be helpful for the [MR Responsible Organisation](#) to consider.

2701
2702 **Adjacent MR scanners at same field strength**

2703 In the event that an MR scanner is installed adjacent to another scanner operating at the same
2704 nominal static magnetic field strength, it is generally advisable for the MRI engineers to utilise the
2705 permitted windows of ramped up field strength to maximise the difference in final static magnetic
2706 fields between the two systems. This helps to avoid the potential for RF signal emitted by one MR
2707 scanner being detected by the other (and vice versa) and negatively impacting on the image quality.
2708 However, even when such a separation is performed, there may still be overlap in RF frequencies
2709 when MR images acquired with a high receiver bandwidth and image artefacts can result if RF cage
2710 performance is insufficient.

2711

Real-world example: RF interference from nearby MR scanner at same field strength

Two 3T MR scanners were installed with a shared MR control room. Although the MR scanners were ramped up with the appropriate separation of centre frequencies, intermittent external RF interference was observed on MR images with high receiver bandwidths. It was subsequently identified that the metal strip at the base of the MR Exam room door that formed the electrical connection with the door frame was missing. This had been removed after the RF cage was built and commissioned to avoid potential damage to this strip during the rest of the building work, but reattaching this had been missed.



Impact: reduced MRI quality until RF leaves reattached on MR Examination room door.

2712

2713

2714 **Confirmation of working remote monitoring**

2715 Sites are encouraged to seek confirmation from the [MR Installer](#)/MR manufacturer that any planned
2716 remote monitoring is working as expected. This is encouraged as soon as possible after the MR
2717 scanner is connected to the local IT network to help mitigate for problems that may arise out of
2718 hours, in particular any problems with the chilled water supply or a magnet quench.

2719

2720

Real-world example: Non-functioning remote monitoring system not followed up.

Remote monitoring of MR system was discovered to be partly/non-functional many months after installation had completed.

Impact: Increased consequences should problems have arisen with cooling for the MR system out of hours, potentially resulting in significant periods of downtime if system had quenched.

2721

2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763

2764
2765

MR system local IT configuration

Configuration of the MR system with regards local network connections (PACS, RIS worklist, other DICOM nodes) and remote monitoring is typically set up by the [MR Installer](#) in conjunction with the Trust PACS/IT team. Local sites are encouraged to confirm local IT configurations are completed as requested. This should include end-to-end testing to confirm a complete patient workflow, i.e. registering a test patient on the RIS, pulling details across to the scanner, scanning a test object and archiving images to PACS. Where specified, retrieval of MRIs from PACS should be confirmed. It may be helpful to confirm any changes in DICOM metadata when retrieving items from the PACS. Additionally, confirmation of MRI transfers to each specified DICOM node is recommended.

MR system commissioning

Following magnet delivery and installation the [MR Installer](#) will run a series of commissioning procedures and tests. These include shimming, tune up, quality assurance (QA) tests and coil QA. The MHRA recommend that the manufacturer or supplier provides written evidence that the equipment is compliant with the procurement specifications and their own performance specifications, and suggest it may be helpful for a hospital technical representative to be present during commissioning procedures.

Control of access

Prior to the magnet being ramped up it's important for the [MR Safety Expert](#) to liaise with the [MR Responsible Person](#)/lead MR radiographers to ensure designation of the [MR Controlled Access Area](#), appropriate display of MR Safety notices and that any personnel working in [MR Controlled Access Area](#) e.g. contractors, Estates staff undergo MR Safety screening. It is recommended that any areas within the [B₀ Hazard Area](#) outside of the MR suite or areas close to the quench pipe outlet are now classified as permit to work areas.

Typically, MRI installers will provide MR Safety signage as per recommendations in IEC 60601-2-33. However, local MR units & Medical Physics teams may prefer to utilise alternative/additional signage, e.g. IPEM MR-Safety Notices ([IPEM 2017](#)).

5.4 Ancillary equipment installation

Ancillary equipment is not always supplied in one process by the magnet installer, so this may arrive anytime during or sometimes post installation with other responsible parties for installation. It is important that any ancillary equipment is tested and labelled as [MR Safe](#), [MR Unsafe](#) or [MR Conditional](#) with conditions attached. Consider any services or enabling works that may be needed for such equipment within the overall project plan.

5.5 Summary & checklist

MR scanner delivery	✓
All approvals obtained for MR scanner delivery, including crane location, delivery route, any required road closures?	
All enabling works for MR scanner delivery completed, including formation of access route into the building and any required scaffolding?	
MR scanner placed on anti-vibration pads in MR Examination room?	
MR scanner connected to chilled water supply?	

MR scanner installation	✓
Separation of centre frequencies for adjacent MR scanners at same nominal field strength?	
Confirmation of fully operational remote monitoring from MR Installer /MR manufacturer?	
Confirmation of MRI IT configurations as specified?	
Confirmation from MR Installer of completed commissioning of MR system?	
Confirmation of working access control to MR Controlled Access Area ?	
Confirmation of installed additional MR Safety signage specified by MR Responsible Organisation	

2766

2767

Ancillary equipment installation	✓
All ancillary equipment (e.g. pump injector, infusion pump, GA machine etc.) commissioned and displays appropriate MR Safety labelling	


2768

2769

DRAFT

2770 **6 Acceptance (RIBA stage 6)**

2771



2772
2773
2774

2775 **6.1 Introduction**

2776 This section covers the acceptance phase of a new MRI installation. Acceptance testing covers the
2777 process of checking that the installation and the performance of the equipment are as expected. It is
2778 performed on behalf of the [MR Responsible Organisation](#) to inform a decision to accept the work
2779 and formally take on responsibility from the MRI manufacturer and/or installation provider.
2780 Additionally, acceptance testing provides baseline measurements for any subsequent checks, e.g. as
2781 part of regular quality assurance programme.

2782
2783 Discussions here are focussed on items that are considered to have additional/specific relevance for
2784 MR suites. For more general, non-MRI specific items, please refer to [HBN 06-01](#). For acceptance of
2785 the MR system, acceptance should only commence once the MRI manufacturer has completed the
2786 installation and commissioning of the MR system and believe it is ready for use. Ideally all building
2787 works should also have completed prior to acceptance testing.

2788
2789 Project teams are encouraged to plan for independent acceptance testing of the MR scanner by a
2790 suitably qualified MR physicist. There are many examples where despite the completion of MRI
2791 manufacturer’s own commissioning, items are inadvertently missed. Additionally, it is important to
2792 factor in an appropriate time into the project plan for acceptance testing.

2793
2794 This guidance does not include any recommendations on specific imaging acceptance checks. This is
2795 anticipated to be the subject of future work. In the meantime, the reader is referred to guidance on
2796 MRI QA, such as IPEM report 112 ([IPEM 2017a](#)).

2797
2798

2799 **6.2 Non-imaging acceptance test checks**

2800 A list of non-imaging acceptance test checks relevant to a typical MRI installation is provided below
2801 in Table 5. These should be considered in addition to items on the Build (4.7) and Installation (5.5)
2802 checklists that have not been completed.

2803

Check	Essential/ Possible	Suggested acceptance criteria
Delivery and commissioning of all ordered RF coils?		As ordered
Installation of all ordered software licences/packages?		As ordered
Confirmation that all commissioning work has been performed and has passed		All commissioning completed
Detachable Table undocks in emergency?	Essential if applicable	Undocks/redocks
MR Conditional Trolley	Essential if applicable	Present and labelled
Patient communication system	Essential	Functional
Patient alarm	Essential	Functional

Check	Essential/ Possible	Suggested acceptance criteria
RF Door opens/closes and locks	Essential	Checked
RF cat flap opens/closes easily	Essential if applicable	Checked
CCTV camera if installed as an extra	Possible	Installed and operational
Check extent of relevant fringe field values	Essential	B₀ Hazard Area does not extend into uncontrolled areas
Acoustic Noise	Possible	Noise levels acceptable in adjacent occupied spaces
RF Cage Attenuation check	Possible	RF Cage installers to demonstrate performance after full installation or independent check of RF cage performance. Copy of RF cage certificate supplied to local Physics team.
For MR systems with quench pipe: risk assessment for accessing locations to visually inspect the quench pipe outlet.	Essential	Checked
Manufacturer phantoms	Essential	Checked as present
Spill kit for phantoms Relevant COSHH forms completed	Essential	Checked as present
Power to auxiliary equipment available	Essential	Checked as functional
Music/video/lights	Possible	Checked as present and functional
Warning signs for entrances to MR Environment and MR CAA	Essential	
Display plots of relevant fringe fields associated with static magnetic field	Essential	
MR Safety labelling of devices/ancillary equipment	Essential	Checked as present with correct conditions on label
Floor markings of magnet field isocontours for MR Conditional ancillary equipment	Possible	
Systems of work for roof/basement	Essential where required	Written/signed off
Medical gases - prep area and MR Examination room. Scavenging outlet- all tested and signed off by medical physics/estates/gas specialist and commissioned.	Essential if applicable	Checked as present and functional
Policy for out-of-hours emergency access lodged with Security/Fire Department	Essential	Policy written and signed off
MR Safe/MR Conditional ladders in technical room	Essential	Checked as present
Display panels in control room wall for oxygen sensor/chilled water flow/chilled water temperature and phase fault errors	Essential	Checked as present

Check	Essential/ Possible	Suggested acceptance criteria
Appropriate labelling next to all display panels/alarms. This may include the following descriptions. <ul style="list-style-type: none"> • What is it. • What is expected if working as intended, e.g. no alarm, normal range of values. • Who and to contact if alarming/outside expected values, and how to contact them. 	Essential	Checked as present
MR Examination room temperature and humidity monitor.	Essential	Checked as present
Quench buttons	Essential for superconducting MR system	Present and confirmed functional by manufacturer
Emergency power off buttons	Essential	Checked as present
All emergency buttons/ features labelled (what is it?, if values are displayed, what values are expected (e.g. for humidity levels)?, who to contact if alarming/outside expected values?)	Essential	Checked as present
Patient Lockers	Essential	Checked as present and functional
Liaison/visits with other teams who may need to access MR Controlled Access Area to explain safety <ul style="list-style-type: none"> - Resuscitation - Security - Domestic Services - Fire Brigade 	Essential as required	Done
MR Conditional ladders in technical room	Essential	Checked as present
MR Conditional Fire Extinguisher	Essential	Present, checked as MR Conditional and labelled

2804
2805


Table 5. List of non-imaging acceptance test checks relevant to a typical MRI installation.

2806
2807
2808
2809
2810

Once the magnet has been installed, commissioned and acceptance tested, all building works including final touches have been completed, and reports/evidence has been submitted to the project team and Trust then the scanner and building can be handed over to the Trust.

2811 7 Use (RIBA stage 7)

2812



2813
2814

2815 7.1 Introduction

2816 This section covers the use of the new MRI installation, from when it is formally accepted and lasting
2817 for the lifetime of the system. Those involved in Facilities and Assets Management support the users
2818 of the MRI department and there should be close working relationships with the [MR Responsible](#)
2819 [Person](#) and the [MR Safety Expert](#) throughout the lifetime of the building.

2820

2821

2822 7.2 Policies and procedures

2823 The [MR Responsible Organisation](#) should have appropriate policies and procedures in place to
2824 support safe working practices within the MR suite and ensure high quality services. Various
2825 guidance and resources are available to support on this, including the following.

- 2826 • MHRA guidelines for MRI safety ([MHRA 2021](#))
- 2827 • SCoR-BAMRR guidelines for safety in MRI ([SOR-BAMRR 2019](#))
- 2828 • A list of all SCoR guidance covering MRI ([SoR](#))
- 2829 • Quality Standard for Imaging ([CoR-RCR 2024](#))

2830

2831 The MHRA also provide guidelines on the management of medical devices more generally ([MHRA](#)
2832 [2021a](#)).

2833

2834 Regular audits of current practice against local policies and procedures, and additionally of local
2835 policies and procedures against national guidance, are encouraged to help ensure up to date high
2836 quality and safe working practices. Audits are considered to be one of the seven pillars of clinical
2837 governance.

2838

2839

2840 7.3 Preventative maintenance.

2841 Regular preventative maintenance and servicing of the MR scanner and supporting plant is key to
2842 addressing issues in a timely manner, ideally before they impact on the MRI service. There are
2843 various examples, particularly with chillers and other supporting plant, where a lack of appropriate
2844 preventative maintenance has resulted in failures that have led to significant downtime of the MR
2845 scanner.

2846

2847 A plan for how service engineers will access certain areas when on site, e.g. [MR Controlled Access](#)
2848 [Area](#), MR Tech room, chillers, AHU, to allow them to carry out their work should be implemented.
2849 Co-ordination of preventative maintenance visits may be helpful to minimize impact on the MRI
2850 service, e.g. arranging for chiller service visits (that may require periods of chiller downtime) to
2851 coincide with MR system service visits.

2852

2853 Chillers

2854 As part of business continuity planning, sites may wish to consider options to hire a temporary chiller
2855 to support the MR system, particularly if there is no back up option.

2856

2857

Real-world example: Mobile chiller hire

Following breakdown of the chiller support for the MR system, a temporary chiller was hired. This was delivered and installed within a few hours, allowing the MR system to be used.

Impact: MRI downtime limited to a few hours

2858

2859 [MR Examination room doors](#)

2860 A preventative maintenance programme associated with the MR Examination room door is
2861 recommended to help avoid various issues that include the following.

- 2862
- 2863 • Repairing of broken RF leaves to maintain RF cage integrity ([Small et al. 2026](#))
 - 2864 • door mechanisms latches and locks are in full working order, reducing the risk of patients and
2865 staff becoming trapped within room ([Steckner et al. 2026](#))
 - 2866 • doors becoming overly difficult to open and close, which may present a manual handling risk
2867 ([Steckner et al. 2026](#)). Additionally, this may result in practices where the MR Examination room
2868 door is not appropriately closed during MRI scanning which may result in external RF
2869 interference impacting image quality.

2870 Periodically cleaning the RF leaves and magnet door frame with alcohol-based wipes can help reduce
2871 residue build up that may impact on electrical contact and RF cage performance. One of the RF cage
2872 manufacturers recommending cleaning the door frame around every 2 months for maximum
2873 performance.

2874

2875

Real-world example: RF cabin door hard to open/close.

Broken door handles due to MR Examination room RF door slamming. Poor MR image quality due to MR Examination room door not completely closed during scans

Impact: additional costs and poor image quality

2876

2877

2878 [Non-ferromagnetic fire extinguishers](#)

2879 If the servicing of non-magnetic fire extinguishers within the MR suite is incorporated into a site-
2880 wide servicing programme, care should be taken to ensure that there is a clear recognition of any
2881 non-ferromagnetic extinguishers and the need to maintain them as non-ferromagnetic.

2882

Real-world example: Fire extinguishers within MR suite were not sufficiently identified as non-ferromagnetic as part of hospital-wide servicing programme.

Non-ferromagnetic fire extinguishers within the MR suite were inadvertently swapped out for standard ferromagnetic fire extinguishers as part of a site-wide servicing programme for fire extinguishers within the hospital.

Impact: the introduced conventional ferromagnetic fire extinguishers presented a significant projectile risk if taken into the [MR Environment](#).

2883

2884 [Generator testing](#)

2885 For MR systems on generator supported secondary power supplies it is highly recommended to plan
2886 for planned generator testing. A sudden loss of power to the MR system can result in errors that can
2887 subsequently lead to significant down time. In 2022, there were 3 cases of generator testing
2888 impacting on MRI reported to NRLS.

2889

2890

2891 [Quench pipe inspections](#)

2892 The MHRA guidelines for MRI safety recommend annual inspections of all vent piping. This should
2893 include, at least, a visual inspection of the external piping. Additionally, the quench pipe outlet
2894 should be visually checked after periods of extreme weather. Responsibility for checks on the
2895 quench pipe sits with the [MR Responsible Organisation](#).

2896

2897 Specific recommendation on steps to perform following installation are provided in the Installation
2898 section to establish a baseline. The following steps are recommended to be taken on an annual
2899 basis, which may form part of a more general MR Safety audit.

- 2900 • Review and update as required any risk assessment for accessing locations to visually inspect
2901 the quench pipe outlet.
- 2902 • Perform a visual inspection of the quench pipe outlet, taking photographic evidence of the
2903 following to check/confirm no changes since previous check.
 - 2904 ○ Access to quench pipe outlet is appropriately controlled
 - 2905 ○ No obstructions to the quench pipe outlet
 - 2906 ○ No changes to any rain covers/protective mesh
 - 2907 ○ No changes to signage
 - 2908 ○ No changes to area below the quench pipe outlet that might increase the risk of
2909 exposure to cryogenic gases in the event of an MRI quench.
- 2910 • Perform a visual inspection of as much of the quench pipe as is practical to do so, taking
2911 photographic evidence of the following to confirm no change since installation
 - 2912 ○ Insulation
 - 2913 ○ Hazard warning tape

2914

2915 [Emergency ramp down unit](#)

2916 The magnet emergency run-down unit (emergency quench button) will usually contain a backup
2917 battery. Some MR manufacturers provide users with the ability to periodically check this backup
2918 battery.

2919

2920 [Drip trays](#)

2921 Ideally any drip trays that are installed, e.g. in tech room, will be installed with a direct connection to
2922 drain. If this is not the case, then periodic checks of trays are recommended to avoid overspilling.

2923

2924 [Oxygen monitors](#)

2925 Conventional oxygen monitors are based on an electrochemical sensor that typically starts to fail
2926 after about 2 years, at which point a low oxygen state will be triggered. Regular replacement of the
2927 oxygen sensor as part of a preventative maintenance is therefore key to avoiding false alarms.
2928 Servicing of oxygen monitors should be performed by qualified individuals.

2929

Real-world example: Automatic trigger of emergency extract inadvertently disabled when oxygen monitor serviced by a non-trained individual.

The chemical sensor for an oxygen monitor was replaced by a member of staff, who inadvertently disabled the automatic trigger of the emergency extract fan when the oxygen alarm was triggered.

Impact: MR suite was operating for an extended period of time with no automatic trigger of emergency extract when low oxygen alarm triggered, impacting the health and safety of staff and patients. Subsequently servicing of the oxygen monitor was contracted out to specialist company.

2930

2931 Confirmation of a working automatic trigger of the emergency air extract for the MR Examination
2932 room is recommended as part of preventative maintenance checks.

2933

2934 It may be helpful to procure a portable oxygen sensor for an MR suite to utilise in the event of a
2935 suspected false oxygen alarm.

2936

2937

2938 7.4 Changes within the MR suite

2939 The [MR Responsible Person](#) should be included in the procurement of any new equipment for the
2940 MR suite. Some items of [MR Conditional](#) ancillary equipment may require modification of the MRI
2941 MR Examination room floor to demarcate areas of high magnetic field where the device may not
2942 enter. Tethers may also be required to limit movement in the MR Examination room. Some [MR](#)
2943 [Conditional](#) equipment requires testing in the MR scanner sound while the scanner is imaging to rule
2944 out mutual interference. Advice should be sought from the [MR Safety Expert](#).

2945

2946 If a change of usage of the MRI department is proposed, e.g., anaesthetics, paediatrics,
2947 compartmentalisation of MRI department to limit aerosol producing procedures (COVID-19), MR-
2948 guided biopsy, radiotherapy, MR-autopsy, etc... a detailed plan should be formulated with all the
2949 relevant parties consulted.

2950

2951

2952 7.5 Changes outside the MR suite

2953 Changes near the new MR suite can have negative impact on the functionality of the MR scanner.
2954 The movement/installation of large ferromagnetic items (e.g., cranes, scaffolding, new lifts, air
2955 ambulance) nearby can alter the highly homogeneous magnetic field of the MR scanner, potentially
2956 affecting patient images.

2957

2958 Installation of other equipment in the vicinity (both in-floor and through-floor) should also be
2959 carefully considered as they may have a sensitivity to elevated magnetic fields (e.g., gamma camera,
2960 fluoroscopy systems, cyclotrons, linear accelerators, CT scanners, other MR systems). Magnetically
2961 guided surgical equipment may require installation more than 30m distance from an MR scanner.

2962

2963 It is important to maintain an access route to the MR scanner for servicing that can accommodate
2964 the replacement/delivery of large items such as a gradient coil and helium dewars. For conventional
2965 superconducting MR systems, in the event of a magnet quench it is typically important for a helium
2966 refill to occur as soon as possible to avoid the magnet warming up the point where a thermal cycle is
2967 required. This is particularly important for 3T and higher field systems. One MR manufacturer
2968 reports a 24-hour window of opportunity to deliver helium to stabilise a 3T system and avoid a
2969 thermal cycle.

2970

Real-world example: Access route to MR scanner for servicing not maintained

When a gradient coil on an MR scanner needed replacing, it was found that building work outside the MR suite that had occurred after the MR system was installed had restricted physical access, leaving insufficient space to remove and replace the coil.

Impact: Additional building work required to restore access for replacement of gradient coil

2971

2972

2973 Any building changes in the vicinity of the quench pipe outlet should first be discussed with the [MR](#)
2974 [Responsible Person](#). Air intakes, doors and windows are a particular concern. Workers in this region
2975 should be aware of cryogen hazard and know how to respond in the event of a quench. Following
2976 any quench, a thorough inspection of the cryogen vent system should be conducted prior to
2977 returning the MR scanner back to service. Any modifications of quench pipe system may be subject
2978 to the Pressure Systems Safety Regulations (2000). Close consultation with the [MR Safety Expert](#) and
2979 the [MR Responsible Person](#) is strongly recommended when any changes are proposed within or in
2980 the vicinity of the MRI department or quench pipe.

2981
2982 Finally, it is important to consider maintaining options for future removal/replacement of the MR
2983 scanner, including the locations where a crane or scaffold are placed to enable this change.
2984
2985

2986 7.6 Adverse incident reporting

2987 A structured incident reporting system is important to enhance MRI patient safety by strengthening
2988 the overall safety culture and providing staff with a reliable mechanism to document adverse
2989 incidents, near misses, and unsafe conditions. Reliable incident reporting depends on a strong
2990 organisational reporting and learning culture. It also requires standardised methods for reviewing
2991 and coding incidents, timely feedback to staff on outcomes and lessons learned and follow-up, to
2992 ensure that corrective actions are fully implemented. Learning from analysis can be shared to
2993 promote system-wide learning with a focus on processes rather than individual blame. This in turn
2994 can help to drive continuous improvement through updates to policies and procedures, training, and
2995 system design. By consistently reviewing and learning from incidents, MRI services can create a safer
2996 environment for both patients and staff.

2997
2998 Services are encouraged to adopt the UKHSA national coding taxonomy for MRI-related incidents
2999 and near misses ([UKHSA 2024](#)). Using a single, standardised coding framework allows services to
3000 identify system-level issues, reduce variability, and enhance safety strategies across MRI practice.
3001 Further information on submitting data to the national incident learning system can be found on the
3002 Medical Exposures Group [webpage](#). Submitting coded MRI incident data to UKHSA will contribute to
3003 the following.

- 3004 • A national overview of MRI safety events
- 3005 • Enable services to benchmark their own trends
- 3006 • Development of effective, evidence-based improvements across the sector

3007 This is a voluntary incident learning system and does not negate the legal requirement to report to
3008 the relevant regulatory authorities.
3009
3010

3011 7.7 Replacement/decommissioning

3012 A route for eventual replacement of the MR system should be maintained as part of the building
3013 maintenance strategy, typically authored by the architects, and the site development control plan.
3014 This should include all aspects of the replacement, e.g. crane placement.
3015

Real-world example: replacement route for MR scanner not maintained.

The original route for transferring the magnet into the building was not protected. When it came to subsequently replace the MR scanner, a new route had to be established requiring removal and subsequent replacement of section of the hospital façade.

Impact: about £70K of additional costs

3016

3017
 3018 The MHRA’s guidance on the management of medical ([MHRA 2021a](#)) provides advice regards
 3019 planning for device replacement and eventual decommissioning and disposal. These include
 3020 suggestions for replacement criteria, appropriate secure deletion of any patient identifiable data and
 3021 guidance on potential sale of medical device or donation for reuse. Global Health Partnerships, a UK
 3022 charity and international development organisation, also provide UK-specific guidance on medical
 3023 equipment donations ([Mullally S, 2013](#)).

3024
 3025 The MR manufacturer may be able to provide information about the current performance of an MR
 3026 system relevant to considerations about replacement/upgrade. This may include metrics on how
 3027 performance has changed during the lifetime of the system, as well as comparisons with similar
 3028 systems and with new generations of MR scanner.

3030 7.8 Summary & checklist

3031

Policies and procedures	✓
Local policies and procedures in place?	
Regular audits?	

3032
 3033

Preventative maintenance	✓
Preventative maintenance in place for the chillers?	
Preventative maintenance in place for the MR Examination room door?	
Non-ferromagnetic fire extinguishers are appropriately recognised in any site-wide servicing programme?	
Annual inspection of all MRI quench pipes?	
Periodic check of magnet quench backup battery (if applicable)?	
Periodic check of any drip trays not connected to drain?	
Preventative maintenance in place for oxygen monitors?	

3034
 3035

Changes within the MR suite	✓
MR Responsible Person included in the procurement of any new equipment for the MR suite?	

3036
 3037

Changes outside of the MR suite	✓
Access route to MR scanner for servicing is maintained?	
Access route for future removal/replacement of the MR scanner is captured as part of long-term site plan to ensure this is considered when any building projects are planned that may impact on the MR scanner or be impacted by the MR scanner?	

3038
 3039

Adverse incident reporting	✓
Adoption of UKHSA national coding taxonomy for MRI-related incidents and near misses?	

3040
 3041

Replacement/decommissioning	✓
Replacement of the MR system is maintained as part of the building maintenance strategy, and the site development control plan?	

3042 8 Examples

3043

3044 “Fly on the wall” accounts of two MRI installation projects are provided here as examples of firstly,
3045 what was considered to be a good example, where the project was well organised and progressed
3046 smoothly, and secondly an example where several issues were identified in hindsight.

3047

3048 8.1 Example 1

3049 This Fly on the Wall account is for an installation of a replacement MR scanner where the project
3050 progressed smoothly. The project team included Project Manager, Head of Radiology, Trust Project
3051 Manager for Estates, MRI Lead Radiographers, representatives from Clinical Engineering, MRI
3052 Physics, MRI manufacturer, building contractors and a company who had recently installed a new
3053 façade to the hospital. The PACS team were also consulted.

3054

3055 **September**

3056 There was a slight delay in getting the Turnkey orders on the procurement system but the
3057 manufacturer had now received the order and the project management team (external to Trust)
3058 were putting a programme together for the replacement of an existing MR scanner.

3059 **October**

3060 • A provisional programme, including a Gantt chart and proposed plan of the MR Suite, had
3061 been issued subject to confirmation of dates for the (expensive) removal and reinstatement
3062 of a Façade on the front of the hospital. This was required to remove the existing MR
3063 scanner from the second floor and deliver the new MR scanner once building works had
3064 progressed. MRI Physics queried the change to an inward opening door to the scanner room
3065 on the proposed plan. However, the direction of the RF door swing couldn't be revised as
3066 previously requested and shown on the manufacturer's drawing, as the vaulted ceiling soffit
3067 outside the MR Examination room would obstruct the door opening. Options for pressure
3068 relief and escape provision were to be explored.

3069 **Late October - Pre-commencement Meeting Part 1**

3070 The first of several virtual meetings had been scheduled. Attendees included Project Manager, Head
3071 of Radiology, Trust Project Manager for Estates, MRI Lead Radiographers, representatives from
3072 Clinical Engineering, MRI Physics, MRI manufacturer, building contractors and the façade company.

3073 On the Agenda:

- 3074 • Cladding Enabling Works and Programme
- 3075 • Order/Lease – provisional sums for medical gases, fire alarm works, nurse call, chiller
3076 replacement, ceiling lighting panels/mood lighting, ventilation works and new injector.
- 3077 • Contract Dates and Contract Documentation – building works contracts & cash flow forecast
3078 to be issued
- 3079 • Vacant possession of site and scanner removal survey – dates for erection of scaffolding and
3080 clearing of site
- 3081 • Programme/Progress
- 3082 • Detailed design – surveys undertaken, direction of scanner room door swing (inward)
3083 discussed
- 3084 • Approval of Layouts – dates for final system layout drawings
- 3085 • Insurances – manufacturer and contractors insurance details to be issued
- 3086 • Planning and Building Regulations
- 3087 • Fire Office Comments – confirmation of no compartment walls in MR Suite

- 3088 • MRI Physics – RF cage test and proposed commissioning dates
- 3089 • Infection Control Measures - details of infection control lead to be shared
- 3090 • CDM regulations – F10 required and to be issued by building contractor. Contractor rules,
- 3091 permits, isolation induction requirements and other site considerations to be issued. Fire
- 3092 heat detectors (not smoke) to be fitted for duration for works. Construction Phase (H&S)
- 3093 Plan to be issued prior to commencement
- 3094 • Site Rules and Restrictions – to be issued
- 3095 • Access to Site, Storage, Security, Site Compound and Access to Live Hospital Areas - not
- 3096 discussed
- 3097 • Emergency Contact Numbers - to be included in Project Directory and contractor
- 3098 information pack.
- 3099 • Cessation of Work – key staff identified and procedures discussed
- 3100 • Distribution of Documentation – staff circulation list identified
- 3101 • Any Other Business
- 3102 • Date of Next Meeting

3103

3104 **Early November - Pre-commencement Meeting Part 2**

3105 The second virtual meeting had been scheduled. Attendees included Project Manager, Head of
 3106 Radiology, Trust Project Manager for Estates, MRI Lead Radiographers, representatives from Clinical
 3107 Engineering, MRI physics, MRI manufacturer, building contractors and the façade company.

3108 On the Agenda:

- 3109 • Site/survey - visit being arranged, liaising with Trust Estates
- 3110 • Cladding removal – manufacturer to arrange ramping down mid-November. Building
- 3111 contractors to arrange delivery of scissor lift. Storage of cladding material to be discussed
- 3112 • Layout drawings – extent of [B₀ Hazard Area](#) noted and accepted. No requirement for
- 3113 additional steel shielding.
- 3114 • Electrical drawings to be issued, mains supply to MR suite and scanner and cabling discussed
- 3115 • Mechanical design – survey on dates confirmed. Chiller position, routes and requirements
- 3116 for chiller swap discussed. Replacement of the existing ventilation/air conditioning serving
- 3117 the MR suite but power supply to be reused. Drawings to be issued.
- 3118 • RF cabin – checking with supplier re pressure relief options
- 3119 • Trust Estates to issue standard contractor’s pack
- 3120 • Head of Radiology has issued project reference number for use on all communications
- 3121 • RF cabin delivery date confirmed. Check size of delivery vehicle in advance.
- 3122 • Internal wall being removed as part of the Technical Room – although identified as non-load
- 3123 bearing it also appears to be reinforced concrete, so it is necessary to assess how quickly this
- 3124 can be removed and the amount of disruption. Neighbouring team to be made aware of
- 3125 likelihood of disruption.

3126

3127 **Late November**

- 3128 • Electrical design drawings and architectural designs have been issued for comment and
- 3129 approval. Clarity requested for:
 - 3130 1. Suspended ceiling type and tile
 - 3131 2. Door type and finish plus ironmongery
 - 3132 3. Laminate finishes for fitted furniture and worktops etc.
 - 3133 4. Floor finishes – type and colour reference
 - 3134 5. Paint finishes – type and colour reference

3135

- 3136 • MRI Physics to review the field plots and confirm if they look acceptable and give thoughts
3137 to any additional MR Safety Notices required.
3138
- 3139 • Exception report required for injector as whole life costs are more expensive than originally
3140 budgeted for.

3141

3142 **Early December - Progress Meeting 1**

3143 The first progress meeting is held. Attendees include Project Manager, Head of Radiology, Trust
3144 Project Manager for Estates, MRI Lead Radiographers, representatives from Clinical Engineering, MRI
3145 Physics, MRI manufacturer, building contractors and the façade company

3146 On the Agenda:

- 3147 • Matters Arising from Previous Minutes
- 3148 ○ Scaffolding and site accommodation is in place.
 - 3149 ○ MRI platform design for magnet removal being double checked by scaffolder and
3150 verified by structural engineer.
 - 3151 ○ Deadline for energising of a fully terminated and tested electrical supply being
3152 provided by the Trust identified.
 - 3153 ○ Contract sums issued.
 - 3154 ○ RF cabin design will be updated following survey
 - 3155 ○ Cash flow forecast issued
 - 3156 ○ No issues reported with site establishment
 - 3157 ○ Manufacturer & contractor latest insurance details issued
 - 3158 ○ Electrical designs issued, comments received relating to emergency lighting to be
3159 addressed.
 - 3160 ○ RF cabin test dates to be advised
 - 3161 ○ Medical Physics acceptance testing dates to be shown on project programme
 - 3162 ○ Copy of F10 (HSE project approval) form to be displayed on site
 - 3163 ○ Personnel inductions to be done by Trust Estates before undertaking site specific
3164 inductions
 - 3165 ○ New H&S file to be issued at project completion
 - 3166 ○ Trust's contractor rules document issued
 - 3167 ○ Asbestos information has been issued. Extent of survey to be reviewed against
3168 finalised mechanical services specification
 - 3169 ○ Internals walls have been evaluated, and non-percussive methods are to be utilised
3170 for concrete cutting.
 - 3171 ○ Further site survey of mechanical services has taken place
 - 3172 ○ Mechanical design – to be issued for comment and further revised when chilled
3173 water scope is agreed.
- 3174 • Contractor's Report – issued and attached to minutes of meeting
 - 3175 • Contractor's Queries and/or Requests for Information- Finishes samples to be delivered to
3176 site this week for selection
 - 3177 • CDM Regulations - safety audits and copies of all reports requested
 - 3178 • Any Other Business - site visits confirmed, social distancing to be observed.

3179

3180 **Mid-December**

- 3181 • Site survey completed and RF cabin drawings updated
- 3182 • Air flow test report issued

- 3183
- 3184
- Pressure relief panels to be installed in the MR scanner room ceiling. Design to meet MHRA Guidelines for MR equipment manufacturers protections which are: -
- 3185
- the cryogen ventilation path (quench vent),
- 3186
- an active emergency extract fan,
- 3187
- a passive overpressure relief (exclusive of the RF door), built into MR installation requirements.
- 3188

3189

3190 **Early January - Progress Meeting 2**

3191 The second progress meeting was held. Attendees included Project Manager, Head of Radiology,
3192 Trust Project Manager for Estates, MRI Lead Radiographers, representatives from Clinical
3193 Engineering, MRI Physics, MRI manufacturer, building contractors and the façade company

3194 On the Agenda:

- 3195
- Matters Arising from Previous Minutes
- 3196
- Dates for cladding reinstatement to be confirmed
- 3197
- Scaffolding has been removed
- 3198
- Scanner delivery date confirmed. Survey to be arranged and RAMS to be issued.
- 3199
- Electrical report was issued, review concluded new mains cable and earth are necessary – to be arranged by the Trust
- 3200
- Revised scope of chilled water works to include removal and offloading of existing chiller and installation of new chiller to serve the MR scanner being delivered in this phase has been instructed.
- 3201
- Detail regarding the scope of ventilation works was issued earlier this year and subsequently reissued. Further detail for HTM derogation to be provided.
- 3202
- Response provided to Estate’s comments regarding emergency lighting in the MR Examination room. There is no [MR Safe](#) DALI emergency lighting system which could be installed within the room. Agreed to check the Trust specification document to ensure compliance the system will be BS and Building Regulations compliant; to be reflected on the derogation schedule as necessary. Manual test will be provided in lieu of DALI self-checking system
- 3203
- RF cabin test dates to be advised with a few days’ notice, expected next week.
- 3204
- Finishes samples selected on site and reflected on the latest architectural drawings included the 20mT flooring demarcation instructed.
- 3205
- Copies of site safety audit reports requested.
- 3206
- Contractor’s Report
- 3207
- Works currently on schedule for system delivery
- 3208
- Request for a Building Control application was clarified as being in respect of the cladding reinstatement, which was noted as being like-for-like with the existing. Application to be made
- 3209
- Penetrations to be properly stopped, including those through the floor slab. To be photographed and recorded.
- 3210
- Detail on who is providing fire stopping and fire dampers
- 3211
- Finishes sub-contractors to be appointed.
- 3212
- Contractor’s Queries and/or Requests for Information
- 3213
- Fire compartmentation and damper positions becoming crucial
- 3214
- MRI Manufacturer
- 3215
- Scanner delivery RAMS to be issued
- 3216
- MR scanner is within the UK.
- 3217
- No BMS links being provided. Trust requirements to be checked.
- 3218
- Fire dampers will need to be connected to fire alarms
- 3219
- 3220
- 3221
- 3222
- 3223
- 3224
- 3225
- 3226
- 3227
- 3228
- 3229
- 3230
- 3231

- 3232 ○ Access for drainage connections to adjacent rooms to be arranged with the
- 3233 department.
- 3234 ● Any Other Business
- 3235 ○ Complaint regarding exhaust position of welfare generator has been addressed by
- 3236 shielding/cowl.
- 3237 ● Access to fire/smoke dampers will be afforded from outside the MR Examination room.

3238

3239 **Mid-January Progress Meeting 3**

3240 The third progress meeting was held. Attendees included Project Manager, Head of Radiology, Trust
 3241 Project Manager for Estates, MRI Lead Radiographers, representatives from Clinical Engineering, MRI
 3242 Physics, MRI manufacturer, building contractors and the façade company

3243 On the Agenda:

- 3244 ● Matters Arising from Previous Minutes
- 3245 ● Dates for cladding reinstatement confirmed
- 3246 ● Scanner delivery date confirmed. Survey date to be confirmed
- 3247 ● Scanner mains electrical cable installation (under Trust instruction) is pulled, awaiting
- 3248 connection and testing which is required most urgently to prevent delay.
- 3249 ● RF door (post Brexit) is being held in customs, to be released late January
- 3250 ● Revised scope of chilled water works is underway. RAMS to be issued for chiller delivery
- 3251 ● HTM derogation reports have been issued and circulated. Will chase sign-off.
- 3252 ● Electrical design review highlighted a request to replace the local power DB within the
- 3253 Control Room, this is included in the budget costs discussed
- 3254 ● Proposed injector installation date discussed
- 3255 ● Proposals in respect of emergency lighting within the Examination Room were further
- 3256 discussed since the last meeting and formalised within the derogations report.
- 3257 ● RF cabin test delayed due to RF door not being on-site
- 3258 ● MRI Physics acceptance dates - early March
- 3259 ● Site dilapidation inspection was undertaken on the date of the previous meeting. No
- 3260 significant issues were recorded although a minor repositioning of the chilled water
- 3261 pipework was assessed.
- 3262 ● Mechanical design drawings have been issued for comment and include previously
- 3263 instructed works. Updated drawings to be issued shortly to include additional fire damper
- 3264 works. No comments received in response to the designs, any further changes requested
- 3265 now will result in delays.
 - 3266 ○ Survey of pipework in Control Room was undertaken and the pipes were confirmed
 - 3267 as redundant, one has been removed one as the other is close to the wall and does
 - 3268 not obstruct circulation. Fire-stopping to complete.
 - 3269 ○ Copies of site safety audit reports requested.
 - 3270 ○ Interpretation of existing fire compartmentation was issued for comment. Fire
 - 3271 officer responded to request compartmentation of the MR suite, with
 - 3272 acknowledgement the RF door and window are not fire rated installations. Feedback
 - 3273 is awaited from Trust Fire Officer regarding the suitability of the existing Control
 - 3274 Room doors, which appear to be fire doors.
 - 3275 ○ Although scanner delivery date is due to be maintained, it was highlighted there will
 - 3276 likely be fire stopping and ventilation works ongoing afterwards which may impact
 - 3277 on clinical service
 - 3278 ○ Fire-stopping will include floor penetrations.
 - 3279 ○ All finishing trades now appointed.
 - 3280 ○ Need to clarify any BMS expectations.

- 3281 ○ Check with mechanical installers any need to access adjacent areas to complete
- 3282 plumbing connections and coordinate with local staff accordingly.
- 3283 ● Contractor's Report
- 3284 ○ Works currently on schedule for system delivery
- 3285 ○ RF cabin installation has progressed well, except for the door delay
- 3286 ○ Out of hours works for chiller pipework are underway
- 3287 ○ Internal doors on site
- 3288 ○ Vinyl flooring works being rescheduled to better coordinate completion of RF cabin and
- 3289 ceiling, to allow for ductwork changes associated with fire dampers.
- 3290 ○ Delay due to fire protection works to be established.
- 3291
- 3292 ○ Contractor's Queries and/or Requests for Information
- 3293 ○ As above
- 3294 ● Manufacturer
- 3295 ○ Trust confirmed no additional purchase orders have been raised against this project
- 3296 at present. To be monitored.
- 3297 ● Employer's Matters
- 3298 ○ Scanner delivery date confirmed
- 3299 ● CDM Regulations
- 3300 ○ No incidents to report
- 3301 ○ A number of complaints and warnings have been made regarding contractors
- 3302 parking around the site. Trust security will be issuing parking tickets
- 3303 ● Any Other Business
- 3304 ○ Next building works valuation being processed in the coming week
- 3305

3306 **Late January**

3307 The RF cage was installed, and the RF test results issued. Outside (RF cabin) reference levels were
 3308 taken, and the RF cabin was tested at frequencies of 15, 63 and 128 MHz at the scanner room door,
 3309 control room window and penetration panel.

3310 *February*

3311

3312 **Early February -Progress Meeting 4**

3313 The 4th progress meeting was held. Attendees included Project Manager, Head of Radiology, Trust
 3314 Project Manager for Estates, MRI Lead Radiographers, representatives from Clinical Engineering, MRI
 3315 Physics, MRI manufacturer, building contractors and the façade company

3316 On the Agenda:

- 3317 ● Matters Arising from Previous Minutes
- 3318 ● Dates for cladding reinstatement confirmed. Scaffold will not be present. RAMS to be
- 3319 checked and reissued
- 3320 ● Scanner delivery date confirmed. Manufacturer visiting site today to re-issue updated
- 3321 delivery RAMS
- 3322 ● Scanner mains electrical cable installation (under Trust instruction) has been connected and
- 3323 tested. Manufacturer needs test certificate for delivery.
- 3324 ● Medical gases works on track, pharmacist input being arranged
- 3325 ● RF door is fitted, test certificate to follow. Cage modifications being made to facilitate
- 3326 damper works, retest date to be confirmed

- 3327 • Need building contractors feedback on Control Room door fire rating
- 3328 • Chiller delivered, pipework and commissioning ongoing
- 3329 • Injector installation date confirmed
- 3330 • HTM derogation reports have been issued, signed off and deemed closed
- 3331 • MRI Physics access confirmed and manufacturer programme has been circulated
- 3332 • New H&S file to be issued at project completion
- 3333 • Mechanical design drawings have been issued for comment and include all instructed works.
- 3334 No further Trust or Fire Officer comments received in response to the designs
- 3335 • Survey of pipework in Control Room was undertaken and the pipes were confirmed as
- 3336 redundant. Fire stopping to penetrations, walls and works to fire dampers/ductwork
- 3337 underway
- 3338 • Copies of site safety audit reports issued
 - 3339 ○ Fire compartmentation works are underway. One damper is above the RF cabin, so
 - 3340 an access hatch has been formed. Access will not be possible once scanner is
 - 3341 ramped to field,
 - 3342 ○ Mechanical installers have been working evenings to minimise any impact on
 - 3343 department. No issues to report
 - 3344 ○ Valuation due shortly, any splits between additional purchase orders to be advised
- 3345 • Contractor's Report
 - 3346 ○ Works have been focussed on preparation for damper installations following the last
 - 3347 meeting
 - 3348 ○ RF cabin ceiling to be completed once ductwork is fitted
 - 3349 ○ Cable containment being completed later this week following RF cabin ceiling
 - 3350 ○ Chiller being commissioned this week
 - 3351 ○ Pre-delivery inspection date/time confirmed
 - 3352 ○ Access to decorate Control Room being managed locally
 - 3353 ○ Site hoardings and temporary screens working well in shared control room
 - 3354 ○ Instruction given to provide new vinyl flooring to the Control Room
 - 3355 ○ MR lead radiographer to confirm changes to Control Room furniture
 - 3356
 - 3357 ○ Contractor's Queries and/or Requests for Information
 - 3358 ○ Nothing further to report.
- 3359 • Manufacturer
 - 3360 ○ Magnet is in storage, collection date confirmed
- 3361 • Employer's Matters
 - 3362 ○ Site inspections to be made prior to closing ceilings
 - 3363 ○ Damper demonstrations to be provided
 - 3364 ○ Scanner delivery date confirmed
 - 3365 ○ CDM Regulations
 - 3366 ○ No incidents to report
- 3367 • Any Other Business
 - 3368 ○ None to report
 - 3369

3370 **Mid –February**

3371 Pre and post MR scanner delivery RF cabin attenuation tests and RF cabin installation and
 3372 completion report issued. Outside (RF cabin) reference levels were taken, and the RF cabin was
 3373 tested at frequencies of 15, 63 and 128 MHz at the scanner room door, control room window and
 3374 penetration panel. All attenuation measurements were within the manufacturer specifications.

3375

3376 **Early March - MRI Physics Commissioning/Acceptance Testing**

3377 With installation complete commissioning /acceptance testing was performed by the MRI Physics
3378 team. An overlap with the installation engineer is always useful to receive copies of their test results
3379 (magnet shim, manufacturer quality assurance (QA) checks, coil (QA), test tools report, tune up) and
3380 general manufacturer scanner information for future reference.

3381 **MRI Physics Tests/Safety Checks**

3382 The following general safety checks and measurements were performed:

- 3383 • **Fringe field measurements** were recorded at various locations using a 3-Axis Hall
3384 Magnetometer to ensure appropriate control of access to restrict public entry to areas
3385 above the B0 Hazard threshold.
- 3386 • **Acoustic Noise Levels** were measured using a digital sound meter particularly when running
3387 sequences with rapid gradient switching and compared to exposure limits specified in the
3388 Control of Noise at Work Regulations 2005
- 3389 • Display of appropriate **MR Safety Notices** was checked at the entrances to the RF cabin, the
3390 technical room, control room, and for the emergency electrical stop, quench button, and
3391 oxygen monitor
- 3392 • **Quench ventilation** exit point checks to ensure that the cryogen hazard zone would be clear
3393 in the event of a quench, suitable MR Safety notices were displayed and access was
3394 restricted at the exit point to limit entry to the cryogen hazard zone.
- 3395 • **Ancillary Equipment** was labelled appropriately
- 3396 • **Fire extinguishers** within the MR Suite were non-ferromagnetic and appropriately labelled
- 3397 • **Functionality** of the patient intercom, emergency lamp, couch stop, couch release, bore
3398 ventilation, bore CCTV and emergency room ventilation fan.
- 3399 • **The Inventory** was checked against purchase order and the serial numbers of installed coils
3400 recorded.
- 3401 • **Manufacturer's QA tests** results were within specification including: coil QA, RF spikes, shim,
3402 eddy current compensation.
3403

3404 **Medical Physics acceptance testing was performed but is outside the scope of this document.**

3405

3406 **What went well?**

- 3407 • There was good communication throughout the installation between the project
3408 management and the hospital team.
- 3409 • The project team included a wide range of staff groups including external project manager,
3410 Radiology, Estates, MRI Lead Radiographers, Clinical Engineering, MRI Physics, PACS team,
3411 MRI manufacturer, building contractors and the façade company
- 3412 • The project manager was very experienced and organised, meeting minutes were sent out
3413 promptly, and there was a good level of engagement with all relevant parties involved
- 3414 • Ceiling pressure relief panel installations did away with the need and considerable cost of a
3415 scanner room door hatch
3416

3417 **What did not go so well?**

- 3418 • Since the original MR scanner had been installed there had been a lot of building
3419 alterations(internal and external) so the original removal/delivery route was out of the
3420 question.

- 3421
- 3422
- 3423
- 3424
- 3425
- 3426
- 3427
- A relatively new façade had been fitted to the front of the hospital which needed to be removed to allow removal of previous/installation of replacement MR scanner at considerable increased the cost to the project (approx. 70k).
 - The door to the MR Examination room needed to open inwards (not recommended) as the vaulted ceiling soffit outside the scanner room fitted post original MRI installation now obstructed a door opening outwards.

3428 **8.2 Example 2**

3429 This Fly on the Wall account was for an installation which was intended to be a new build (new MRI
3430 and CT scanner) housed in an extension to a community hospital. This was complicated by the fact
3431 that the community hospital was a listed building and there were tight regulations/specifications for
3432 extending the building which weren't compatible with what would make a functioning MR/CT unit.
3433 The new MR/CT units were eventually installed in a relocatable POD while the planning for the
3434 extension to the listed building continued.

3435

3436 This is an example where Medical Physics weren't directly involved with the project and were not
3437 invited to attend meetings. There appeared to be a lack of communication between the project
3438 management, manufacturer, Trust MR Lead, MR radiographers and MRI Physics leading to a MR
3439 relocatable unit which wasn't as ideal as it could have been.

3440 Timelines were as follows:

3441 **November**

3442 Initial plans to replace the current mobile MR scanner with a purpose-built MRI/CT was forwarded to
3443 MRI Physics for comment.

3444

3445 **November - November of following year**

3446 Many issues followed with the design and planning permission for the new build as the hospital
3447 concerned was a listed building.

3448

3449 **December**

3450 Initial designs for permanent building were shared with MRI Physics. Trust MR Lead requested
3451 information on any national guidelines and supporting documentation about proposed plans for the
3452 design.

3453

3454 **December -November of following year**

3455 A decision was made to house the MR and CT in a temporary structure while planning permission
3456 and issues over the extension to the listed building (current community hospital) were resolved.

3457 **November**

- 3458
- 3459
- 3460
- 3461
- 3462
- 3463
- Two possible locations for the relocatable MR scanner were sent to for MRI Physics for review, particularly with reference to the position of high voltage cables from an electrical substation at the back of the preferred carpark.
 - E-mails from the manufacturer to the Trust MR Lead outlined details of the on-site applications training , with the specifics of training to be finalised once the actual dates were released by project management.

3464 **December**

- 3465
- 3466
- MRI Physics were sent the plans for the "temporary" structure which would house the MR scanner until it could be moved into its permanent location.

- 3467
- 3468
- 3469
- 3470
- The project manager and manufacturer had received concerns from the adjacent property (a care home) about noise from the scanner during operation while in its temporary structure.
 - MRI Physics measured the noise outside another similar POD already installed at another local Trust to estimate potential noise pollution.

3471 **January**

3472 The project management team issued the foundation drawings for review and comment to
3473 Radiology Manager and Trust MR Lead. There were recommendations for a trial pit to confirm
3474 ground conditions which required management of disruption to existing car park and list of key
3475 issues that needed clarifying:

- 3476
- 3477
- 3478
- 3479
- 3480
- 3481
- 3482
1. Scope – exactly who is doing what, what pre-work do the Trust need to complete before the install occurs.
 2. Logistics – Site set up areas, crane lift areas and lift plans, sequence, etc.
 3. H&S – Method statements – what do the Trust need to see, who is the principal installation contractor, & is there one or more than one, etc)?
 4. Programme – we need to firm up the attached.

3483 **Mid-January**

3484 The Trust MR Lead sent round questions following a project meeting (which didn't involve MRI
3485 Physics) about additional fixtures, quotes for injectors, [MR Conditional](#) equipment (e.g.
3486 trolley/chair), [MR Conditional](#) fire extinguisher. Queries were raised over scanner noise for the POD.
3487 Dates for applications specialist training were still to be arranged.

3488

3489 MR radiographer's questions/comments:

- 3490
- 3491
- 3492
- 3493
- 3494
- 3495
- 3496
- 3497
- 3498
- 3499
- 3500
- 3501
- 3502
- 3503
1. No need for an [MR Conditional](#) trolley, but a [MR Conditional](#) wheelchair, whilst not essential, would most definitely aid with flow and ensure a swift turnover between patients.
 2. Assume that there is sufficient space to manoeuvre a patient on a trolley, from the reception area, past the toilet doors, and turning 90 degrees to enter the MR prep area?
 3. Coil cupboard is desirable
 4. A wall mounted pump loading system, outside of the scan room will aid flow.
 5. Lockable drugs cabinet required.
 6. A crash trolley shared with CT in reception area
 7. Patient hoist available?
 8. Sluice/macerator shared with CT?
 9. PC and Landline essential

3504 **February**

3505 Exploratory excavations were planned at the site of the permanent extension (with a JCB) which was
3506 near to the current location of a mobile MR scanner. MRI Physics were concerned about level of
3507 vibration and recommend avoiding scanning on the day the closest hole was being dug.

3508

3509 **Early March**

3510 The applications specialist e-mailed the Trust MR Lead with potential dates of mid April for
3511 applications training however there was no access to the scanner for clinical MRI scans before the
3512 end of April due to on-going building work to install a reception pod with walkways and in the
3513 adjacent CT scanner.

3514 **Mid March**

3515 Revised schedule for the installation was issued with suggested dates for Medical Physics acceptance
3516 testing for early April. No Physics involvement in project meetings.

3517

3518 **Early April**

- 3519
- MRI Physics e-mailed the project management team about the expected schedule for the
3520 MRI installation as the Physics acceptance was originally planned for that week but there
3521 had been no confirmation this was going ahead.
 - MRI Physics were informed that manufacturer commissioning had been completed and the
3522 MR scanner was ready for acceptance testing , but an engineer was needed on site as they
3523 had the keys to the unit.
 - More e-mail correspondence followed with project management stating that reception
3524 hasn't been finished and wasn't ready for patients so MRI Physics couldn't do the
3525 acceptance testing There would be an issue getting engineers on site to give MRI Physics
3526 access, so Physics acceptance was booked for mid-April once we explained that no patients
3527 were being scanned during acceptance testing.

3530 The acceptance testing went smoothly on the day, the images analysed, and acceptance report
3531 generated. The MR Local Rules were updated to include the replacement scanner.

3532 MRI Physics requested the following:

- 3533
- A copy of the cage certificate
 - Information on what ventilation measures were in place in case of a Helium leak inside the
3534 scanner room as there didn't appear to be an emergency extraction system hooked into the
3535 O2 monitor
 - Information on handover arrangements
 - Dates for applications specialist training r as MRIPhysics wanted to attend.

3539

3540 **What went well?**

- 3541
- Despite MRI Physics not being invited to project meetings or cc'd in emails there was good
3542 communication between the MRI Radiology/MRI radiographer teams to ensure MRI Physics
3543 were informed and involved
 - Acceptance testing went smoothly

3545 **What did not go so well?**

- 3546
- Project meetings didn't include all staff groups as recommended in the MHRA guidelines to
3547 facilitate a smooth installation
 - There was poor communication between project management, MRI physics, MRI
3548 radiographers and Radiology/Imaging throughout the project.
 - Major issues with plans for MR/CT in extension to existing location as this was a listed
3549 building with strict building regulations. Had to plan for move to temporary POD instead
 - Unforeseen potential vibration issues for the POD which required investigating
 - Unforeseen noise pollution measurements due to POD location next to Care Home.
 - Retrospective design issues included:
 - No room for a trolley in the MR POD apart from in the MR Examination room

3555

- 3556
- 3557
- 3558
- 3559
- 3560
- 3561
- 3562
- 3563
- 3564
- 3565
- 3566
- 3567
- 3568
- 3569
- 3570
- 3571
- Poor patient evacuation route, with the need to open a gate to get a trolley out into a car park
 - Use of semi-private changing area as preparation/cannulation room for patients requiring contrast so only 1 patient in at a time despite having 2 cubicles, s
 - No sink in the changing/preparation area, so staff need to walk past staff in the control room to use the sink for hand washing
 - No room around the sink for mounting soap dispensers/towels, these were located on a wall to the side
 - The Fire panel was located in the technical room and would have been better in the control room for accessibility
 - Two RF doors into the MR Examination room; the one from technical room was unnecessary as there was external access to the technical room
 - MRI Physics acceptance testing scheduling issues included:
 - Lack of communication over acceptance testing dates
 - Access to MRI POD required an engineer to come on site
 - Confusion from project team over acceptance testing involving patient scans

DRAFT

3572 9 References

- 3573 ACR manual on MR Safety (2024), [https://www.acr.org/Clinical-Resources/Radiology-Safety/MR-](https://www.acr.org/Clinical-Resources/Radiology-Safety/MR-Safety)
3574 [Safety](https://www.acr.org/Clinical-Resources/Radiology-Safety/MR-Safety)
- 3575 Anwar et al (2022) Paediatric magnetic resonance imaging adaptations without the use of sedation
3576 or anaesthesia: A narrative review. J Med Imaging Radiat Sci;53(3):505-514. doi:
3577 10.1016/j.jmir.2022.04.048. Epub 2022 May 16.
- 3578 BBC (2025) "Hospital says toy MR scanner helps save £150k",
3579 <https://www.bbc.co.uk/news/articles/c24rlyprqq4o>
- 3580 BIR Risk Assessments, [https://www.bir.org.uk/get-involved/special-interest-groups/bir-magnetic-](https://www.bir.org.uk/get-involved/special-interest-groups/bir-magnetic-resonance/mr-safety-risk-assessments.aspx)
3581 [resonance/mr-safety-risk-assessments.aspx](https://www.bir.org.uk/get-involved/special-interest-groups/bir-magnetic-resonance/mr-safety-risk-assessments.aspx)
- 3582 BS 5266-1 (2025) Emergency lighting - Emergency lighting of premises. Code of practice
- 3583 Carter et al (2010) Mock MRI: reducing the need for anaesthesia in children. Pediatr Radiol.
3584 40(8):1368-74. doi: 10.1007/s00247-010-1554-5. Epub 2010 Feb 26.
- 3585 CIBSE (2019) LG02 Lighting for healthcare premises, [https://www.cibse.org/knowledge-](https://www.cibse.org/knowledge-research/knowledge-portal/lighting-guide-02-lighting-for-healthcare-premises-2019/)
3586 [research/knowledge-portal/lighting-guide-02-lighting-for-healthcare-premises-2019/](https://www.cibse.org/knowledge-research/knowledge-portal/lighting-guide-02-lighting-for-healthcare-premises-2019/)
- 3587 CEMFAW (2016), The Control of Electromagnetic Fields at Work Regulations,
3588 <https://www.legislation.gov.uk/ukxi/2016/588/contents/made>
- 3589 College of Radiographers & Royal College of Radiologists (2024) Quality Standard for Imaging.
3590 <https://www.collegeofradiographers.ac.uk/about-the-college/qs>
- 3591 Heales and Lloyd (2022) Play simulation for children in magnetic resonance imaging. J Med Imaging
3592 Radiat Sci ;53(1):10-16. doi: 10.1016/j.jmir.2021.10.003. Epub 2021 Nov 24.
- 3593 Health Building Note 00-01. General design guidance for healthcare buildings. NHS England (2014).
3594 [https://www.england.nhs.uk/publication/designing-health-and-community-care-](https://www.england.nhs.uk/publication/designing-health-and-community-care-buildings-hbn-00-01/)
3595 [buildings-hbn-00-01/](https://www.england.nhs.uk/publication/designing-health-and-community-care-buildings-hbn-00-01/)
- 3596 Health Building Note 06-01. Facilities for diagnostic imaging and interventional radiology. In
3597 preparation
- 3598 Health Technical Memorandum 00: Policies and principles of healthcare engineering. NHS England
3599 (2014). [https://www.england.nhs.uk/publication/building-engineering-in-the-health-](https://www.england.nhs.uk/publication/building-engineering-in-the-health-sector-hm-00/)
3600 [sector-hm-00/](https://www.england.nhs.uk/publication/building-engineering-in-the-health-sector-hm-00/)
- 3601 Health Technical Memorandum 03-01: Specialised ventilation for healthcare premises. NHS England
3602 (2021). [https://www.england.nhs.uk/publication/specialised-ventilation-for-healthcare-](https://www.england.nhs.uk/publication/specialised-ventilation-for-healthcare-buildings/)
3603 [buildings/](https://www.england.nhs.uk/publication/specialised-ventilation-for-healthcare-buildings/)
- 3604 Health Technical Memorandum 06-01: Electrical services supply and distribution. NHS England
3605 (2017) [https://www.england.nhs.uk/publication/electrical-services-supply-and-](https://www.england.nhs.uk/publication/electrical-services-supply-and-distribution-hm-06-01/)
3606 [distribution-hm-06-01/](https://www.england.nhs.uk/publication/electrical-services-supply-and-distribution-hm-06-01/)
- 3607 Health Technical Memorandum 08-01: Acoustics. NHS England (2013)
3608 [https://www.england.nhs.uk/publication/health-sector-buildings-acoustic-design-](https://www.england.nhs.uk/publication/health-sector-buildings-acoustic-design-requirements-hm-08-01/)
3609 [requirements-hm-08-01/](https://www.england.nhs.uk/publication/health-sector-buildings-acoustic-design-requirements-hm-08-01/)
- 3610 IEC 60601-2-33:2022 Medical electrical equipment - Part 2-33: Particular requirements for the basic
3611 safety and essential performance of magnetic resonance equipment for medical
3612 diagnosis. Reproduced as BS EN ISO 60601-2-33:2024
- 3613 IPEM MR Safety signage (2017), [https://www.ipem.ac.uk/resources/mri/mri-safety-notice-](https://www.ipem.ac.uk/resources/mri/mri-safety-notice-magnetic-resonance-imaging/)
3614 [magnetic-resonance-imaging/](https://www.ipem.ac.uk/resources/mri/mri-safety-notice-magnetic-resonance-imaging/)
- 3615 IPEM Report 112: Quality Control and Artefacts in MRI. IPEM (2017a)
3616

3617 MHRA Safety guidelines for MRI equipment in clinical use (2021).
3618 [https://www.gov.uk/government/publications/safety-guidelines-for-magnetic-](https://www.gov.uk/government/publications/safety-guidelines-for-magnetic-resonance-imaging-equipment-in-clinical-use)
3619 [resonance-imaging-equipment-in-clinical-use](https://www.gov.uk/government/publications/safety-guidelines-for-magnetic-resonance-imaging-equipment-in-clinical-use)

3620 MHRA Managing medical devices (2021a). [https://www.gov.uk/government/publications/managing-](https://www.gov.uk/government/publications/managing-medical-devices)
3621 [medical-devices](https://www.gov.uk/government/publications/managing-medical-devices)

3622 Moelker A et al (2003). Efficacy of passive acoustic screening: implications for the design of imager
3623 and MR-suite. JMRI Feb;17(2):270-5. doi: 10.1002/jmri.10251.

3624 Mullally S (2013) A toolkit for medical equipment donations to low-resource settings: making It
3625 work. Global Health Partnerships.
3626 [https://www.globalhealthpartnerships.org/resources/making-work-toolkit-medical-](https://www.globalhealthpartnerships.org/resources/making-work-toolkit-medical-equipment-donations/)
3627 [equipment-donations/](https://www.globalhealthpartnerships.org/resources/making-work-toolkit-medical-equipment-donations/)

3628 NHS England (2023) Processes for managing and reporting derogations from estates technical
3629 standards and guidance. [https://www.england.nhs.uk/publication/processes-for-](https://www.england.nhs.uk/publication/processes-for-managing-and-reporting-derogations-from-estates-technical-standards-and-guidance/)
3630 [managing-and-reporting-derogations-from-estates-technical-standards-and-guidance/](https://www.england.nhs.uk/publication/processes-for-managing-and-reporting-derogations-from-estates-technical-standards-and-guidance/)

3631 NHS Supply chain (2025) [https://www.supplychain.nhs.uk/product-information/contract-launch-](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/?utm_source=magnetic-resonance-imaging-scanners-and-associated-option-and-related-services)
3632 [brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/?utm_source=magnetic-resonance-imaging-scanners-and-associated-option-and-related-services)
3633 [services/?utm_source=magnetic-resonance-imaging-scanners-and-associated-option-](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/?utm_source=magnetic-resonance-imaging-scanners-and-associated-option-and-related-services)
3634 [and-related-services](https://www.supplychain.nhs.uk/product-information/contract-launch-brief/magnetic-resonance-imaging-scanners-and-associated-option-and-related-services/?utm_source=magnetic-resonance-imaging-scanners-and-associated-option-and-related-services)

3635 Recht P et al (2019), Optimization of MRI Turnaround Times Through the Use of Dockable Tables and
3636 Innovative Architectural Design Strategies. AJR Am J Roentgenol. Apr;212(4):855-858.
3637 doi: 10.2214/AJR.18.20459

3638 Patients Association (2024), [https://www.patients-association.org.uk/blog/how-can-patient-](https://www.patients-association.org.uk/blog/how-can-patient-experience-of-diagnostic-services-be-improved)
3639 [experience-of-diagnostic-services-be-improved](https://www.patients-association.org.uk/blog/how-can-patient-experience-of-diagnostic-services-be-improved)

3640 PSSR (2000), <https://www.legislation.gov.uk/ukxi/2000/128/contents/made>

3641 Quality Standard for Imaging (2024), [https://www.rcr.ac.uk/our-services/management-service-](https://www.rcr.ac.uk/our-services/management-service-delivery/quality-standard-for-imaging-qs/)
3642 [delivery/quality-standard-for-imaging-qs/](https://www.rcr.ac.uk/our-services/management-service-delivery/quality-standard-for-imaging-qs/)

3643 RIBA (2020) Plan of work. [https://www.architecture.com/knowledge-and-resources/resources-](https://www.architecture.com/knowledge-and-resources/resources-landing-page/riba-plan-of-work)
3644 [landing-page/riba-plan-of-work](https://www.architecture.com/knowledge-and-resources/resources-landing-page/riba-plan-of-work)

3645 Small et al (2026) MRI faraday cage performance during the lifetime of clinical MR systems. MAGMA
3646 doi: 10.1007/s10334-025-01321-8

3647 Society of Radiographers & British Associated of Magnetic Resonance Radiographers (2019) Safety in
3648 Magnetic Resonance. [https://www.sor.org/learning-advice/professional-body-guidance-](https://www.sor.org/learning-advice/professional-body-guidance-and-publications/documents-and-publications/policy-guidance-document-library/safety-in-magnetic-resonance-imaging)
3649 [and-publications/documents-and-publications/policy-guidance-document-library/safety-](https://www.sor.org/learning-advice/professional-body-guidance-and-publications/documents-and-publications/policy-guidance-document-library/safety-in-magnetic-resonance-imaging)
3650 [in-magnetic-resonance-imaging](https://www.sor.org/learning-advice/professional-body-guidance-and-publications/documents-and-publications/policy-guidance-document-library/safety-in-magnetic-resonance-imaging)

3651 Society of Radiographers. Various guidance associated with MRI, [https://www.sor.org/Learning-](https://www.sor.org/Learning-advice/Professional-body-guidance-and-publications/Documents-and-publications/Policy-Guidance-Documents-Library?searchTerm=mri)
3652 [advice/Professional-body-guidance-and-publications/Documents-and-](https://www.sor.org/Learning-advice/Professional-body-guidance-and-publications/Documents-and-publications/Policy-Guidance-Documents-Library?searchTerm=mri)
3653 [publications/Policy-Guidance-Documents-Library?searchTerm=mri](https://www.sor.org/Learning-advice/Professional-body-guidance-and-publications/Documents-and-publications/Policy-Guidance-Documents-Library?searchTerm=mri)

3654 Steckner et al (2024) Transitioning from 0.5 to 0.9 mT: Protecting against inadvertent activation of
3655 magnet mode in active implants. Magn Reson Med. 2024 Nov;92(5):2237-2245. doi:
3656 10.1002/mrm.30153. Epub 2024 Jul 5.

3657 Steckner et al (2026) Commentary: The MR scanner room door is a latent safety issue. MAGMA. doi:
3658 10.1007/s10334-025-01310-x

3659 Stunden et al (2021) Comparing a Virtual Reality-Based Simulation App (VR-MRI) With a Standard
3660 Preparatory Manual and Child Life Program for Improving Success and Reducing Anxiety
3661 During Pediatric Medical Imaging: Randomized Clinical Trial. J Med Internet Res
3662 23(9):e22942. doi: 10.2196/22942.

3663 UK Health Security Agency (2024) National coding taxonomy for incident learning in clinical imaging,
3664 MRI and nuclear medicine. [https://www.gov.uk/government/publications/national-](https://www.gov.uk/government/publications/national-coding-taxonomy-for-incident-learning-in-clinical-imaging-mri-and-nuclear-medicine)
3665 [coding-taxonomy-for-incident-learning-in-clinical-imaging-mri-and-nuclear-medicine](https://www.gov.uk/government/publications/national-coding-taxonomy-for-incident-learning-in-clinical-imaging-mri-and-nuclear-medicine)

3666 Wilson et al (2019) Guidelines for the safe provision of anaesthesia in magnetic resonance units
3667 2019: Guidelines from the Association of Anaesthetists and the Neuro Anaesthesia and
3668 Critical Care Society of Great Britain and Ireland. *Anaesthesia* 74(5):638-650. doi:
3669 10.1111/anae.14578.
3670
3671

DRAFT